

# OLYMPIA REGION CLEAN AIR AGENCY

2940 Limited Lane NW - Olympia, Washington 98502 - 360-539-1610 – Fax 360-491-6308

## FORM 1- NOTICE OF CONSTRUCTION TO CONSTRUCT - INSTALL - ESTABLISH OR MODIFY AN AIR CONTAMINANT SOURCE

**Form 1 Instructions:**

1. Please complete all the fields below. **This NOC application is considered incomplete until signed.**
2. If the application contains any confidential business information, please complete a Request of Confidentiality of Records ([www.orcaa.org/forms](http://www.orcaa.org/forms)).
3. Duty to Correction Application: An applicant has the duty to supplement or correct an application. Any applicant who fails to submit any relevant facts or who has submitted incorrect information in a permit application must, upon becoming aware of such failure or incorrect submittal, promptly submit supplementary factors or corrected information.

Business Name: <div style="font-size: 1.2em; color: blue;">Spencer Manufacturing</div>	<b>For ORCAA use only</b> File No: 670 County No: 67 Source No: 963 Application No: 24NOC1642
Mailing Address: <div style="font-size: 1.2em; color: blue;">PO Box 8379 Covington WA 98042</div>	Date Received: <div style="color: red; font-weight: bold; font-size: 1.1em;">Received MAR 18 2024  ORCAA</div>
Physical Address of Project or New Source: <div style="font-size: 1.2em; color: blue;">2757 29<sup>th</sup> Ave SW Tumwater, WA 98512</div>	
Billing Address: <div style="font-size: 1.2em; color: blue;">PO Box 8379 Covington, WA 98042</div>	
Project or Equipment to be installed/established: <div style="font-size: 1.5em; color: blue; margin-top: 10px;">Paint Booth</div>	
Anticipated startup date: ___/___/___ Is facility currently registered with ORCAA? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
This project must meet the requirements of the State Environmental Policy Act (SEPA) before ORCAA can issue final approval. Indicate the SEPA compliance option: <input type="checkbox"/> SEPA was satisfied by _____ (government agency) on ___/___/___ (date) - Include a copy of the SEPA determination <input type="checkbox"/> SEPA threshold determination by _____ (government agency) is pending - Include a copy of the environmental checklist <input checked="" type="checkbox"/> ORCAA is the only government agency requiring a permit - Include ORCAA Environmental Checklist <input type="checkbox"/> This project is exempt from SEPA per _____ (WAC citation).	
Name of Owner of Business: <div style="font-size: 1.2em; color: blue;">Gary Zukowski</div>	Agency Use Only
Title: <div style="font-size: 1.2em; color: blue;">President</div>	
Email: <div style="font-size: 1.2em; color: blue;">Gary@spencer-manufacturing.com</div>	Phone: <div style="font-size: 1.2em; color: blue;">253-833-2122</div>
Authorized Representative for Application (if different than owner): <div style="font-size: 1.2em; color: blue;">Brandon McClintic</div>	
Title: <div style="font-size: 1.2em; color: blue;">Operations Manager</div>	
Email: <div style="font-size: 1.2em; color: blue;">Bj@spencer-manufacturing.com</div>	Phone: <div style="font-size: 1.2em; color: blue;">253-833-2122</div>
I hereby certify that the information contained in this application is, to the best of my knowledge, complete and correct.	
Signature of Owner or Authorized Representative: (sign in Blue Ink)	
<div style="font-size: 1.5em; color: blue; font-family: cursive;">Branda McClintic</div>	Date: <div style="font-size: 1.2em; color: blue;">3-14-24</div>
<b>IMPORTANT:</b> Do not send via email or other electronic means. ORCAA must receive Original, hardcopy, signed application and payment prior to processing application.	

# OLYMPIC REGION CLEAN AIR AGENCY

2940 Limited Lane NW - Olympia, Washington 98502 - 360-539-7610 – Fax 360-491-6308

## FORM 1D- Contact Information

<b>Business Name</b>	<b>FOR ORCAA USE</b>
Spencer Manufacturing	<b>FILE #</b> 670
<b>Physical Site Address (Street address, city, state, zip)</b> 2757 29th Ave SW Tumwater, WA 98512	<b>CTY #</b> 67
	<b>SRC #</b> 963
<b>Previous Business Name (if applicable)</b>	<b>Date Received</b> Received MAR 18 2024
	ORCAA

### Contact Information

<b>Inspection Contact</b>	
Name Brandon McClinton	Title Operations Manager
Phone <del>360</del> 253-833-2122	Email BJ@spencer-manufacturing.com
<b>Billing Contact</b>	
Name Karin Zukowski	Title VP / Accountant
Phone 253-833-2122	Email Karin@spencer-manufacturing.com
<b>Emission Inventory Contact</b>	
Name SAME AS #1	Title
Phone	Email
<b>Complaint Contact</b>	
Name SAME AS #1	Title
Phone	Email
<b>Permit Contact</b>	
Name SAME AS #1	Title
Phone	Email

The **inspection contact** is the on-site person responsible for the everyday operation of the site and is available for inspections.

The **billing contact** is the person invoices are sent.

The **emission inventory contact** is the person requests for emissions information and material use information are sent.

The **complaint contact** is the person who receives and responds to complaints received on-site and who is contacted regarding complaints ORCAA receives.

The **permit contact** is the person responsible for filling out permit applications and receiving approval from ORCAA.

### Heavy Metal Information

Application of coatings containing compounds of chromium (Cr), lead (Pb), manganese (Mn), nickel (Ni), or cadmium (Cd):	<input type="checkbox"/> Yes** <input checked="" type="checkbox"/> No
---	---

\*\*Please provide SDS/ MSDS information and estimated annual usage for each product

### Other Process Information

Abrasive Blasting:	<input type="checkbox"/> Yes (Form 17) <input checked="" type="checkbox"/> No
Welding:	<input type="checkbox"/> Yes (Form 19) <input type="checkbox"/> No
Metal Cutting:	<input type="checkbox"/> Yes (Form 31) <input type="checkbox"/> No
Fluidized Bed Coating:	<input type="checkbox"/> Yes <input type="checkbox"/> No

### Cleaning/Etching/Degreasing Information

Methylene Chloride Stripping:	<input type="checkbox"/> Yes** <input checked="" type="checkbox"/> No
Phosphate or Chromate Conversion Coating:	<input type="checkbox"/> Yes** <input checked="" type="checkbox"/> No
Chemical/Acid Rinsing or Bathing:	<input type="checkbox"/> Yes** <input checked="" type="checkbox"/> No

\*\*Please provide SDS/ MSDS information and estimated annual usage for each product

### Exhaust/Stack/Building Information

Motor Power (hp):	2 HP	
Exhaust Air Flow Rate at 0.65" w.g. (acfm):	14,000 CFM	
Fan Diameter (feet):	2.25	
Stack Type:	<input checked="" type="checkbox"/> Vertical (Ceiling Outlet)	<input type="checkbox"/> Horizontal (Wall Outlet)
Stack Height (feet from ground):	26 ft	
Stack Inside Diameter (inches):	25.5	
Stack weatherproof damper or exhaust apparatus:	<input type="checkbox"/> None <input type="checkbox"/> Hexagonal <input type="checkbox"/> Stack within stack	<input checked="" type="checkbox"/> Butterfly <input type="checkbox"/> Inverted cone <input type="checkbox"/> Other (explain in attachment)
Bldg. Peak Height (feet):	20 ft	
Bldg. Width (feet):	100 ft	
Bldg. Length (feet)	200 ft	

### Air Quality Modeling Site Information

Distance from the centroid of the stack to the shop's property line (feet):	SEE SITE plan CI
Distance from the centroid of the stack to the nearest point on the property line of a permanent residence (feet):	NONE THAT I CAN SEE

### Filing Fee:

See <https://www.orcaa.org/services/fee-schedules/> for an up-to-date list of fees



# OLYMPIC REGION CLEAN AIR AGENCY

2940 Limited Lane NW - Olympia, Washington 98502

Telephone: (360)-539-7610 – Fax: (360)-491-6308

[www.orcaa.org](http://www.orcaa.org)

## FORM 8

Fill out all the applicable equipment information requested below and submit the appropriate fees.

### SPRAY COATING (Autobody) SURFACE COATING (Aviation, Wood, Boat, Other)

#### Shop Information

Business Name: <i>Spencer Manufacturing</i>	Contact Person: <i>Brandon McClintic</i>
	Phone Number: <i>253-833-2122</i>
	Email: <i>BJ@Spencer-Manufacturing.com</i>
Operating Schedule: <i>10</i> hrs/day, <i>4</i> days/wk,      wks/yr	Indicate days when operating: <input checked="" type="checkbox"/> M <input checked="" type="checkbox"/> T <input checked="" type="checkbox"/> W <input checked="" type="checkbox"/> Thu <input type="checkbox"/> F <input type="checkbox"/> Sat <input type="checkbox"/> Sun

#### Process Information

Flow:	<input type="checkbox"/> Cross front flow <input type="checkbox"/> Full downdraft <input checked="" type="checkbox"/> Side downdraft <input type="checkbox"/> Combination <input type="checkbox"/> Cross reverse flow <input type="checkbox"/> Semi-downdraft <input type="checkbox"/> Updraft <input type="checkbox"/> Other (explain in attachment)
Exhaust:	<input type="checkbox"/> Side Wall <input type="checkbox"/> Pit/Trench Design <input checked="" type="checkbox"/> Ceiling <input type="checkbox"/> Rear Wall <input type="checkbox"/> Front/Doors
Intake Type:	<input type="checkbox"/> Natural <input checked="" type="checkbox"/> Forced (air make-up unit)
Enclosure Type:	<input checked="" type="checkbox"/> Fully enclosed <input type="checkbox"/> Compact/modular <input type="checkbox"/> Open table/bench <input type="checkbox"/> Closed top open front (CTOF) <input type="checkbox"/> Curtain/tent/drape <input type="checkbox"/> Other (explain in attachment) <input type="checkbox"/> Tunnel
Width (feet): <i>14</i>	Length (feet): <i>24</i> Height (feet): <i>10</i>
Manufacturer:	<i>AFC</i>
Model Number:	<i>CP-3D</i>
Serial Number:	<i>02-0998</i>
Pressure Gauge:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No              Filter Plenum: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Intended Applicator Usage (see next section):	<input checked="" type="checkbox"/> Applicator #1 <input type="checkbox"/> Applicator #3 <input type="checkbox"/> Applicator #5 <input type="checkbox"/> Applicator #2 <input type="checkbox"/> Applicator #4
Air Pollution Control Methods:	<input type="checkbox"/> Water Wash <input checked="" type="checkbox"/> Low VOC coatings <input type="checkbox"/> Cartridge unit (Form 12) <input type="checkbox"/> Scrubber <input type="checkbox"/> Cyclone (Form 13) <input type="checkbox"/> Enclosed spray gun cleaner <input type="checkbox"/> Oxidizer (Form 35) <input type="checkbox"/> Baghouse (Form 12)
<b>Heater/Curing Information (if applicable)</b>	
Heater Placement:	<input checked="" type="checkbox"/> Part of spray booth unit <input type="checkbox"/> Separate curing enclosure (Form 11)
Curing/Heating Type :	<input checked="" type="checkbox"/> Hot air dryer <input type="checkbox"/> Infrared dryer <input type="checkbox"/> Other (explain in attachment) <input type="checkbox"/> Ultraviolet <input type="checkbox"/> Boiler
Fuel/Heat Type :	<input checked="" type="checkbox"/> Natural gas <input type="checkbox"/> Electric <input type="checkbox"/> Other (explain in attachment) <input type="checkbox"/> Propane (LP) Gas <input type="checkbox"/> Diesel
Maximum Heating Rate (MMBtu/hr):	<i>1,075,000 BTU (1.075 MBit)</i>
Maximum Air Flow Rate (acfm):	<del><i>14,000</i></del> <i>CFM 7"</i>

### Coating Operation Information

Type:	<input checked="" type="checkbox"/> Existing Stationary Source	<input type="checkbox"/> Temporary Source	<input type="checkbox"/> New Stationary Source
NAICS Code(s):			

### Coating Equipment Information

	Applicator #1	Applicator #2	Applicator #3	Applicator #4	Applicator #5	
Coating Type**:	<input type="checkbox"/> Brush/Roller <input type="checkbox"/> Web <input checked="" type="checkbox"/> Wet spray <input type="checkbox"/> Deposition <input type="checkbox"/> Powder <input type="checkbox"/> Plating	<input type="checkbox"/> Brush/Roller <input type="checkbox"/> Web <input checked="" type="checkbox"/> Wet spray <input type="checkbox"/> Deposition <input type="checkbox"/> Powder <input type="checkbox"/> Plating	<input type="checkbox"/> Brush/Roller <input type="checkbox"/> Web <input type="checkbox"/> Wet spray <input type="checkbox"/> Deposition <input type="checkbox"/> Powder <input type="checkbox"/> Plating	<input type="checkbox"/> Brush/Roller <input type="checkbox"/> Web <input type="checkbox"/> Wet spray <input type="checkbox"/> Deposition <input type="checkbox"/> Powder <input type="checkbox"/> Plating	<input type="checkbox"/> Brush/Roller <input type="checkbox"/> Web <input type="checkbox"/> Wet spray <input type="checkbox"/> Deposition <input type="checkbox"/> Powder <input type="checkbox"/> Plating	<input type="checkbox"/> Brush/Roller <input type="checkbox"/> Web <input type="checkbox"/> Wet spray <input type="checkbox"/> Deposition <input type="checkbox"/> Powder <input type="checkbox"/> Plating
Manufacturer:	SATA	SATA	Sherrill Williams	Emerald		
Model:			See Att.	See Att.		
Quantity:	1	1				
Technology Type:	<input checked="" type="checkbox"/> HVLP <input type="checkbox"/> Electrostatic <input type="checkbox"/> Air-assisted airless <input type="checkbox"/> Airless <input type="checkbox"/> Air spray <input type="checkbox"/> Rotary cup <input type="checkbox"/> Airbrush <input type="checkbox"/> Other (explain in attachment)	<input checked="" type="checkbox"/> HVLP <input type="checkbox"/> Electrostatic <input type="checkbox"/> Air-assisted airless <input type="checkbox"/> Airless <input type="checkbox"/> Air spray <input type="checkbox"/> Rotary cup <input type="checkbox"/> Airbrush <input type="checkbox"/> Other (explain in attachment)	<input type="checkbox"/> HVLP <input type="checkbox"/> Electrostatic <input type="checkbox"/> Air-assisted airless <input type="checkbox"/> Airless <input type="checkbox"/> Air spray <input type="checkbox"/> Rotary cup <input type="checkbox"/> Airbrush <input checked="" type="checkbox"/> Other (explain in attachment)	<input type="checkbox"/> HVLP <input type="checkbox"/> Electrostatic <input type="checkbox"/> Air-assisted airless <input type="checkbox"/> Airless <input type="checkbox"/> Air spray <input type="checkbox"/> Rotary cup <input type="checkbox"/> Airbrush <input checked="" type="checkbox"/> Other (explain in attachment)	<input type="checkbox"/> HVLP <input type="checkbox"/> Electrostatic <input type="checkbox"/> Air-assisted airless <input type="checkbox"/> Airless <input type="checkbox"/> Air spray <input type="checkbox"/> Rotary cup <input type="checkbox"/> Airbrush <input type="checkbox"/> Other (explain in attachment)	
Automation/Control:	<input checked="" type="checkbox"/> Manual <input type="checkbox"/> Automatic	<input checked="" type="checkbox"/> Manual <input type="checkbox"/> Automatic	<input type="checkbox"/> Manual <input type="checkbox"/> Automatic	<input type="checkbox"/> Manual <input type="checkbox"/> Automatic	<input type="checkbox"/> Manual <input type="checkbox"/> Automatic	
Air Supply Pressure (psi):			N/A	N/A		
Fluid Output Pressure (psi):			N/A	N/A		
Mounting:	<input checked="" type="checkbox"/> Handheld Gun <input type="checkbox"/> Machine/Reciprocator	<input checked="" type="checkbox"/> Handheld Gun <input type="checkbox"/> Machine/Reciprocator	<input type="checkbox"/> Handheld Gun <input type="checkbox"/> Machine/Reciprocator	<input type="checkbox"/> Handheld Gun <input type="checkbox"/> Machine/Reciprocator	<input type="checkbox"/> Handheld Gun <input type="checkbox"/> Machine/Reciprocator	

\*\*Only provide further information for applicators that are not roller/brush

### Dry Filter Information

	Pre-Filter	Exhaust Filter
Manufacturer:	Please see	
Model:		
Media Type:	Attached	
Overall Arrest Efficiency (%):		
Filtered Area (squared feet):		

### Material Usage Information

Provide the following information and attach copies of Material Safety Data Sheets (MSDS) used in all coating operations, including but not limited to pre-treatment wash, chemical strippers, paint, primer, topcoat, clearcoat, gelcoat, lacquer, stain, catalyst, activator, hardener, resin, filler, sealer, adhesive, solvent and thinner/reducer and any other materials used which contain volatile organic compounds (VOC). Use additional pages if necessary. For similar materials such as multiple color variations of a stain or paint, enter as single item with a usage rate representing the total gallons of all variations used, and provide the MSDS for the constituent which is most used.

NAME OF MATERIAL (as on SDS/ MSDS):	ESTIMATED ANNUAL USAGE (in gallons):	Applicator # ( as defined in the "Coating Equipment Information" section):
Genesis Reducer R7K7210	2 gal	#1
3.5Voc Epoxy primer E2A933	10 gal	#1
Epoxy Primer Activator V6V943	2.5 gal	#1
Ultra Clean Surface cleaner <sup>R7K158</sup>	1 gal	#3
1093/96 hardner	4.25 gal	#2
G2 series paint	9 gal	#2
LV series paint	2.5 gal	#2
Lacquer thinner	110 gal	#4

# Notice of Construction (NOC) Fee Schedule

Effective July 1, 2023

## NOC Fees - ORCAA Rule 3.3(a)

	Filing Fee
+	Additional NOC Processing Fees
+	<u>Other Costs</u>
	NOC Fee

## Filing Fee - ORCAA Rule 3.3(b)

	Complexity Fee
+	<u>Equipment Fee(s)</u> (for each piece of equipment, unless they are identical per 3.3(b)(2))
	Filing Fee

## Complexity Fee

Complexity Level 1	\$ 1279
Complexity Level 2 <sup>1</sup>	\$ 2560
Complexity Level 3 <sup>1</sup>	\$ 4281
Complexity Level 4 <sup>1</sup>	\$ 10358

## Equipment Fee

Equipment/Activity	Fee	Base-Fee Hours
Abrasive Blasting	\$ 491	5
Asphalt Plant	\$ 3639	37
<i>Combustion Equipment not otherwise listed (Million Btu/hr heat input at design capacity)</i>		
Less than 10	\$ 1180	12
10 or more but less than 30	\$ 1279	13
30 or more but less than 100	\$ 2557	26
More than 100	\$ 6886	70
Temporary Combustion Equipment (Onsite < 1 year)	One half the filing fee	One half the base-fee hours
Coffee Roaster	\$ 688	7
<i>Composting Operation (Average material throughput – tons per day)</i>		
Less than 50	\$ 1279	13
50 or more but less than 200	\$ 2262	23
More than 200	\$ 3345	34
Concrete Batch Plant	\$ 1967	20
Crematory	\$ 1082	11
Dry Cleaner (per machine)	\$ 688	7
Dry Kilns	\$ 1279	13
Emergency Engine – cumulative horsepower < 2000 bhp	\$ 885	9
Emergency Engine -cumulative horsepower ≥ 2000 bhp	\$ 1770	18
Non-Emergency Engine (per engine)	\$ 1279	13
Gasoline Dispensing Station	\$ 688	7
Log yard	\$ 688	7

Printing	\$ 688	7
Process Equipment ≤20,000 cubic feet per minute at design capacity	\$ 984	10
Rock Crushing Plant – includes General Order	\$ 491	5
Soil Remediation	\$ 1279	13
Spray Painting – Autobody (per operation/booth)	\$ 786	8
Surface Coating – Aviation, Wood, Truck Bed Lining, Boat, Other (per operation/booth)	\$ 1378	14
Storage Tanks ≤10,000-gallon total capacity (other than at retail gasoline dispensing stations)	\$ 885	9
Wastewater Treatment Plant	\$ 2065	21
Welding	\$ 984	10
Other Equipment not listed above - Small <sup>2</sup>	\$ 491	5
Other Equipment not listed above - Medium <sup>2</sup>	\$ 1377	14
Other Equipment not listed above - Large <sup>2</sup>	\$ 3345	34
In-Kind Replacements –Replacement of equipment with a unit of same or smaller size and combusting the same or cleaner fuel (if applicable). This fee reduction does not apply to asphalt plants, combustion equipment >30 MMBtu/hr, or other replacements at the discretion of the Executive Director.	One half the applicable filing fee	One half the associated base-fee hours

### Control Device Replacement/Change in Conditions (No Complexity Fee)

Equipment/Activity	Fee	Base-Fee Hours
Control Device Replacement per ORCAA Rule 6.1.10 NOC	\$ 786	8
Change in Conditions per ORCAA Rule 6.1.11 <sup>4</sup> NOC	\$ 688	7

### Additional NOC Processing Fees - ORCAA Rule 3.3(c)

Additional NOC Processing fees, including work that exceeds the base-fee hours, will be billed at the following hourly rate as specified in ORCAA Rule 3.3(d).

Hourly Rate	\$ 98.36
-------------	----------

### Other Costs - ORCAA Rule 3.3(d)

Publishing and consulting costs incurred will be billed to the applicant as specified in ORCAA Rule 3.3(d).

### Variance per ORCAA Rule 2.3, Compliance Schedule per ORCAA Rule 2.6(f), or Restricting the Potential to Emit per ORCAA Rule 5.3 (SMO)

Fees	Fee	Base-Fee Hours
Filing Fee	\$ 1377	14
Add'l processing costs above allowed hours – per hour	\$ 98.36	
Actual legal notice fees	Actual cost	
Actual ORCAA legal fees	Actual cost	

#### <sup>1</sup>Complexity – Level 1, Level 2, Level 3 and Level 4

The following includes equipment that would be considered in each permit complexity class if installed by themselves. If the application includes more than one piece of equipment/process or if your equipment/process is not listed, please contact ORCAA Engineering Department for a complexity determination for your project.





To Whom It May Concern:

The *AMS-1000* heat systems requires **1075 cubic feet per hour** of natural gas with a minimum pressure flow rate of **7 inches of water column pressure**. It is imperative that we maintain a minimum of 7 inches of water column pressure (measured at the ball cock valve) at the **full fire rate** of **1075 MBH**, which equates to 1,075,000 BTU's.

**CAUTION:** Gas pressure above **14 inches of water column pressure** at the burner may damage the standard regulator. In the event of excessive gas pipe runs or multiple appliances, we recommend a medium pressure gas supply from the service to the burner with a primary regulator that will drop pressure at the burner from medium pressure to 14 inches of water column pressure.

For additional information, please refer to page JA1, *Capacities and Specifications*, paragraph 2, model number J30A-10 and page JA3 (*Gas Piping*).


If you have any further questions or concerns, please contact the technical department at the toll free number listed below. Thank you.

AFC, Inc.  
250 Airport Parkway  
Oroville, CA 95965

Phone: 800-331-7744  
Fax: 530-533-0179  
E-Mail: Sales@afc-ca.com

*"Built in America - Supported with Integrity"*  
Quality Products Since 1967  
www.afc-ca.com

SPENCER MANUFACTURING  
 2757 29TH AVE SW  
 TUMWATER, WA 98512  
 PARCEL NO. 63050002400



GENERAL CODE COMPLIANCE

SITE DATA	
SITE AREA	3.17 AC
ZONING	I1 LIGHT INDUSTRIAL
OCCUPANCY	B, F, I, S 1
CONSTRUCTION	II-B
SETRACKS (REQUIRED)	
FRONT	20'
SIDE	10'
REAR	10'
SETRACKS (PROVIDED)	
FRONT	216' WEST
SIDE	220' NORTH
SIDE	35' SOUTH
REAR	10' EAST
BUILDING AREA	12,000 SF

TENANT/OWNER INFORMATION

SPENCER MANUFACTURING  
 C/O MR. GARY ZUKOWSKI  
 7050 SOUTH 188TH  
 KENT, WA 98032  
 PH. (425) 251-5050

PARCEL NUMBER  
 63050002400

NOTE

THESE PLANS HAVE BEEN CREATED TO DETAIL A PAINT BOOTH INSTALLATION WITHIN BUILDING C OF THE ABOVE PARCEL. ALL OTHER ASPECTS OF THE PLAN ARE CONSIDERED "EXISTING" AND CONSTRUCTED UNDER A SEPARATE PERMIT.



SHEET NUMBER	SHEET TITLE	SHEET DESCRIPTION
1	C1	SITE PLAN
2	A1	FIRST FLOOR PLAN WITH DIMENSIONS
3	A2	ELEVATIONS
4	S1	PARTIAL ROOF PLAN
5	M1	

A SITE PLAN  
 C1 SCALE 1" = 40'

FILE Spencer\_Struct.dwg

PROJECT: ENTER JOB TITLE FROM TIMESHEET

CHECKED BY: RLM  
 DETAILED BY: RLM  
 DESIGNED BY: RLM

DATE NO. REVISION BY



2724 Black Lake Boulevard SW Suite 202  
 Tumwater, WA 98512  
 ph: (360) 352-2477 fax: (360) 352-0179 E-mail: adm@vectorengineeringinc.com

SPENCER SPRAY BOOTH  
 2757 29TH AVE SW  
 TUMWATER, WA 98512

C1

SPENCER MANUFACTURING  
 2757 29TH AVE SW  
 TUMWATER, WA 98512

SITE PLAN

SHT 1 OF 5

# AIR FILTER TESTING LABORATORIES, INC.

4032 OLD LA GRANGE ROAD | CRESTWOOD, KENTUCKY 40014

PHONE | FAX (502)222-5720

REPORT NO. 8269 TEST NO. 4 SHEET NO. 5


## ASHRAE METHOD 52.1-1992 AIRFLOW -VS- RESISTANCE AND INITIAL SILICA DIOXIDE DUST FRACTION REMOVAL EFFICIENCY; CLEAN DEVICE

TEST REQUESTED BY	AIR FILTRATION CO., INC.
MANUFACTURER	AIR FILTRATION CO., INC.
HOW AFTL PROCURED TEST SAMPLE	FURNISHED BY MANUFACTURER
PRODUCT NAME	LAMINAR III
MODEL NO.	L2424
DIMENSIONS	24 IN. H      24 IN. W      1 IN. D
PRODUCT DESCRIPTION	MEDIA TYPE - NON-WOVEN POLYESTER
	MEDIA AREA - 4.0 FT <sup>2</sup>
	ADHESIVE - WATER BASED TACKIFIER

TEST AIR FLOW RATE (CFM)	(100 FPM)	400
SILICA DIOXIDE DUST FRACTION (5 - 10 $\mu$ M) INCREMENT (g)		30
INITIAL SILICA DIOXIDE DUST FRACTION (5 - 10 $\mu$ M) REMOVAL EFFICIENCY (%)		98.3

### CLEAN DEVICE

AIRFLOW -VS- RESISTANCE




DATE  
TEST SUPERVISOR  
ENGINEERING APPROVAL

11-14-1994

J.P.S.

*David J. Murphy Jr.*



# AIR FILTER TESTING LABORATORIES, INC.

4632 Old LaGrange Road Crestwood, Kentucky 40014

REPORT NO. 6269 TEST NO. 1

## PAINT ARRESTOR FILTER PERFORMANCE TEST REMOVAL EFFICIENCY AND PAINT HOLDING CAPACITY

### DEVICE TESTED

TEST REQUESTED BY SUPERIOR GLASS FIBERS, INC.  
MANUFACTURER SUPERIOR GLASS FIBERS, INC.  
PRODUCT NAME GLASS FIBER PAINT ARRESTOR PAD  
HOW LABORATORY PROCURED TEST SAMPLE FURNISHED BY MANUFACTURER  
MODEL NO. TGT 25-250-14-2-2-00  
DIMENSIONS 20 IN. H 20 IN. W 2 1/2 IN. D  
PRODUCT DESCRIPTION: GLASS FIBER PAD - 14 GRAM GTO PA PA+GA

### TEST CONDITIONS

AIRFLOW RATE 

150	FPM
1	QT/40 MIN
70-80	DEGREE F

  
PAINT APPLICATION RATE  
AIR TEMPERATURE  
DESCRIPTION OF PAINT USED AIR DRY SYNTHETIC ENAMEL

### TEST RESULTS

INITIAL RESISTANCE CLEAN PAINT ARRESTOR FILTER 


0.03	IN. W.G.
1413.5	GRAMS
78.34	GRAMS
1491.84	GRAMS
1.00	IN. W.G.
94.0	%
2.22	POUNDS

  
WEIGHT GAIN PAINT ARRESTOR FILTER  
FINAL ARRESTANCE FILTERS WEIGHT GAIN  
TOTAL WEIGHT PAINT FED (DRY BASES)  
PERFORMANCE TO CHANGE OUT RESISTANCE  
AVERAGE PAINT OVER SPRAY REMOVAL EFFICIENCY  
PAINT HOLDING CAPACITY 

1005	GRAMS
------	-------

 OR

DATES OF TEST 8-16-1991  
TEST SUPERVISOR W.T.S.  
ENGINEERING APPROVAL David J. Murphy Jr.



# **S** **SPENCER** **MANUFACTURING** A Division of Veritas Industries, Inc

**Application # 3 Sherwin Williams R7K158 surface cleaner is applied to painted surface using a rag.**

**Application # 4 Emerald lacquer thinner is used to clean spray equipment.**

# SAFETY DATA SHEET

GENESIS® REDUCER COMPLIANT SOLVENT

Medium

R7K7210

## Section 1. Identification

Product identifier : GENESIS® REDUCER COMPLIANT SOLVENT  
Medium  
Product code : R7K7210  
Product type : Liquid.

### Relevant identified uses of the substance or mixture and uses advised against

Material uses : Paint or paint related material.  
: Industrial use only.

Supplier's details : Sherwin-Williams Automotive Australia Pty Limited  
Unit 11/8 Kerta Road  
Kincumber NSW 2251  
AUSTRALIA  
T: +612 43684054

Emergency telephone number (with hours of operation) : Poisons Information Centre: Australia 131 126

## Section 2. Hazard(s) identification

Classification of the substance or mixture : FLAMMABLE LIQUIDS - Category 2  
SKIN CORROSION/IRRITATION - Category 2  
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3

### GHS label elements

Hazard pictograms :



Signal word : **DANGER**  
Hazard statements : **Highly flammable liquid and vapor.**  
**Causes serious eye irritation.**  
**Causes skin irritation.**  
**May cause respiratory irritation.**  
**May cause drowsiness or dizziness.**

### Precautionary statements

Prevention : Wear protective gloves. Wear eye or face protection. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating, lighting and all material-handling equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Keep container tightly closed. Use only outdoors or in a well-ventilated area. Avoid breathing vapor. Wash hands thoroughly after handling.

## Section 2. Hazard(s) identification

- Response** : IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing. Call a POISON CENTER or physician if you feel unwell. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water or shower. IF ON SKIN: Wash with plenty of soap and water. Take off contaminated clothing. If skin irritation occurs: Get medical attention. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If eye irritation persists: Get medical attention.
- Storage** : Store locked up. Store in a well-ventilated place. Keep cool.
- Disposal** : Dispose of contents and container in accordance with all local, regional, national and international regulations.
- Supplemental label elements** : Please refer to the SDS for additional information. Keep out of reach of children. Do not transfer contents to other containers for storage.

**Other hazards which do not result in classification** : None known.

## Section 3. Composition and ingredient information

- Substance/mixture** : Mixture
- Other means of identification** : Not available.

### CAS number/other identifiers

Not available.

Ingredient name	% (w/w)	CAS number
Acetone	>60%	67-64-1
p-Chlorobenzotrifluoride	10 - <30%	98-56-6

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

Occupational exposure limits, if available, are listed in Section 8.

## Section 4. First aid measures

### Description of necessary first aid measures

- Eye contact** : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 15 minutes. Get medical attention.
- Inhalation** : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention. If necessary, call a poison center or physician. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband. In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
- Skin contact** : Flush contaminated skin with plenty of water. Remove contaminated clothing and shoes. Continue to rinse for at least 15 minutes. Get medical attention. Wash clothing before reuse. Clean shoes thoroughly before reuse.

## Section 4. First aid measures

- Ingestion** : Wash out mouth with water. Remove dentures if any. Remove victim to fresh air and keep at rest in a position comfortable for breathing. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Get medical attention. If necessary, call a poison center or physician. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

### Most important symptoms/effects, acute and delayed

#### Potential acute health effects

- Eye contact** : Causes serious eye irritation.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause respiratory irritation.
- Skin contact** : Causes skin irritation.
- Ingestion** : Can cause central nervous system (CNS) depression.

#### Over-exposure signs/symptoms

- Eye contact** : Adverse symptoms may include the following:  
pain or irritation  
watering  
redness
- Inhalation** : Adverse symptoms may include the following:  
respiratory tract irritation  
coughing  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness
- Skin contact** : Adverse symptoms may include the following:  
irritation  
redness
- Ingestion** : No specific data.

### Indication of immediate medical attention and special treatment needed, if necessary

- Notes to physician** : In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
- Specific treatments** : No specific treatment.
- Protection of first-aiders** : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

See toxicological information (Section 11)

## Section 5. Fire-fighting measures

#### Extinguishing media

- Suitable extinguishing media** : Use dry chemical, CO<sub>2</sub>, water spray (fog) or foam.
- Unsuitable extinguishing media** : Do not use water jet.



## Section 5. Fire-fighting measures

- Specific hazards arising from the chemical** : Highly flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Vapors may accumulate in low or confined areas or travel a considerable distance to a source of ignition and flash back.
- Hazardous thermal decomposition products** : Decomposition products may include the following materials:  
carbon dioxide  
carbon monoxide  
halogenated compounds  
carbonyl halides
- Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.
- Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.
- Hazchem code** : Not applicable.

## Section 6. Accidental release measures

### Personal precautions, protective equipment and emergency procedures

- For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.
- For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".
- Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

### Methods and materials for containment and cleaning up

- Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.
- Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

## Section 7. Handling and storage


### Precautions for safe handling

- Protective measures** : Put on appropriate personal protective equipment (see Section 8). Do not ingest. Avoid contact with eyes, skin and clothing. Avoid breathing vapor or mist. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.
- Advice on general occupational hygiene** : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.
- Conditions for safe storage, including any incompatibilities** : Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use. Avoid release to the environment.

## Section 8. Exposure controls and personal protection

### Control parameters

#### Occupational exposure limits

Ingredient name	Exposure limits
Acetone	<b>Safe Work Australia (Australia, 4/2018).</b>  STEL: 2375 mg/m <sup>3</sup> 15 minutes. STEL: 1000 ppm 15 minutes. TWA: 1185 mg/m <sup>3</sup> 8 hours. TWA: 500 ppm 8 hours.

- Biological limit values** : There is no biological limit allocated.
- Appropriate engineering controls** : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.
- Environmental exposure controls** : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

### Individual protection measures

- Hygiene measures** : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

## Section 8. Exposure controls and personal protection

- Eye/face protection** : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: chemical splash goggles.
- Skin protection**
- Hand protection** : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.
- Body protection** : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear anti-static protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.
- Other skin protection** : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.
- Respiratory protection** : Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use.

## Section 9. Physical and chemical properties

### Appearance

- Physical state** : Liquid.
- Color** : Not available.
- Odor** : Not available.
- Odor threshold** : Not available.
- pH** : Not available.
- Melting point** : Not available.
- Boiling point** : 55°C (131°F)
- Flash point** : Closed cup: -16°C (3.2°F) [Pensky-Martens Closed Cup]
- Evaporation rate** : 5.6 (butyl acetate = 1)
- Flammability (solid, gas)** : Not available.
- Lower and upper explosive (flammable) limits** : Lower: 0.9%  
Upper: 12.8%
- Vapor pressure** : 24 kPa (180 mm Hg) [at 20°C]
- Vapor density** : 2 [Air = 1]
- Relative density** : 0.9
- Solubility** : Not available.
- Partition coefficient: n-octanol/water** : Not available.
- Auto-ignition temperature** : Not available.
- Decomposition temperature** : Not available.
- Viscosity** : Kinematic (40°C (104°F)): <0.205 cm<sup>2</sup>/s (<20.5 cSt)

### Aerosol product

- Heat of combustion** : 32.459 kJ/g

## Section 10. Stability and reactivity

- Reactivity** : No specific test data related to reactivity available for this product or its ingredients.
- Chemical stability** : The product is stable.
- Possibility of hazardous reactions** : Under normal conditions of storage and use, hazardous reactions will not occur.
- Conditions to avoid** : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.
- Incompatible materials** : Reactive or incompatible with the following materials:  
oxidizing materials
- Hazardous decomposition products** : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

## Section 11. Toxicological information

### Information on toxicological effects

#### Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Acetone	LD50 Oral	Rat	5800 mg/kg	-
p-Chlorobenzotrifluoride	LD50 Oral	Rat	13 g/kg	-

#### Irritation/Corrosion

Product/ingredient name	Result	Species	Score	Exposure	Observation
Acetone	Eyes - Mild irritant	Human	-	186300 ppm	-
	Eyes - Mild irritant	Rabbit	-	10 UI	-
	Eyes - Moderate irritant	Rabbit	-	24 hours 20 mg	-
	Eyes - Severe irritant	Rabbit	-	20 mg	-
	Skin - Mild irritant	Rabbit	-	24 hours 500 mg	-
	Skin - Mild irritant	Rabbit	-	395 mg	-

#### Sensitization

Not available.

#### Mutagenicity

Not available.

#### Carcinogenicity

Not available.

#### Reproductive toxicity

Not available.

#### Teratogenicity

Not available.

#### Specific target organ toxicity (single exposure)

## Section 11. Toxicological information

Name	Category	Route of exposure	Target organs
Acetone p-Chlorobenzotrifluoride	Category 3 Category 3	Not applicable. Not applicable.	Narcotic effects Respiratory tract irritation

### Specific target organ toxicity (repeated exposure)

Not available.

### Aspiration hazard

Not available.

**Information on the likely routes of exposure** : Not available.

### Potential acute health effects

- Eye contact** : Causes serious eye irritation.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause respiratory irritation.
- Skin contact** : Causes skin irritation.
- Ingestion** : Can cause central nervous system (CNS) depression.

### Symptoms related to the physical, chemical and toxicological characteristics

- Eye contact** : Adverse symptoms may include the following:  
pain or irritation  
watering  
redness
- Inhalation** : Adverse symptoms may include the following:  
respiratory tract irritation  
coughing  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness
- Skin contact** : Adverse symptoms may include the following:  
irritation  
redness
- Ingestion** : No specific data.

### Delayed and immediate effects and also chronic effects from short and long term exposure

#### Short term exposure

- Potential immediate effects** : Not available.
- Potential delayed effects** : Not available.

#### Long term exposure

- Potential immediate effects** : Not available.
- Potential delayed effects** : Not available.

### Potential chronic health effects

Not available.

- General** : No known significant effects or critical hazards.
- Carcinogenicity** : No known significant effects or critical hazards.

## Section 11. Toxicological information

- Mutagenicity** : No known significant effects or critical hazards.  
**Teratogenicity** : No known significant effects or critical hazards.  
**Developmental effects** : No known significant effects or critical hazards.  
**Fertility effects** : No known significant effects or critical hazards.

### Numerical measures of toxicity

#### Acute toxicity estimates

Not available.

## Section 12. Ecological information

### Toxicity

Product/ingredient name	Result	Species	Exposure
Acetone	Acute EC50 7200000 µg/l Fresh water	Algae - Selenastrum sp.	96 hours
	Acute LC50 6000000 µg/l Fresh water	Crustaceans - Gammarus pulex	48 hours
	Acute LC50 6900 mg/l Fresh water	Daphnia - Daphnia magna	48 hours
	Acute LC50 5600 ppm Fresh water	Fish - Poecilia reticulata	96 hours
	Chronic NOEC 4.95 mg/l Marine water	Algae - Ulva pertusa	96 hours
	Chronic NOEC 0.016 ml/L Fresh water	Crustaceans - Daphniidae	21 days
	Chronic NOEC 0.1 ml/L Fresh water	Daphnia - Daphnia magna - Neonate	21 days
	Chronic NOEC 0.1 mg/l Fresh water	Fish - Fundulus heteroclitus	4 weeks

### Persistence and degradability

Product/ingredient name	Aquatic half-life	Photolysis	Biodegradability
Acetone	-	-	Readily

### Bioaccumulative potential

Not available.

### Mobility in soil

- Soil/water partition coefficient (K<sub>oc</sub>)** : Not available.

- Other adverse effects** : No known significant effects or critical hazards.







## Section 13. Disposal considerations

- Disposal methods** : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly.

## Section 13. Disposal considerations

internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

## Section 14. Transport information

	ADG	ADR/RID	IMDG	IATA
UN number	UN1263	UN1263	UN1263	UN1263
UN proper shipping name	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL
Transport hazard class(es)	3 	3  	3  	3 
Packing group	II	II	II	II
Environmental hazards	Yes. The environmentally hazardous substance mark is not required.	Yes.	Yes.	Yes. The environmentally hazardous substance mark is not required.
Additional information	<u>Hazchem code</u> Not applicable.	The environmentally hazardous substance mark is not required when transported in sizes of ≤5 L or ≤5 kg. <u>Special provisions</u> 640 (C) <u>Tunnel code</u> D/E	The marine pollutant mark is not required when transported in sizes of ≤5 L or ≤5 kg. <u>Emergency schedules</u> F-E, S-E	The environmentally hazardous substance mark may appear if required by other transportation regulations.

**Special precautions for user** : **Transport within user's premises:** always transport in closed containers that are upright and secure. Ensure that persons transporting the product know what to do in the event of an accident or spillage.

Transport in bulk according to Annex II of MARPOL and the IBC Code : Not available.

## Section 15. Regulatory information

### Standard Uniform Schedule of Medicine and Poisons

Not regulated.

### Model Work Health and Safety Regulations - Scheduled Substances

No listed substance

### Agricultural and Veterinary Chemicals Code Act 1994

Not available.

### International regulations

#### Chemical Weapon Convention List Schedules I, II & III Chemicals

Not listed.

#### Montreal Protocol

Not listed.

#### Stockholm Convention on Persistent Organic Pollutants

## Section 15. Regulatory information

Not listed.

### Rotterdam Convention on Prior Informed Consent (PIC)

Not listed.

### UNECE Aarhus Protocol on POPs and Heavy Metals

Not listed.

## Section 16. Any other relevant information

### History

Date of printing : 27, November, 2019.

Date of issue/Date of revision : 27, November, 2019

Date of previous issue : 28, May, 2019

Version : 2

Key to abbreviations : ADG = Australian Dangerous Goods  
ADR = The European Agreement concerning the International Carriage of Dangerous Goods by Road  
ATE = Acute Toxicity Estimate  
BCF = Bioconcentration Factor  
GHS = Globally Harmonized System of Classification and Labelling of Chemicals  
IATA = International Air Transport Association  
IBC = Intermediate Bulk Container  
IMDG = International Maritime Dangerous Goods  
LogPow = logarithm of the octanol/water partition coefficient  
MARPOL = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)  
N/A = Not available  
SUSMP = Standard Uniform Schedule of Medicine and Poisons  
UN = United Nations

### Procedure used to derive the classification

Classification	Justification
FLAMMABLE LIQUIDS - Category 2	On basis of test data
SKIN CORROSION/IRRITATION - Category 2	Calculation method
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3	Calculation method

References : Not available.

Indicates information that has changed from previously issued version.

### Notice to reader

It is recommended that each customer or recipient of this Safety Data Sheet (SDS) study it carefully and consult resources, as necessary or appropriate, to become aware of and understand the data contained in this SDS and any hazards associated with the product. This information is provided in good faith and believed to be accurate as of the effective date herein. However, no warranty, express or implied, is given. The information presented here applies only to the product as shipped. The addition of any material can change the composition, hazards and risks of the product. Products shall not be repackaged, modified, or tinted except as specifically instructed by the manufacturer, including but not limited to the incorporation of products not specified by the manufacturer, or the use or addition of products in proportions not specified by the manufacturer. Regulatory requirements are subject to change and may differ between various locations and jurisdictions. The customer/buyer/user is responsible to ensure that his activities comply with all country, federal, state, provincial or local laws. The conditions for use of the product are not under the control of the manufacturer; the customer/buyer/user is responsible to determine the conditions necessary for the safe use of this product. The customer/buyer/user should not use the product for any purpose other



## **Section 16. Any other relevant information**

than the purpose shown in the applicable section of this SDS without first referring to the supplier and obtaining written handling instructions. Due to the proliferation of sources for information such as manufacturer-specific SDS, the manufacturer cannot be responsible for SDSs obtained from any other source.

**End of SDS**

# SAFETY DATA SHEET

R7K158

## Section 1. Identification

**Product name** : UltraClean™ Surfacers Cleaner  
**Product code** : R7K158  
**Other means of identification** : Not available.  
**Product type** : Liquid.  
**Relevant identified uses of the substance or mixture and uses advised against**  
Paint or paint related material.

**Manufacturer** : The Sherwin-Williams Company  
4440 Warrensville Center Road  
Warrensville Heights, OH 44128

**National contact** : Sherwin-Williams Canada Inc.  
180 Brunel Road  
Mississauga, Ontario L4Z 1T5 Canada

**Emergency telephone number of the company** : US / Canada: (800) 424-9300  
Mexico: (52) 55-4160-8800 / (52) 55-4160-8819 Monday to Friday from 8:30 a.m. to 5:30 p.m.

**Product Information Telephone Number** : US / Canada: (800) 798-5872  
Mexico: 01-800-022-7926

**Regulatory Information Telephone Number** : US / Canada: (216) 566-2902  
Mexico: (52) 55-4160-8819 / (52) 55-4160-8806

**Transportation Emergency Telephone Number** : US / Canada: (800) 424-9300  
Mexico: SETIQ 01-800-00-214-00 / (52) 55-5559-1588 24 hours / 365 days a year

## Section 2. Hazards identification

**Classification of the substance or mixture** : FLAMMABLE LIQUIDS - Category 2  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3  
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 2  
ASPIRATION HAZARD - Category 1  
Percentage of the mixture consisting of ingredient(s) of unknown acute oral toxicity: 100%  
Percentage of the mixture consisting of ingredient(s) of unknown acute dermal toxicity: 100%  
Percentage of the mixture consisting of ingredient(s) of unknown acute inhalation toxicity: 100%

### GHS label elements

**Hazard pictograms** :



**Signal word** : Danger

## Section 2. Hazards identification

**Hazard statements** : Highly flammable liquid and vapor.  
May be fatal if swallowed and enters airways.  
May cause respiratory irritation.  
May cause drowsiness or dizziness.  
May cause damage to organs through prolonged or repeated exposure.

### Precautionary statements

**Prevention** : Wear protective gloves. Wear eye or face protection. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating, lighting and all material-handling equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Keep container tightly closed. Use only outdoors or in a well-ventilated area. Do not breathe vapor.

**Response** : Get medical attention if you feel unwell. IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER or physician if you feel unwell. IF SWALLOWED: Immediately call a POISON CENTER or physician. Do NOT induce vomiting. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water or shower.

**Storage** : Store locked up. Store in a well-ventilated place. Keep cool.

**Disposal** : Dispose of contents and container in accordance with all local, regional, national and international regulations.

**Supplemental label elements** DELAYED EFFECTS FROM LONG TERM OVEREXPOSURE. Contains solvents which can cause permanent brain and nervous system damage. Intentional misuse by deliberately concentrating and inhaling the contents can be harmful or fatal. WARNING: This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm. FOR PROFESSIONAL USE ONLY.  
Please refer to the SDS for additional information. Keep out of reach of children. Do not transfer contents to other containers for storage.

**Hazards not otherwise classified** : None known.

## Section 3. Composition/information on ingredients

**Substance/mixture** : Mixture

**Other means of identification** : Not available.

### CAS number/other identifiers

Ingredient name	% by weight	CAS number
Lt. Aliphatic Hydrocarbon Solvent	94.89	64742-89-8
Light Aliphatic Hydrocarbon	5.11	64742-47-8

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

**There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health and hence require reporting in this section.**

Occupational exposure limits, if available, are listed in Section 8.

## Section 4. First aid measures

### Description of necessary first aid measures

**Eye contact** : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention following exposure or if feeling unwell.

## Section 4. First aid measures

- Inhalation** : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention. If necessary, call a poison center or physician. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.
- Skin contact** : Flush contaminated skin with plenty of water. Remove contaminated clothing and shoes. Continue to rinse for at least 10 minutes. Get medical attention following exposure or if feeling unwell. Wash clothing before reuse. Clean shoes thoroughly before reuse.
- Ingestion** : Get medical attention immediately. Call a poison center or physician. Wash out mouth with water. Remove dentures if any. Remove victim to fresh air and keep at rest in a position comfortable for breathing. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Aspiration hazard if swallowed. Can enter lungs and cause damage. Do not induce vomiting. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

### Most important symptoms/effects, acute and delayed

#### Potential acute health effects

- Eye contact** : No known significant effects or critical hazards.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause respiratory irritation.
- Skin contact** : No known significant effects or critical hazards.
- Ingestion** : Can cause central nervous system (CNS) depression. May be fatal if swallowed and enters airways.

#### Over-exposure signs/symptoms

- Eye contact** : No specific data.
- Inhalation** : Adverse symptoms may include the following:  
respiratory tract irritation  
coughing  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness
- Skin contact** : No specific data.
- Ingestion** : Adverse symptoms may include the following:  
nausea or vomiting

### Indication of immediate medical attention and special treatment needed, if necessary

- Notes to physician** : Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.
- Specific treatments** : No specific treatment.
- Protection of first-aiders** : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

## Section 4. First aid measures

See toxicological information (Section 11)

## Section 5. Fire-fighting measures

### Extinguishing media

**Suitable extinguishing media** : Use dry chemical, CO<sub>2</sub>, water spray (fog) or foam.

**Unsuitable extinguishing media** : Do not use water jet.

**Specific hazards arising from the chemical** : Highly flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Vapors may accumulate in low or confined areas or travel a considerable distance to a source of ignition and flash back.

**Hazardous thermal decomposition products** : Decomposition products may include the following materials:  
carbon dioxide  
carbon monoxide

**Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.

**Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

## Section 6. Accidental release measures

### Personal precautions, protective equipment and emergency procedures

**For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.

**For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

**Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

### Methods and materials for containment and cleaning up

**Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.

## Section 6. Accidental release measures

- Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

## Section 7. Handling and storage

### Precautions for safe handling

- Protective measures** : Put on appropriate personal protective equipment (see Section 8). Do not breathe vapor or mist. Do not swallow. Avoid contact with eyes, skin and clothing. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.
- Advice on general occupational hygiene** : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

- Conditions for safe storage, including any incompatibilities** : Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use.

## Section 8. Exposure controls/personal protection

### Control parameters

#### Occupational exposure limits (OSHA United States)

Ingredient name	CAS #	Exposure limits
Lt. Aliphatic Hydrocarbon Solvent Light Aliphatic Hydrocarbon	64742-89-8 64742-47-8	None. <b>ACGIH TLV (United States, 3/2019).</b> <b>Absorbed through skin.</b> TWA: 200 mg/m <sup>3</sup> , (as total hydrocarbon vapor) 8 hours.

#### Occupational exposure limits (Canada)

## Section 8. Exposure controls/personal protection

Ingredient name	CAS #	Exposure limits
Petroleum refining, hydrotreated light distillate	64742-47-8	<p><b>CA British Columbia Provincial (Canada, 5/2019). Absorbed through skin.</b> TWA: 200 mg/m<sup>3</sup>, (as total hydrocarbon vapour) 8 hours.</p> <p><b>CA Alberta Provincial (Canada, 6/2018). Absorbed through skin.</b> 8 hrs OEL: 200 mg/m<sup>3</sup>, (as total hydrocarbon vapour) 8 hours.</p> <p><b>CA Ontario Provincial (Canada, 1/2018). Absorbed through skin.</b> TWA: 200 mg/m<sup>3</sup>, (as total hydrocarbon vapour) 8 hours.</p>

### Occupational exposure limits (Mexico)

Ingredient name	CAS #	Exposure limits
Light Aliphatic Hydrocarbon	64742-47-8	<p><b>ACGIH TLV (United States, 3/2019). Absorbed through skin.</b> TWA: 200 mg/m<sup>3</sup>, (as total hydrocarbon vapor) 8 hours.</p>

- Appropriate engineering controls** : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.
- Environmental exposure controls** : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

### Individual protection measures

- Hygiene measures** : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.
- Eye/face protection** : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: safety glasses with side-shields.
- Skin protection**
- Hand protection** : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.
- Body protection** : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear anti-static protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.

## Section 8. Exposure controls/personal protection

- Other skin protection** : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.
- Respiratory protection** : Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use.

## Section 9. Physical and chemical properties

### Appearance

- Physical state** : Liquid.
- Color** : Not available.
- Odor** : Not available.
- Odor threshold** : Not available.
- pH** : Not available.
- Melting point/freezing point** : Not available.
- Boiling point/boiling range** : 115°C (239°F)
- Flash point** : Closed cup: 7°C (44.6°F) [Pensky-Martens Closed Cup]
- Evaporation rate** : 1.5 (butyl acetate = 1)
- Flammability (solid, gas)** : Not available.
- Lower and upper explosive (flammable) limits** : Lower: 0.9%  
Upper: 6%
- Vapor pressure** : 1.6 kPa (12 mm Hg) [at 20°C]
- Vapor density** : 4.1 [Air = 1]
- Relative density** : 0.74
- Solubility** : Not available.
- Partition coefficient: n-octanol/water** : Not available.
- Auto-ignition temperature** : Not available.
- Decomposition temperature** : Not available.
- Viscosity** : Kinematic (40°C (104°F)): <0.205 cm<sup>2</sup>/s (<20.5 cSt)
- Molecular weight** : Not applicable.

### Aerosol product

- Heat of combustion** : 43.355 kJ/g

## Section 10. Stability and reactivity

- Reactivity** : No specific test data related to reactivity available for this product or its ingredients.
- Chemical stability** : The product is stable.
- Possibility of hazardous reactions** : Under normal conditions of storage and use, hazardous reactions will not occur.
- Conditions to avoid** : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.



## Section 10. Stability and reactivity

**Incompatible materials** : Reactive or incompatible with the following materials:  
oxidizing materials

**Hazardous decomposition products** : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

## Section 11. Toxicological information

### Information on toxicological effects

#### Acute toxicity

Not available.

#### Irritation/Corrosion

Not available.

#### Sensitization

Not available.

#### Mutagenicity

Not available.

#### Carcinogenicity

Not available.

#### Reproductive toxicity

Not available.

#### Teratogenicity

Not available.

#### Specific target organ toxicity (single exposure)

Name	Category	Route of exposure	Target organs
Lt. Aliphatic Hydrocarbon Solvent	Category 3 Category 3	Not applicable. Not applicable.	Narcotic effects Respiratory tract irritation
Light Aliphatic Hydrocarbon	Category 3 Category 3	Not applicable. Not applicable.	Narcotic effects Respiratory tract irritation

#### Specific target organ toxicity (repeated exposure)

Name	Category	Route of exposure	Target organs
Lt. Aliphatic Hydrocarbon Solvent Light Aliphatic Hydrocarbon	Category 2 Category 2	Not determined Not determined	Not determined Not determined

#### Aspiration hazard

Name	Result
Lt. Aliphatic Hydrocarbon Solvent Light Aliphatic Hydrocarbon	ASPIRATION HAZARD - Category 1 ASPIRATION HAZARD - Category 1

**Information on the likely routes of exposure** : Not available.

#### Potential acute health effects

**Eye contact** : No known significant effects or critical hazards.

# Section 11. Toxicological information

- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause respiratory irritation.
- Skin contact** : No known significant effects or critical hazards.
- Ingestion** : Can cause central nervous system (CNS) depression. May be fatal if swallowed and enters airways.

## Symptoms related to the physical, chemical and toxicological characteristics

- Eye contact** : No specific data.
- Inhalation** : Adverse symptoms may include the following:
  - respiratory tract irritation
  - coughing
  - nausea or vomiting
  - headache
  - drowsiness/fatigue
  - dizziness/vertigo
  - unconsciousness
- Skin contact** : No specific data.
- Ingestion** : Adverse symptoms may include the following:
  - nausea or vomiting

## Delayed and immediate effects and also chronic effects from short and long term exposure

### Short term exposure

- Potential immediate effects** : Not available.
- Potential delayed effects** : Not available.

### Long term exposure

- Potential immediate effects** : Not available.
- Potential delayed effects** : Not available.

### Potential chronic health effects

Not available.

- General** : May cause damage to organs through prolonged or repeated exposure.
- Carcinogenicity** : No known significant effects or critical hazards.
- Mutagenicity** : No known significant effects or critical hazards.
- Teratogenicity** : No known significant effects or critical hazards.
- Developmental effects** : No known significant effects or critical hazards.
- Fertility effects** : No known significant effects or critical hazards.

## Numerical measures of toxicity

### Acute toxicity estimates

Not available.

## Section 12. Ecological information

### Toxicity

Product/ingredient name	Result	Species	Exposure
Lt. Aliphatic Hydrocarbon Solvent	Acute LC50 >100000 ppm Fresh water	Fish - Oncorhynchus mykiss	96 hours
Light Aliphatic Hydrocarbon	Acute LC50 2200 µg/l Fresh water	Fish - Lepomis macrochirus	4 days

### Persistence and degradability

Not available.

### Bioaccumulative potential

Product/ingredient name	LogP <sub>ow</sub>	BCF	Potential
Lt. Aliphatic Hydrocarbon Solvent	-	10 to 2500	high

### Mobility in soil

Soil/water partition coefficient (K<sub>oc</sub>) : Not available.

Other adverse effects : No known significant effects or critical hazards.







## Section 13. Disposal considerations

**Disposal methods** : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

## Section 14. Transport information

	DOT Classification	TDG Classification	Mexico Classification	IATA	IMDG
UN number	UN1263	UN1263	UN1263	UN1263	UN1263
UN proper shipping name	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL. Marine pollutant (Lt. Aliphatic Hydrocarbon Solvent, Light Aliphatic Hydrocarbon)

## Section 14. Transport information

Transport hazard class(es)	3 	3 	3 	3 	3  
Packing group	II	II	II	II	II
Environmental hazards	No.	No.	No.	Yes. The environmentally hazardous substance mark is not required.	Yes.
Additional information	-  <b>ERG No.</b> 128	Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.18-2.19 (Class 3). <b>ERG No.</b> 128	-  <b>ERG No.</b> 128	The environmentally hazardous substance mark may appear if required by other transportation regulations.	The marine pollutant mark is not required when transported in sizes of ≤5 L or ≤5 kg. <b>Emergency schedules F-E, S-E</b>

**Special precautions for user** : Multi-modal shipping descriptions are provided for informational purposes and do not consider container sizes. The presence of a shipping description for a particular mode of transport (sea, air, etc.), does not indicate that the product is packaged suitably for that mode of transport. All packaging must be reviewed for suitability prior to shipment, and compliance with the applicable regulations is the sole responsibility of the person offering the product for transport. People loading and unloading dangerous goods must be trained on all of the risks deriving from the substances and on all actions in case of emergency situations.

**Transport in bulk according to Annex II of MARPOL and the IBC Code** : Not available.

**Proper shipping name** : Not available.  
**Ship type** : Not available.  
**Pollution category** : Not available.

## Section 15. Regulatory information

### International regulations

#### International lists

**Australia inventory (AICS)**: Not determined.  
**China inventory (IECSC)**: Not determined.  
**Japan inventory (ENCS)**: Not determined.  
**Japan inventory (ISHL)**: Not determined.  
**Korea inventory (KECI)**: Not determined.  
**New Zealand Inventory of Chemicals (NZIoC)**: Not determined.  
**Philippines inventory (PICCS)**: Not determined.  
**Taiwan Chemical Substances Inventory (TCSI)**: Not determined.  
**Thailand inventory**: Not determined.  
**Turkey inventory**: Not determined.  
**Vietnam inventory**: Not determined.

## Section 16. Other information

### Hazardous Material Information System (U.S.A.)

Health	2
Flammability	3
Physical hazards	0

The customer is responsible for determining the PPE code for this material. For more information on HMIS® Personal Protective Equipment (PPE) codes, consult the HMIS® Implementation Manual.

Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks. Although HMIS® ratings and the associated label are not required on SDSs or products leaving a facility under 29 CFR 1910.1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered trademark and service mark of the American Coatings Association, Inc.

#### Procedure used to derive the classification

Classification	Justification
FLAMMABLE LIQUIDS - Category 2	On basis of test data
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 2	Calculation method
ASPIRATION HAZARD - Category 1	Calculation method

#### History

Date of printing	: 2/12/2020
Date of issue/Date of revision	: 2/12/2020
Date of previous issue	: 11/30/2019
Version	: 7
Key to abbreviations	: ATE = Acute Toxicity Estimate BCF = Bioconcentration Factor GHS = Globally Harmonized System of Classification and Labelling of Chemicals IATA = International Air Transport Association IBC = Intermediate Bulk Container IMDG = International Maritime Dangerous Goods LogPow = logarithm of the octanol/water partition coefficient MARPOL = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution) N/A = Not available SGG = Segregation Group UN = United Nations

☑ Indicates information that has changed from previously issued version.

#### Notice to reader

It is recommended that each customer or recipient of this Safety Data Sheet (SDS) study it carefully and consult resources, as necessary or appropriate, to become aware of and understand the data contained in this SDS and any hazards associated with the product. This information is provided in good faith and believed to be accurate as of the effective date herein. However, no warranty, express or implied, is given. The information presented here applies only to the product as shipped. The addition of any material can change the composition, hazards and risks of the product. Products shall not be repackaged, modified, or tinted except as specifically instructed by the manufacturer, including but not limited to the incorporation of products not specified by the manufacturer, or the use or addition of products in proportions not specified by the manufacturer. Regulatory requirements are subject to change and may differ between various locations and jurisdictions. The customer/buyer/user is responsible to ensure that his activities comply with all country, federal, state, provincial or local laws. The

## Section 16. Other information

conditions for use of the product are not under the control of the manufacturer; the customer/buyer/user is responsible to determine the conditions necessary for the safe use of this product. The customer/buyer/user should not use the product for any purpose other than the purpose shown in the applicable section of this SDS without first referring to the supplier and obtaining written handling instructions. Due to the proliferation of sources for information such as manufacturer-specific SDS, the manufacturer cannot be responsible for SDSs obtained from any other source.

# SAFETY DATA SHEET

E2A933

## Section 1. Identification

**Product name** : 3.5 VOC Epoxy Primer (Part A)  
Gray

**Product code** : E2A933

**Other means of identification** : Not available.

**Product type** : Liquid.

**Relevant identified uses of the substance or mixture and uses advised against**

Paint or paint related material.

**Manufacturer** : The Sherwin-Williams Company  
4440 Warrensville Center Road  
Warrensville Heights, OH 44128

**National contact** : Sherwin-Williams Canada Inc.  
180 Brunel Road  
Mississauga, Ontario L4Z 1T5 Canada

**Emergency telephone number of the company** : US / Canada: (800) 424-9300  
Mexico: (52) 55-4160-8800 / (52) 55-4160-8819 Monday to Friday from 8:30 a.m. to 5:30 p.m.

**Product Information telephone Number** : US / Canada: (800) 798-5872  
Mexico: 01-800-022-7926

**Regulatory Information Telephone Number** : US / Canada: (216) 566-2902  
Mexico: (52) 55-4160-8819 / (52) 55-4160-8806

**Transportation Emergency Telephone Number** : US / Canada: (800) 424-9300  
Mexico: SETIQ 01-800-00-214-00 / (52) 55-5559-1588 24 hours / 365 days a year

## Section 2. Hazards identification

**Classification of the substance or mixture** : FLAMMABLE LIQUIDS - Category 2  
SKIN CORROSION/IRRITATION - Category 2  
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A  
SKIN SENSITIZATION - Category 1  
CARCINOGENICITY - Category 1A  
TOXIC TO REPRODUCTION (Unborn child) - Category 2  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3  
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) (lungs) - Category 1  
Percentage of the mixture consisting of ingredient(s) of unknown acute oral toxicity: 8.1%  
Percentage of the mixture consisting of ingredient(s) of unknown acute dermal toxicity: 10%  
Percentage of the mixture consisting of ingredient(s) of unknown acute inhalation toxicity: 16.1%

### GHS label elements

<b>Date of issue/Date of revision</b> : 5/19/2020	<b>Date of previous issue</b> : 4/3/2020	<b>Version</b> : 17.02	1/23
E2A933	3.5 VOC Epoxy Primer (Part A) Gray	SHW-85-NA-GHS-CA	

## Section 2. Hazards identification

Hazard pictograms :



Signal word :

Danger

Hazard statements :

Highly flammable liquid and vapor.  
Causes serious eye irritation.  
Causes skin irritation.  
May cause an allergic skin reaction.  
May cause cancer.  
Suspected of damaging the unborn child.  
May cause drowsiness or dizziness.  
Causes damage to organs through prolonged or repeated exposure. (lungs)

### Precautionary statements

Prevention :

Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Wear protective gloves. Wear eye or face protection. Wear protective clothing. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating, lighting and all material-handling equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Keep container tightly closed. Use only outdoors or in a well-ventilated area. Do not breathe vapor. Do not eat, drink or smoke when using this product. Wash hands thoroughly after handling. Contaminated work clothing must not be allowed out of the workplace.

Response :

Get medical attention if you feel unwell. IF exposed or concerned: Get medical attention. IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER or physician if you feel unwell. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water or shower. IF ON SKIN: Wash with plenty of soap and water. Wash contaminated clothing before reuse. If skin irritation or rash occurs: Get medical attention. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If eye irritation persists: Get medical attention.

Storage :

Store locked up. Store in a well-ventilated place. Keep cool.

Disposal :

Dispose of contents and container in accordance with all local, regional, national and international regulations.

Supplemental label elements

DELAYED EFFECTS FROM LONG TERM OVEREXPOSURE. Contains solvents which can cause permanent brain and nervous system damage. Intentional misuse by deliberately concentrating and inhaling the contents can be harmful or fatal. WARNING: This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm. FOR PROFESSIONAL USE ONLY. This product must be mixed with other components before use. Before opening the packages, READ AND FOLLOW WARNING LABELS ON ALL COMPONENTS. Adequate ventilation required when sanding or abrading the dried film. If Adequate ventilation cannot be provided wear an approved particulate respirator (NIOSH approved). Follow respirator manufacturer's directions for respirator use. DELAYED EFFECTS FROM LONG TERM OVEREXPOSURE. Abrading or sanding of the dry film may release Crystalline Silica which has been shown to cause lung damage and cancer under long term exposure.

Please refer to the SDS for additional information. Keep out of reach of children. Do not transfer contents to other containers for storage.

Hazards not otherwise classified

: None known.



## Section 3. Composition/information on ingredients

Substance/mixture : Mixture  
Other means of identification : Not available.

### CAS number/other identifiers

Ingredient name	% by weight	CAS number
Barium Sulfate	15.83	7727-43-7
Talc	13.71	14807-96-6
Acetone	9.76	67-64-1
Titanium Dioxide	9.03	13463-67-7
Phenol, polymer with formaldehyde, glycidylether	8.12	28064-14-4
n-Butyl Acetate	6.95	123-86-4
Methyl n-Propyl Ketone	6.07	107-87-9
2-methoxy-1-methylethyl acetate	3.8	108-65-6
Organosilane Ester	1.9	2530-83-8
Xylene, mixed isomers	0.47	1330-20-7
Med. Aliphatic Hydrocarbon Solvent	0.38	64742-88-7
Methyl Isobutyl Ketone	0.35	108-10-1
Toluene	0.26	108-88-3
Crystalline Silica, respirable powder	0.16	14808-60-7
1,2,4-Trimethylbenzene	0.13	95-63-6
Ethylbenzene	0.12	100-41-4
Carbon Black	0.11	1333-86-4

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health and hence require reporting in this section.

Occupational exposure limits, if available, are listed in Section 8.

## Section 4. First aid measures

### Description of necessary first aid measures

- Eye contact** : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention.
- Inhalation** : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention. If necessary, call a poison center or physician. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.
- Skin contact** : Wash with plenty of soap and water. Remove contaminated clothing and shoes. Wash contaminated clothing thoroughly with water before removing it, or wear gloves. Continue to rinse for at least 10 minutes. Get medical attention. In the event of any complaints or symptoms, avoid further exposure. Wash clothing before reuse. Clean shoes thoroughly before reuse.
- Ingestion** : Wash out mouth with water. Remove dentures if any. Remove victim to fresh air and keep at rest in a position comfortable for breathing. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Get medical attention. If necessary, call a poison center or physician. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention.

## Section 4. First aid measures

immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

### Most important symptoms/effects, acute and delayed

#### Potential acute health effects

- Eye contact** : Causes serious eye irritation.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness.
- Skin contact** : Causes skin irritation. May cause an allergic skin reaction.
- Ingestion** : Can cause central nervous system (CNS) depression.

#### Over-exposure signs/symptoms

- Eye contact** : Adverse symptoms may include the following:  
pain or irritation  
watering  
redness
- Inhalation** : Adverse symptoms may include the following:  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations
- Skin contact** : Adverse symptoms may include the following:  
irritation  
redness  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations
- Ingestion** : Adverse symptoms may include the following:  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations

### Indication of immediate medical attention and special treatment needed, if necessary

- Notes to physician** : Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.
- Specific treatments** : No specific treatment.
- Protection of first-aiders** : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

See toxicological information (Section 11)

## Section 5. Fire-fighting measures

### Extinguishing media

**Suitable extinguishing media** : Use dry chemical, CO<sub>2</sub>, water spray (fog) or foam.

**Unsuitable extinguishing media** : Do not use water jet.

**Specific hazards arising from the chemical** : Highly flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Vapors may accumulate in low or confined areas or travel a considerable distance to a source of ignition and flash back.

**Hazardous thermal decomposition products** : Decomposition products may include the following materials:  
carbon dioxide  
carbon monoxide  
sulfur oxides  
phosphorus oxides  
metal oxide/oxides

**Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.

**Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

## Section 6. Accidental release measures

### Personal precautions, protective equipment and emergency procedures

**For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.

**For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

**Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

### Methods and materials for containment and cleaning up

**Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.

**Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the

## Section 6. Accidental release measures

same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

## Section 7. Handling and storage

### Precautions for safe handling

- Protective measures** : Put on appropriate personal protective equipment (see Section 8). Persons with a history of skin sensitization problems should not be employed in any process in which this product is used. Avoid exposure - obtain special instructions before use. Avoid exposure during pregnancy. Do not handle until all safety precautions have been read and understood. Do not get in eyes or on skin or clothing. Do not breathe vapor or mist. Do not ingest. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.
- Advice on general occupational hygiene** : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

- Conditions for safe storage, including any incompatibilities** : Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use.

## Section 8. Exposure controls/personal protection

### Control parameters

#### Occupational exposure limits (OSHA United States)

Ingredient name	CAS #	Exposure limits
Barium Sulfate	7727-43-7	<b>ACGIH TLV (United States, 3/2019).</b> TWA: 5 mg/m <sup>3</sup> 8 hours. Form: Inhalable fraction <b>NIOSH REL (United States, 10/2016).</b> TWA: 5 mg/m <sup>3</sup> 10 hours. Form: Respirable fraction TWA: 10 mg/m <sup>3</sup> 10 hours. Form: Total
Talc	14807-96-6	<b>OSHA PEL (United States, 5/2018).</b> TWA: 5 mg/m <sup>3</sup> 8 hours. Form: Respirable fraction TWA: 15 mg/m <sup>3</sup> 8 hours. Form: Total dust <b>NIOSH REL (United States, 10/2016).</b> TWA: 2 mg/m <sup>3</sup> 10 hours. Form: Respirable fraction <b>ACGIH TLV (United States, 3/2019).</b> TWA: 2 mg/m <sup>3</sup> 8 hours. Form: Respirable fraction
Acetone	67-64-1	

## Section 8. Exposure controls/personal protection

Titanium Dioxide	13463-67-7	<p><b>ACGIH TLV (United States, 3/2019).</b> TWA: 250 ppm 8 hours. STEL: 500 ppm 15 minutes.</p> <p><b>NIOSH REL (United States, 10/2016).</b> TWA: 250 ppm 10 hours. TWA: 590 mg/m<sup>3</sup> 10 hours.</p> <p><b>OSHA PEL (United States, 5/2018).</b> TWA: 1000 ppm 8 hours. TWA: 2400 mg/m<sup>3</sup> 8 hours.</p>
Phenol, polymer with formaldehyde, glycidylether n-Butyl Acetate	28064-14-4 123-86-4	<p><b>ACGIH TLV (United States, 3/2019).</b> TWA: 10 mg/m<sup>3</sup> 8 hours.</p> <p><b>OSHA PEL (United States, 5/2018).</b> TWA: 15 mg/m<sup>3</sup> 8 hours. Form: Total dust None.</p> <p><b>NIOSH REL (United States, 10/2016).</b> TWA: 150 ppm 10 hours. TWA: 710 mg/m<sup>3</sup> 10 hours. STEL: 200 ppm 15 minutes. STEL: 950 mg/m<sup>3</sup> 15 minutes.</p> <p><b>OSHA PEL (United States, 5/2018).</b> TWA: 150 ppm 8 hours. TWA: 710 mg/m<sup>3</sup> 8 hours.</p> <p><b>ACGIH TLV (United States, 3/2019).</b> STEL: 150 ppm 15 minutes. TWA: 50 ppm 8 hours.</p>
Methyl n-Propyl Ketone	107-87-9	<p><b>NIOSH REL (United States, 10/2016).</b> TWA: 150 ppm 10 hours. TWA: 530 mg/m<sup>3</sup> 10 hours.</p> <p><b>OSHA PEL (United States, 5/2018).</b> TWA: 200 ppm 8 hours. TWA: 700 mg/m<sup>3</sup> 8 hours.</p> <p><b>ACGIH TLV (United States, 3/2019).</b> STEL: 150 ppm 15 minutes.</p>
2-methoxy-1-methylethyl acetate	108-65-6	<p><b>AIHA WEEL (United States, 7/2018).</b> TWA: 50 ppm 8 hours.</p> <p>None.</p> <p><b>ACGIH TLV (United States, 3/2019).</b> TWA: 100 ppm 8 hours. TWA: 434 mg/m<sup>3</sup> 8 hours. STEL: 150 ppm 15 minutes. STEL: 651 mg/m<sup>3</sup> 15 minutes.</p> <p><b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours. TWA: 435 mg/m<sup>3</sup> 8 hours.</p>
Organosilane Ester Xylene, mixed isomers	2530-83-8 1330-20-7	<p><b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours. TWA: 400 mg/m<sup>3</sup> 8 hours.</p> <p><b>ACGIH TLV (United States, 3/2019).</b> TWA: 20 ppm 8 hours. STEL: 75 ppm 15 minutes.</p> <p><b>NIOSH REL (United States, 10/2016).</b> TWA: 50 ppm 10 hours. TWA: 205 mg/m<sup>3</sup> 10 hours. STEL: 75 ppm 15 minutes. STEL: 300 mg/m<sup>3</sup> 15 minutes.</p> <p><b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours.</p>
Med. Aliphatic Hydrocarbon Solvent	64742-88-7	<p><b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours. TWA: 400 mg/m<sup>3</sup> 8 hours.</p> <p><b>ACGIH TLV (United States, 3/2019).</b> TWA: 20 ppm 8 hours. STEL: 75 ppm 15 minutes.</p> <p><b>NIOSH REL (United States, 10/2016).</b> TWA: 50 ppm 10 hours. TWA: 205 mg/m<sup>3</sup> 10 hours. STEL: 75 ppm 15 minutes. STEL: 300 mg/m<sup>3</sup> 15 minutes.</p> <p><b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours.</p>
Methyl Isobutyl Ketone	108-10-1	<p><b>ACGIH TLV (United States, 3/2019).</b> TWA: 20 ppm 8 hours. STEL: 75 ppm 15 minutes.</p> <p><b>NIOSH REL (United States, 10/2016).</b> TWA: 50 ppm 10 hours. TWA: 205 mg/m<sup>3</sup> 10 hours. STEL: 75 ppm 15 minutes. STEL: 300 mg/m<sup>3</sup> 15 minutes.</p> <p><b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours.</p>

## Section 8. Exposure controls/personal protection

Toluene	108-88-3	<p>TWA: 410 mg/m<sup>3</sup> 8 hours.  <b>OSHA PEL Z2 (United States, 2/2013).</b>                      TWA: 200 ppm 8 hours.                      CEIL: 300 ppm                      AMP: 500 ppm 10 minutes.  <b>NIOSH REL (United States, 10/2016).</b>                      TWA: 100 ppm 10 hours.                      TWA: 375 mg/m<sup>3</sup> 10 hours.                      STEL: 150 ppm 15 minutes.                      STEL: 560 mg/m<sup>3</sup> 15 minutes.  <b>ACGIH TLV (United States, 3/2019).</b>                      TWA: 20 ppm 8 hours.</p>
Crystalline Silica, respirable powder	14808-60-7	<p><b>OSHA PEL Z3 (United States, 6/2016).</b>                      TWA: 250 mppcf / (%SiO<sub>2</sub>+5) 8 hours. Form: Respirable                      TWA: 10 mg/m<sup>3</sup> / (%SiO<sub>2</sub>+2) 8 hours. Form: Respirable  <b>OSHA PEL (United States, 5/2018).</b>                      TWA: 50 µg/m<sup>3</sup> 8 hours. Form: Respirable dust  <b>ACGIH TLV (United States, 3/2019).</b>                      TWA: 0.025 mg/m<sup>3</sup> 8 hours. Form: Respirable fraction  <b>NIOSH REL (United States, 10/2016).</b>                      TWA: 0.05 mg/m<sup>3</sup> 10 hours. Form: respirable dust</p>
1,2,4-Trimethylbenzene	95-63-6	<p><b>ACGIH TLV (United States, 3/2019).</b>                      TWA: 25 ppm 8 hours.                      TWA: 123 mg/m<sup>3</sup> 8 hours.  <b>NIOSH REL (United States, 10/2016).</b>                      TWA: 25 ppm 10 hours.                      TWA: 125 mg/m<sup>3</sup> 10 hours.</p>
Ethylbenzene	100-41-4	<p><b>ACGIH TLV (United States, 3/2019).</b>                      TWA: 20 ppm 8 hours.  <b>NIOSH REL (United States, 10/2016).</b>                      TWA: 100 ppm 10 hours.                      TWA: 435 mg/m<sup>3</sup> 10 hours.                      STEL: 125 ppm 15 minutes.                      STEL: 545 mg/m<sup>3</sup> 15 minutes.  <b>OSHA PEL (United States, 5/2018).</b>                      TWA: 100 ppm 8 hours.                      TWA: 435 mg/m<sup>3</sup> 8 hours.</p>
Carbon Black	1333-86-4	<p><b>NIOSH REL (United States, 10/2016).</b>                      TWA: 3.5 mg/m<sup>3</sup> 10 hours.                      TWA: 0.1 mg of PAHs/cm<sup>3</sup> 10 hours.  <b>ACGIH TLV (United States, 3/2019).</b>                      TWA: 3 mg/m<sup>3</sup> 8 hours. Form: Inhalable fraction  <b>OSHA PEL (United States, 5/2018).</b>                      TWA: 3.5 mg/m<sup>3</sup> 8 hours.</p>

### Occupational exposure limits (Canada)

## Section 8. Exposure controls/personal protection

Ingredient name	CAS #	Exposure limits
talc (none asbestiform)	14807-96-6	<p><b>CA British Columbia Provincial (Canada, 5/2019).</b>                      TWA: 2 mg/m<sup>3</sup> 8 hours. Form: Respirable                      TWA: 0.1 f/cc 8 hours.</p> <p><b>CA Quebec Provincial (Canada, 1/2014).</b>                      TWAEV: 3 mg/m<sup>3</sup> 8 hours. Form:                      Respirable dust.</p> <p><b>CA Ontario Provincial (Canada, 1/2018).</b>                      TWA: 2 mg/m<sup>3</sup> 8 hours. Form: Respirable                      fraction.                      TWA: 2 f/cc 8 hours.</p> <p><b>CA Alberta Provincial (Canada, 6/2018).</b>                      8 hrs OEL: 2 mg/m<sup>3</sup> 8 hours. Form:                      Respirable particulate</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>                      TWA: 2 mg/m<sup>3</sup> 8 hours. Form: respirable                      fraction</p>
Acetone	67-64-1	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>                      8 hrs OEL: 1200 mg/m<sup>3</sup> 8 hours.                      15 min OEL: 1800 mg/m<sup>3</sup> 15 minutes.                      8 hrs OEL: 500 ppm 8 hours.                      15 min OEL: 750 ppm 15 minutes.</p> <p><b>CA British Columbia Provincial (Canada, 5/2019).</b>                      TWA: 250 ppm 8 hours.                      STEL: 500 ppm 15 minutes.</p> <p><b>CA Ontario Provincial (Canada, 1/2018).</b>                      TWA: 250 ppm 8 hours.                      STEL: 500 ppm 15 minutes.</p> <p><b>CA Quebec Provincial (Canada, 1/2014).</b>                      TWAEV: 500 ppm 8 hours.                      TWAEV: 1190 mg/m<sup>3</sup> 8 hours.                      STEV: 1000 ppm 15 minutes.                      STEV: 2380 mg/m<sup>3</sup> 15 minutes.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>                      STEL: 750 ppm 15 minutes.                      TWA: 500 ppm 8 hours.</p>
Titanium dioxide	13463-67-7	<p><b>CA British Columbia Provincial (Canada, 5/2019).</b>                      TWA: 3 mg/m<sup>3</sup> 8 hours. Form: Respirable                      dust                      TWA: 10 mg/m<sup>3</sup> 8 hours. Form: Total dust</p> <p><b>CA Quebec Provincial (Canada, 1/2014).</b>                      TWAEV: 10 mg/m<sup>3</sup> 8 hours. Form: Total                      dust.</p> <p><b>CA Alberta Provincial (Canada, 6/2018).</b>                      8 hrs OEL: 10 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Ontario Provincial (Canada, 1/2018).</b>                      TWA: 10 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>                      STEL: 20 mg/m<sup>3</sup> 15 minutes.                      TWA: 10 mg/m<sup>3</sup> 8 hours.</p>

## Section 8. Exposure controls/personal protection

Normal butyl acetate	123-86-4	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>            15 min OEL: 200 ppm 15 minutes.            15 min OEL: 950 mg/m<sup>3</sup> 15 minutes.            8 hrs OEL: 150 ppm 8 hours.            8 hrs OEL: 713 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA British Columbia Provincial (Canada, 5/2019).</b>            TWA: 20 ppm 8 hours.</p> <p><b>CA Ontario Provincial (Canada, 1/2018).</b>            TWA: 150 ppm 8 hours.            STEL: 200 ppm 15 minutes.</p> <p><b>CA Quebec Provincial (Canada, 1/2014).</b>            TWAEV: 150 ppm 8 hours.            TWAEV: 713 mg/m<sup>3</sup> 8 hours.            STEV: 200 ppm 15 minutes.            STEV: 950 mg/m<sup>3</sup> 15 minutes.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>            STEL: 200 ppm 15 minutes.            TWA: 150 ppm 8 hours.</p>
Methyl propyl ketone	107-87-9	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>            8 hrs OEL: 200 ppm 8 hours.            15 min OEL: 250 ppm 15 minutes.            8 hrs OEL: 705 mg/m<sup>3</sup> 8 hours.            15 min OEL: 881 mg/m<sup>3</sup> 15 minutes.</p> <p><b>CA British Columbia Provincial (Canada, 5/2019).</b>            TWA: 150 ppm 8 hours.            STEL: 250 ppm 15 minutes.</p> <p><b>CA Ontario Provincial (Canada, 1/2018).</b>            STEL: 150 ppm 15 minutes.</p> <p><b>CA Quebec Provincial (Canada, 1/2014).</b>            TWAEV: 150 ppm 8 hours.            TWAEV: 530 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>            STEL: 250 ppm 15 minutes.            TWA: 200 ppm 8 hours.</p>
Xylene	1330-20-7	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>            8 hrs OEL: 100 ppm 8 hours.            15 min OEL: 651 mg/m<sup>3</sup> 15 minutes.            15 min OEL: 150 ppm 15 minutes.            8 hrs OEL: 434 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA British Columbia Provincial (Canada, 5/2019).</b>            TWA: 100 ppm 8 hours.            STEL: 150 ppm 15 minutes.</p> <p><b>CA Quebec Provincial (Canada, 1/2014).</b>            TWAEV: 100 ppm 8 hours.            TWAEV: 434 mg/m<sup>3</sup> 8 hours.            STEV: 150 ppm 15 minutes.            STEV: 651 mg/m<sup>3</sup> 15 minutes.</p> <p><b>CA Ontario Provincial (Canada, 1/2018).</b>            STEL: 150 ppm 15 minutes.            TWA: 100 ppm 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b></p>



## Section 8. Exposure controls/personal protection

Methyl isobutyl ketone

108-10-1

STEL: 150 ppm 15 minutes.  
TWA: 100 ppm 8 hours.

**CA Alberta Provincial (Canada, 6/2018).**

8 hrs OEL: 205 mg/m<sup>3</sup> 8 hours.

8 hrs OEL: 50 ppm 8 hours.

15 min OEL: 75 ppm 15 minutes.

15 min OEL: 307 mg/m<sup>3</sup> 15 minutes.

**CA British Columbia Provincial (Canada, 5/2019).**

TWA: 20 ppm 8 hours.

STEL: 75 ppm 15 minutes.

**CA Ontario Provincial (Canada, 1/2018).**

TWA: 20 ppm 8 hours.

STEL: 75 ppm 15 minutes.

**CA Quebec Provincial (Canada, 1/2014).**

TWAEV: 50 ppm 8 hours.

TWAEV: 205 mg/m<sup>3</sup> 8 hours.

STEV: 75 ppm 15 minutes.

STEV: 307 mg/m<sup>3</sup> 15 minutes.

**CA Saskatchewan Provincial (Canada, 7/2013).**

STEL: 75 ppm 15 minutes.

TWA: 50 ppm 8 hours.

Toluene

108-88-3

**CA Alberta Provincial (Canada, 6/2018).**

**Absorbed through skin.**

8 hrs OEL: 50 ppm 8 hours.

8 hrs OEL: 188 mg/m<sup>3</sup> 8 hours.

**CA British Columbia Provincial (Canada, 5/2019).**

TWA: 20 ppm 8 hours.

**CA Ontario Provincial (Canada, 1/2018).**

TWA: 20 ppm 8 hours.

**CA Quebec Provincial (Canada, 1/2014).**

**Absorbed through skin.**

TWAEV: 50 ppm 8 hours.

TWAEV: 188 mg/m<sup>3</sup> 8 hours.

**CA Saskatchewan Provincial (Canada,**

**7/2013). Absorbed through skin.**

STEL: 60 ppm 15 minutes.

TWA: 50 ppm 8 hours.

Kaolin

1332-58-7

**CA Alberta Provincial (Canada, 6/2018).**

8 hrs OEL: 2 mg/m<sup>3</sup> 8 hours. Form:

Respirable

**CA British Columbia Provincial (Canada, 5/2019).**

TWA: 2 mg/m<sup>3</sup> 8 hours. Form: Respirable

**CA Quebec Provincial (Canada, 1/2014).**

TWAEV: 5 mg/m<sup>3</sup> 8 hours. Form:

Respirable dust.

**CA Ontario Provincial (Canada, 1/2018).**

TWA: 2 mg/m<sup>3</sup> 8 hours. Form: Respirable fraction.

**CA Saskatchewan Provincial (Canada, 7/2013).**

STEL: 4 mg/m<sup>3</sup> 15 minutes. Form: respirable fraction

TWA: 2 mg/m<sup>3</sup> 8 hours. Form: respirable

## Section 8. Exposure controls/personal protection

Quartz	14808-60-7	<p>fraction  <b>CA British Columbia Provincial (Canada, 5/2019).</b>  TWA: 0.025 mg/m<sup>3</sup> 8 hours. Form: Respirable  <b>CA Quebec Provincial (Canada, 1/2014).</b>  TWAEV: 0.1 mg/m<sup>3</sup> 8 hours. Form: Respirable dust.  <b>CA Ontario Provincial (Canada, 1/2018).</b>  TWA: 0.1 mg/m<sup>3</sup> 8 hours. Form: Respirable fraction.  <b>CA Alberta Provincial (Canada, 6/2018).</b>  8 hrs OEL: 0.025 mg/m<sup>3</sup> 8 hours. Form: Respirable particulate  <b>CA Saskatchewan Provincial (Canada, 7/2013).</b>  TWA: 0.05 mg/m<sup>3</sup> 8 hours. Form: respirable fraction</p>
Ethylbenzene	100-41-4	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>  8 hrs OEL: 100 ppm 8 hours.  8 hrs OEL: 434 mg/m<sup>3</sup> 8 hours.  15 min OEL: 543 mg/m<sup>3</sup> 15 minutes.  15 min OEL: 125 ppm 15 minutes.  <b>CA British Columbia Provincial (Canada, 5/2019).</b>  TWA: 20 ppm 8 hours.  <b>CA Ontario Provincial (Canada, 1/2018).</b>  TWA: 20 ppm 8 hours.  <b>CA Quebec Provincial (Canada, 1/2014).</b>  TWAEV: 100 ppm 8 hours.  TWAEV: 434 mg/m<sup>3</sup> 8 hours.  STEV: 125 ppm 15 minutes.  STEV: 543 mg/m<sup>3</sup> 15 minutes.  <b>CA Saskatchewan Provincial (Canada, 7/2013).</b>  STEL: 125 ppm 15 minutes.  TWA: 100 ppm 8 hours.</p>
Carbon black	1333-86-4	<p><b>CA British Columbia Provincial (Canada, 5/2019).</b>  TWA: 3 mg/m<sup>3</sup> 8 hours. Form: Inhalable  <b>CA Ontario Provincial (Canada, 1/2018).</b>  TWA: 3 mg/m<sup>3</sup> 8 hours. Form: Inhalable fraction.  <b>CA Alberta Provincial (Canada, 6/2018).</b>  8 hrs OEL: 3.5 mg/m<sup>3</sup> 8 hours.  <b>CA Quebec Provincial (Canada, 1/2014).</b>  TWAEV: 3.5 mg/m<sup>3</sup> 8 hours.  <b>CA Saskatchewan Provincial (Canada, 7/2013).</b>  STEL: 7 mg/m<sup>3</sup> 15 minutes.  TWA: 3.5 mg/m<sup>3</sup> 8 hours.</p>

### Occupational exposure limits (Mexico)

## Section 8. Exposure controls/personal protection

Ingredient name	CAS #	Exposure limits
Acetone	67-64-1	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 500 ppm 8 hours. STEL: 750 ppm 15 minutes.
n-Butyl Acetate	123-86-4	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 150 ppm 8 hours. STEL: 200 ppm 15 minutes.
Methyl n-Propyl Ketone	107-87-9	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 100 ppm 8 hours. STEL: 700 ppm 15 minutes.
Toluene	108-88-3	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 20 ppm 8 hours.
Ethylbenzene	100-41-4	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 20 ppm 8 hours.

**Appropriate engineering controls** : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

**Environmental exposure controls** : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

### Individual protection measures

**Hygiene measures** : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Contaminated work clothing should not be allowed out of the workplace. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

**Eye/face protection** : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: chemical splash goggles.

### Skin protection

**Hand protection** : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.

**Body protection** : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear anti-static protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.

**Other skin protection** : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

## Section 8. Exposure controls/personal protection

**Respiratory protection** : Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use.

## Section 9. Physical and chemical properties

### Appearance

**Physical state** : Liquid.  
**Color** : Not available.  
**Odor** : Not available.  
**Odor threshold** : Not available.  
**pH** : Not available.  
**Melting point/freezing point** : Not available.  
**Boiling point/boiling range** : 55°C (131°F)  
**Flash point** : Closed cup: 4°C (39.2°F) [Pensky-Martens Closed Cup]  
**Evaporation rate** : 5.6 (butyl acetate = 1)  
**Flammability (solid, gas)** : Not available.  
**Lower and upper explosive (flammable) limits** : Lower: 1.3%  
Upper: 13.1%  
**Vapor pressure** : 24 kPa (180 mm Hg) [at 20°C]  
**Vapor density** : 2 [Air = 1]  
**Relative density** : 1.44  
**Solubility** : Not available.  
**Partition coefficient: n-butanol/water** : Not available.  
**Auto-ignition temperature** : Not available.  
**Decomposition temperature** : Not available.  
**Viscosity** : Kinematic (40°C (104°F)): >0.205 cm<sup>2</sup>/s (>20.5 cSt)  
**Molecular weight** : Not applicable.  
**Aerosol product**  
**Heat of combustion** : 8.832 kJ/g

## Section 10. Stability and reactivity

**Reactivity** : No specific test data related to reactivity available for this product or its ingredients.

**Chemical stability** : The product is stable.

**Possibility of hazardous reactions** : Under normal conditions of storage and use, hazardous reactions will not occur.

**Conditions to avoid** : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.

**Incompatible materials** : Reactive or incompatible with the following materials:  
oxidizing materials

## Section 10. Stability and reactivity

**Hazardous decomposition products** : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

## Section 11. Toxicological information

### Information on toxicological effects

#### Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Acetone	LD50 Oral	Rat	5800 mg/kg	-
n-Butyl Acetate	LD50 Dermal	Rabbit	>17600 mg/kg	-
	LD50 Oral	Rat	10768 mg/kg	-
Methyl n-Propyl Ketone	LD50 Dermal	Rabbit	6500 mg/kg	-
	LD50 Oral	Rat	1600 mg/kg	-
2-methoxy-1-methylethyl acetate	LD50 Dermal	Rabbit	>5 g/kg	-
	LD50 Oral	Rat	8532 mg/kg	-
Organosilane Ester	LD50 Oral	Rat	7.01 g/kg	-
Xylene, mixed isomers	LC50 Inhalation Gas.	Rat	5000 ppm	4 hours
	LD50 Oral	Rat	4300 mg/kg	-
Methyl Isobutyl Ketone	LD50 Oral	Rat	2080 mg/kg	-
Toluene	LC50 Inhalation Vapor	Rat	49 g/m <sup>3</sup>	4 hours
	LD50 Oral	Rat	636 mg/kg	-
1,2,4-Trimethylbenzene	LC50 Inhalation Vapor	Rat	18000 mg/m <sup>3</sup>	4 hours
	LD50 Oral	Rat	5 g/kg	-
Ethylbenzene	LD50 Dermal	Rabbit	>5000 mg/kg	-
	LD50 Oral	Rat	3500 mg/kg	-
Carbon Black	LD50 Oral	Rat	>15400 mg/kg	-

#### Irritation/Corrosion

Product/ingredient name	Result	Species	Score	Exposure	Observation
Talc	Skin - Mild irritant	Human	-	72 hours 300 ug l	-
Acetone	Eyes - Mild irritant	Human	-	186300 ppm	-
	Eyes - Mild irritant	Rabbit	-	10 UI	-
	Eyes - Moderate irritant	Rabbit	-	24 hours 20 mg	-
	Eyes - Severe irritant	Rabbit	-	20 mg	-
	Skin - Mild irritant	Rabbit	-	24 hours 500 mg	-
Titanium Dioxide	Skin - Mild irritant	Rabbit	-	395 mg	-
	Skin - Mild irritant	Human	-	72 hours 300 ug l	-
n-Butyl Acetate	Eyes - Moderate irritant	Rabbit	-	100 mg	-
	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
Methyl n-Propyl Ketone	Skin - Mild irritant	Rabbit	-	405 mg	-
Organosilane Ester	Eyes - Mild irritant	Rabbit	-	100 mg	-
	Skin - Mild irritant	Rabbit	-	500 mg	-
Xylene, mixed isomers	Eyes - Mild irritant	Rabbit	-	87 mg	-
	Eyes - Severe irritant	Rabbit	-	24 hours 5 mg	-
	Skin - Mild irritant	Rat	-	8 hours 60 UI	-
	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
Methyl Isobutyl Ketone	Skin - Moderate irritant	Rabbit	-	100 %	-
	Eyes - Moderate irritant	Rabbit	-	24 hours 100 UI	-

Date of issue/Date of revision : 5/19/2020 Date of previous issue : 4/3/2020 Version : 17.02 15/23

E2A933 3.5 VOC Epoxy Primer (Part A)  
Gray

SHW-85-NA-GHS-CA

## Section 11. Toxicological information

Toluene	Eyes - Severe irritant	Rabbit	-	40 mg	-
	Skin - Mild irritant	Rabbit	-	24 hours 500 mg	-
	Eyes - Mild irritant	Rabbit	-	0.5 minutes 100 mg	-
	Eyes - Mild irritant	Rabbit	-	870 ug	-
	Eyes - Severe irritant	Rabbit	-	24 hours 2 mg	-
	Skin - Mild irritant	Pig	-	24 hours 250 UI	-
Ethylbenzene	Skin - Mild irritant	Rabbit	-	435 mg	-
	Skin - Moderate irritant	Rabbit	-	24 hours 20 mg	-
	Skin - Moderate irritant	Rabbit	-	500 mg	-
	Eyes - Severe irritant	Rabbit	-	500 mg	-
	Skin - Mild irritant	Rabbit	-	24 hours 15 mg	-

### Sensitization

Not available.

### Mutagenicity

Not available.

### Carcinogenicity

Not available.

### Classification

Product/ingredient name	OSHA	IARC	NTP
Talc	-	3	-
Titanium Dioxide	-	2B	-
Xylene, mixed isomers	-	3	-
Methyl Isobutyl Ketone	-	2B	-
Toluene	-	3	-
Crystalline Silica, respirable powder	-	1	Known to be a human carcinogen.
Ethylbenzene	-	2B	-
Carbon Black	-	2B	-

### Reproductive toxicity

Not available.

### Teratogenicity

Not available.

### Specific target organ toxicity (single exposure)

Name	Category	Route of exposure	Target organs
Acetone	Category 3 Category 3	Not applicable. Not applicable.	Narcotic effects Respiratory tract irritation
n-Butyl Acetate	Category 3	Not applicable.	Narcotic effects
Methyl n-Propyl Ketone	Category 3 Category 3	Not applicable. Not applicable.	Narcotic effects Respiratory tract irritation
2-methoxy-1-methylethyl acetate	Category 3	Not applicable.	Narcotic effects
Xylene, mixed isomers	Category 3	Not applicable.	Respiratory tract irritation

## Section 11. Toxicological information

Med. Aliphatic Hydrocarbon Solvent	Category 3 Category 3	Not applicable. Not applicable.	Narcotic effects Respiratory tract irritation
Methyl Isobutyl Ketone	Category 3 Category 3	Not applicable. Not applicable.	Narcotic effects Respiratory tract irritation
Toluene	Category 3 Category 3	Not applicable. Not applicable.	Narcotic effects Respiratory tract irritation
1,2,4-Trimethylbenzene	Category 3	Not applicable.	Respiratory tract irritation
Ethylbenzene	Category 3 Category 3	Not applicable. Not applicable.	Narcotic effects Respiratory tract irritation

### Specific target organ toxicity (repeated exposure)

Name	Category	Route of exposure	Target organs
Talc	Category 1	Inhalation	lungs
Acetone	Category 2	Not determined	Not determined
Methyl n-Propyl Ketone	Category 2	Not determined	Not determined
Xylene, mixed isomers	Category 2	Not determined	Not determined
Med. Aliphatic Hydrocarbon Solvent	Category 1	Not determined	Not determined
Methyl Isobutyl Ketone	Category 2	Not determined	Not determined
Toluene	Category 2	Not determined	Not determined
Crystalline Silica, respirable powder	Category 1	Inhalation	Not determined
Ethylbenzene	Category 2	Not determined	Not determined

### Aspiration hazard

Name	Result
Xylene, mixed isomers	ASPIRATION HAZARD - Category 1
Med. Aliphatic Hydrocarbon Solvent	ASPIRATION HAZARD - Category 1
Toluene	ASPIRATION HAZARD - Category 1
1,2,4-Trimethylbenzene	ASPIRATION HAZARD - Category 1
Ethylbenzene	ASPIRATION HAZARD - Category 1

**Information on the likely routes of exposure** : Not available.

### Potential acute health effects

- Eye contact** : Causes serious eye irritation.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness.
- Skin contact** : Causes skin irritation. May cause an allergic skin reaction.
- Ingestion** : Can cause central nervous system (CNS) depression.

### Symptoms related to the physical, chemical and toxicological characteristics

- Eye contact** : Adverse symptoms may include the following:  
 pain or irritation  
 watering  
 redness

## Section 11. Toxicological information

- Inhalation** : Adverse symptoms may include the following:  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations
- Skin contact** : Adverse symptoms may include the following:  
irritation  
redness  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations
- Ingestion** : Adverse symptoms may include the following:  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations

### Delayed and immediate effects and also chronic effects from short and long term exposure

#### Short term exposure

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.

#### Long term exposure

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.

#### Potential chronic health effects

Not available.

- General** : Causes damage to organs through prolonged or repeated exposure. Once sensitized, a severe allergic reaction may occur when subsequently exposed to very low levels.
- Carcinogenicity** : May cause cancer. Risk of cancer depends on duration and level of exposure.
- Mutagenicity** : No known significant effects or critical hazards.
- Teratogenicity** : Suspected of damaging the unborn child.
- Developmental effects** : No known significant effects or critical hazards.
- Fertility effects** : No known significant effects or critical hazards.

### Numerical measures of toxicity

#### Acute toxicity estimates

Route	ATE value
Oral	26376.77 mg/kg



## Section 12. Ecological information

### Toxicity

Product/ingredient name	Result	Species	Exposure
Barium Sulfate	Acute EC50 634 mg/l Fresh water	Crustaceans - Cypris subglobosa	48 hours
	Acute EC50 32 mg/l Fresh water	Daphnia - Daphnia magna	48 hours
Acetone	Acute EC50 7200000 µg/l Fresh water	Algae - Selenastrum sp.	96 hours
	Acute LC50 6000000 µg/l Fresh water	Crustaceans - Gammarus pulex	48 hours
	Acute LC50 6900 mg/l Fresh water	Daphnia - Daphnia magna	48 hours
	Acute LC50 5600 ppm Fresh water	Fish - Poecilia reticulata	96 hours
	Chronic NOEC 4.95 mg/l Marine water	Algae - Ulva pertusa	96 hours
	Chronic NOEC 0.016 ml/L Fresh water	Crustaceans - Daphniidae	21 days
	Chronic NOEC 0.1 ml/L Fresh water	Daphnia - Daphnia magna - Neonate	21 days
	Chronic NOEC 5 µg/l Marine water	Fish - Gasterosteus aculeatus - Larvae	42 days
Titanium Dioxide	Acute LC50 >1000000 µg/l Marine water	Fish - Fundulus heteroclitus	96 hours
	Acute LC50 32 mg/l Marine water	Crustaceans - Artemia salina	48 hours
n-Butyl Acetate	Acute LC50 18000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
	Acute LC50 1240000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
Methyl n-Propyl Ketone	Acute LC50 8500 µg/l Marine water	Crustaceans - Palaemonetes pugio	48 hours
	Acute LC50 13400 µg/l Fresh water	Fish - Pimephales promelas	96 hours
Methyl Isobutyl Ketone	Acute LC50 505000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
	Chronic NOEC 78 mg/l Fresh water	Daphnia - Daphnia magna	21 days
	Chronic NOEC 168 mg/l Fresh water	Fish - Pimephales promelas - Embryo	33 days
Toluene	Acute EC50 12500 µg/l Fresh water	Algae - Pseudokirchneriella subcapitata	72 hours
	Acute EC50 11600 µg/l Fresh water	Crustaceans - Gammarus pseudolimnaeus - Adult	48 hours
	Acute EC50 6000 µg/l Fresh water	Daphnia - Daphnia magna - Juvenile (Fledgling, Hatchling, Weanling)	48 hours
1,2,4-Trimethylbenzene	Acute LC50 5500 µg/l Fresh water	Fish - Oncorhynchus kisutch - Fry	96 hours
	Chronic NOEC 1000 µg/l Fresh water	Daphnia - Daphnia magna	21 days
	Acute LC50 4910 µg/l Marine water	Crustaceans - Elasmopus pecteniscrus - Adult	48 hours
Ethylbenzene	Acute LC50 7720 µg/l Fresh water	Fish - Pimephales promelas	96 hours
	Acute EC50 4600 µg/l Fresh water	Algae - Pseudokirchneriella subcapitata	72 hours
	Acute EC50 3600 µg/l Fresh water	Algae - Pseudokirchneriella subcapitata	96 hours
	Acute EC50 6.53 mg/l Marine water	Crustaceans - Artemia sp. - Nauplii	48 hours
	Acute EC50 2.93 mg/l Fresh water	Daphnia - Daphnia magna - Neonate	48 hours
	Acute LC50 4200 µg/l Fresh water	Fish - Oncorhynchus mykiss	96 hours

### Persistence and degradability

Product/ingredient name	Aquatic half-life	Photolysis	Biodegradability
Acetone	-	-	Readily
n-Butyl Acetate	-	-	Readily
Xylene, mixed isomers	-	-	Readily
Methyl Isobutyl Ketone	-	-	Readily
Toluene	-	-	Readily
Ethylbenzene	-	-	Readily

## Section 12. Ecological Information

### Bioaccumulative potential

Product/ingredient name	LogP <sub>ow</sub>	BCF	Potential
Xylene, mixed isomers	-	8.1 to 25.9	low
Toluene	-	90	low
1,2,4-Trimethylbenzene	-	243	low

### Mobility in soil







Soil/water partition coefficient (K<sub>oc</sub>) : Not available.

Other adverse effects : No known significant effects or critical hazards.

## Section 13. Disposal considerations

**Disposal methods** : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

## Section 14. Transport information

	DOT Classification	TDG Classification	Mexico Classification	IATA	IMDG
UN number	UN1263	UN1263	UN1263	UN1263	UN1263
UN proper shipping name	PAINT	PAINT	PAINT	PAINT	PAINT. Marine pollutant (Phenol, polymer with formaldehyde, glycidylether, Zinc Phosphate)
Transport hazard class(es)	3 	3 	3 	3 	3  
Packing group	II	II	II	II	II
Environmental hazards	No.	No.	No.	Yes. The environmentally hazardous substance mark is not required.	Yes.

## Section 14. Transport information

Additional information	-	Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.18-2.19 (Class 3).	-	The environmentally hazardous substance mark may appear if required by other transportation regulations.	The marine pollutant mark is not required when transported in sizes of ≤5 L or ≤5 kg. <b>Emergency schedules F-E, S-E</b>
	<b>ERG No.</b> 128	<b>ERG No.</b> 128	<b>ERG No.</b> 128		

**Special precautions for user** : Multi-modal shipping descriptions are provided for informational purposes and do not consider container sizes. The presence of a shipping description for a particular mode of transport (sea, air, etc.), does not indicate that the product is packaged suitably for that mode of transport. All packaging must be reviewed for suitability prior to shipment, and compliance with the applicable regulations is the sole responsibility of the person offering the product for transport. People loading and unloading dangerous goods must be trained on all of the risks deriving from the substances and on all actions in case of emergency situations.

**Transport in bulk according to Annex II of MARPOL and the IBC Code** : Not available.

**Proper shipping name** : Not available.  
**Ship type** : Not available.  
**Pollution category** : Not available.

## Section 15. Regulatory information

### International regulations

**International lists** :

- Australia inventory (AICS)**: Not determined.
- China inventory (IECSC)**: Not determined.
- Japan inventory (ENCS)**: Not determined.
- Japan inventory (ISHL)**: Not determined.
- Korea inventory (KECI)**: Not determined.
- New Zealand Inventory of Chemicals (NZIoC)**: Not determined.
- Philippines inventory (PICCS)**: Not determined.
- Taiwan Chemical Substances Inventory (TCSI)**: Not determined.
- Thailand inventory**: Not determined.
- Turkey inventory**: Not determined.
- Vietnam inventory**: Not determined.

## Section 16. Other information

### Hazardous Material Information System (U.S.A.)

Health	*	3
Flammability		3
Physical hazards		0

The customer is responsible for determining the PPE code for this material. For more information on HMIS® Personal Protective Equipment (PPE) codes, consult the HMIS® Implementation Manual.

## Section 16. Other information

Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks. Although HMIS® ratings and the associated label are not required on SDSs or products leaving a facility under 29 CFR 1910.1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered trademark and service mark of the American Coatings Association, Inc.

### Procedure used to derive the classification

Classification	Justification
FLAMMABLE LIQUIDS - Category 2	On basis of test data
SKIN CORROSION/IRRITATION - Category 2	Calculation method
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A	Calculation method
SKIN SENSITIZATION - Category 1	Calculation method
CARCINOGENICITY - Category 1A	Calculation method
TOXIC TO REPRODUCTION (Unborn child) - Category 2	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) (lungs) - Category 1	Calculation method

### History

Date of printing : 5/19/2020

Date of issue/Date of revision : 5/19/2020

Date of previous issue : 4/3/2020

Version : 17.02

Key to abbreviations : ATE = Acute Toxicity Estimate  
BCF = Bioconcentration Factor  
GHS = Globally Harmonized System of Classification and Labelling of Chemicals  
IATA = International Air Transport Association  
IBC = Intermediate Bulk Container  
IMDG = International Maritime Dangerous Goods  
LogPow = logarithm of the octanol/water partition coefficient  
MARPOL = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)  
N/A = Not available  
SGG = Segregation Group  
UN = United Nations

☑ Indicates information that has changed from previously issued version.

### Notice to reader

It is recommended that each customer or recipient of this Safety Data Sheet (SDS) study it carefully and consult resources, as necessary or appropriate, to become aware of and understand the data contained in this SDS and any hazards associated with the product. This information is provided in good faith and believed to be accurate as of the effective date herein. However, no warranty, express or implied, is given. The information presented here applies only to the product as shipped. The addition of any material can change the composition, hazards and risks of the product. Products shall not be repackaged, modified, or tinted except as specifically instructed by the manufacturer, including but not limited to the incorporation of products not specified by the manufacturer, or the use or addition of products in proportions not specified by the manufacturer. Regulatory requirements are subject to change and may differ between various locations and jurisdictions. The customer/buyer/user is responsible to ensure that his activities comply with all country, federal, state, provincial or local laws. The conditions for use of the product are not under the control of the manufacturer; the customer/buyer/user is responsible to determine the conditions necessary for the safe use of this product. The customer/buyer/user should not use the product for any purpose other than the purpose shown in the applicable section of this SDS without first referring to the supplier and obtaining written handling instructions. Due to the proliferation of sources for information such as manufacturer-specific SDS, the manufacturer cannot be responsible for SDSs obtained from any other source.



# SAFETY DATA SHEET

V6V943

## Section 1. Identification

**Product name** : Epoxy Primer Activator (Part B)

**Product code** : V6V943

**Other means of identification** : Not available.

**Product type** : Liquid.

**Relevant identified uses of the substance or mixture and uses advised against**

Paint or paint related material.

**Manufacturer** : The Sherwin-Williams Company  
4440 Warrensville Center Road  
Warrensville Heights, OH 44128

**National contact** : Sherwin-Williams Canada Inc.  
180 Brunel Road  
Mississauga, Ontario L4Z 1T5 Canada

**Emergency telephone number of the company** : US / Canada: (800) 424-9300  
Mexico: (52) 55-4160-8800 / (52) 55-4160-8819 Monday to Friday from 8:30 a.m. to 5:30 p.m.

**Product Information Telephone Number** : US / Canada: (800) 798-5872  
Mexico: 01-800-022-7926

**Regulatory Information Telephone Number** : US / Canada: (216) 566-2902  
Mexico: (52) 55-4160-8819 / (52) 55-4160-8806

**Transportation Emergency Telephone Number** : US / Canada: (800) 424-9300  
Mexico: SETIQ 01-800-00-214-00 / (52) 55-5559-1588 24 hours / 365 days a year

## Section 2. Hazards identification

**Classification of the substance or mixture** : FLAMMABLE LIQUIDS - Category 3  
SKIN CORROSION/IRRITATION - Category 1  
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 1  
RESPIRATORY SENSITIZATION - Category 1  
SKIN SENSITIZATION - Category 1  
CARCINOGENICITY - Category 2  
TOXIC TO REPRODUCTION (Unborn child) - Category 1B  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3  
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 2  
Percentage of the mixture consisting of ingredient(s) of unknown acute oral toxicity: 38.4%  
Percentage of the mixture consisting of ingredient(s) of unknown acute dermal toxicity: 51.2%  
Percentage of the mixture consisting of ingredient(s) of unknown acute inhalation toxicity: 38.4%

### GHS label elements

## Section 2. Hazards identification

Hazard pictograms :



Signal word :

Danger

Hazard statements :

Flammable liquid and vapor.  
Causes severe skin burns and eye damage.  
May cause allergy or asthma symptoms or breathing difficulties if inhaled.  
May cause an allergic skin reaction.  
May damage the unborn child.  
Suspected of causing cancer.  
May cause drowsiness or dizziness.  
May cause damage to organs through prolonged or repeated exposure.

### Precautionary statements

Prevention :

Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Wear protective gloves. Wear eye or face protection. Wear protective clothing. Wear respiratory protection. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating, lighting and all material-handling equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Keep container tightly closed. Use only outdoors or in a well-ventilated area. Do not breathe vapor. Wash hands thoroughly after handling. Contaminated work clothing must not be allowed out of the workplace.

Response :

Get medical attention if you feel unwell. IF exposed or concerned: Get medical attention. IF INHALED: If breathing is difficult, remove person to fresh air and keep comfortable for breathing. Immediately call a POISON CENTER or physician. If experiencing respiratory symptoms: Call a POISON CENTER or physician. IF SWALLOWED: Immediately call a POISON CENTER or physician. Rinse mouth. Do NOT induce vomiting. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water or shower. Wash contaminated clothing before reuse. Immediately call a POISON CENTER or physician. IF ON SKIN: Wash with plenty of soap and water. Wash contaminated clothing before reuse. If skin irritation or rash occurs: Get medical attention. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Immediately call a POISON CENTER or physician.

Storage :

Store locked up. Store in a well-ventilated place. Keep cool.

Disposal :

Dispose of contents and container in accordance with all local, regional, national and international regulations.

Supplemental label elements

DELAYED EFFECTS FROM LONG TERM OVEREXPOSURE. Contains solvents which can cause permanent brain and nervous system damage. Intentional misuse by deliberately concentrating and inhaling the contents can be harmful or fatal. WARNING: This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm. FOR PROFESSIONAL USE ONLY. This product must be mixed with other components before use. Before opening the packages, READ AND FOLLOW WARNING LABELS ON ALL COMPONENTS. Please refer to the SDS for additional information. Keep out of reach of children. Do not transfer contents to other containers for storage.

Hazards not otherwise classified

: None known.

## Section 3. Composition/information on ingredients

Substance/mixture : Mixture  
Other means of identification : Not available.

### CAS number/other identifiers

Ingredient name	% by weight	CAS number
Polyketamine	29.59	1612162-82-9
2-methoxy-1-methylethyl acetate	27.76	108-65-6
n-Butyl Acetate	15.31	123-86-4
Methyl Isobutyl Ketone	12.81	108-10-1
Ketamine	8.84	1612145-88-6
2-Methoxy-1-Propanol Acetate	0.14	70657-70-4
Ethylenediamine	0.11	107-15-3

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

**There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health and hence require reporting in this section.**

Occupational exposure limits, if available, are listed in Section 8.

## Section 4. First aid measures

### Description of necessary first aid measures

- Eye contact** : Get medical attention immediately. Call a poison center or physician. Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Chemical burns must be treated promptly by a physician.
- Inhalation** : Get medical attention immediately. Call a poison center or physician. Remove victim to fresh air and keep at rest in a position comfortable for breathing. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband. In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours. In the event of any complaints or symptoms, avoid further exposure.
- Skin contact** : Get medical attention immediately. Call a poison center or physician. Wash with plenty of soap and water. Remove contaminated clothing and shoes. Wash contaminated clothing thoroughly with water before removing it, or wear gloves. Continue to rinse for at least 10 minutes. Chemical burns must be treated promptly by a physician. In the event of any complaints or symptoms, avoid further exposure. Wash clothing before reuse. Clean shoes thoroughly before reuse.
- Ingestion** : Get medical attention immediately. Call a poison center or physician. Wash out mouth with water. Remove dentures if any. Remove victim to fresh air and keep at rest in a position comfortable for breathing. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Chemical burns must be treated promptly by a physician. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

### Most important symptoms/effects, acute and delayed

Date of issue/Date of revision : 5/4/2020 Date of previous issue : 11/28/2019 Version : 11 3/16  
V6V943 Epoxy Primer Activator (Part B) SHW-85-NA-GHS-CA



## Section 4. First aid measures

### Potential acute health effects

- Eye contact** : Causes serious eye damage.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause allergy or asthma symptoms or breathing difficulties if inhaled.
- Skin contact** : Causes severe burns. May cause an allergic skin reaction.
- Ingestion** : Can cause central nervous system (CNS) depression.

### Over-exposure signs/symptoms

- Eye contact** : Adverse symptoms may include the following:  
pain  
watering  
redness
- Inhalation** : Adverse symptoms may include the following:  
wheezing and breathing difficulties  
asthma  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations
- Skin contact** : Adverse symptoms may include the following:  
pain or irritation  
redness  
blistering may occur  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations
- Ingestion** : Adverse symptoms may include the following:  
stomach pains  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations

### Indication of immediate medical attention and special treatment needed, if necessary

- Notes to physician** : In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
- Specific treatments** : No specific treatment.
- Protection of first-aiders** : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

See toxicological information (Section 11)

## Section 5. Fire-fighting measures

### Extinguishing media

**Suitable extinguishing media** : Use dry chemical, CO<sub>2</sub>, water spray (fog) or foam.

**Unsuitable extinguishing media** : Do not use water jet.

**Specific hazards arising from the chemical** : Flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Vapors may accumulate in low or confined areas or travel a considerable distance to a source of ignition and flash back.

**Hazardous thermal decomposition products** : Decomposition products may include the following materials:  
carbon dioxide  
carbon monoxide  
nitrogen oxides

**Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.

**Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

## Section 6. Accidental release measures

### Personal precautions, protective equipment and emergency procedures

**For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Do not breathe vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.

**For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

**Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

### Methods and materials for containment and cleaning up

**Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.

**Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

## Section 7. Handling and storage

### Precautions for safe handling

- Protective measures** : Put on appropriate personal protective equipment (see Section 8). Persons with a history of skin sensitization problems or asthma, allergies or chronic or recurrent respiratory disease should not be employed in any process in which this product is used. Avoid exposure - obtain special instructions before use. Avoid exposure during pregnancy. Do not handle until all safety precautions have been read and understood. Do not get in eyes or on skin or clothing. Do not breathe vapor or mist. Do not ingest. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.
- Advice on general occupational hygiene** : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

- Conditions for safe storage, including any incompatibilities** : Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use.

## Section 8. Exposure controls/personal protection

### Control parameters

#### Occupational exposure limits (OSHA United States)

Ingredient name	CAS #	Exposure limits
Polyketamine	1612162-82-9	None.
2-methoxy-1-methylethyl acetate	108-65-6	<b>AIHA WEEL (United States, 7/2018).</b> TWA: 50 ppm 8 hours.
n-Butyl Acetate	123-86-4	<b>NIOSH REL (United States, 10/2016).</b> TWA: 150 ppm 10 hours. TWA: 710 mg/m <sup>3</sup> 10 hours. STEL: 200 ppm 15 minutes. STEL: 950 mg/m <sup>3</sup> 15 minutes. <b>OSHA PEL (United States, 5/2018).</b> TWA: 150 ppm 8 hours. TWA: 710 mg/m <sup>3</sup> 8 hours. <b>ACGIH TLV (United States, 3/2019).</b> STEL: 150 ppm 15 minutes. TWA: 50 ppm 8 hours.
Methyl Isobutyl Ketone	108-10-1	<b>ACGIH TLV (United States, 3/2019).</b> TWA: 20 ppm 8 hours. STEL: 75 ppm 15 minutes. <b>NIOSH REL (United States, 10/2016).</b> TWA: 50 ppm 10 hours. TWA: 205 mg/m <sup>3</sup> 10 hours. STEL: 75 ppm 15 minutes.

## Section 8. Exposure controls/personal protection

<p>Ketamine 2-Methoxy-1-Propanol Acetate Ethylenediamine</p>	<p>1612145-88-6 70657-70-4 107-15-3</p>	<p>STEL: 300 mg/m<sup>3</sup> 15 minutes.  <b>OSHA PEL (United States, 5/2018).</b>  TWA: 100 ppm 8 hours.  TWA: 410 mg/m<sup>3</sup> 8 hours.  None.  None.  <b>ACGIH TLV (United States, 3/2019).</b>  <b>Absorbed through skin.</b>  TWA: 10 ppm 8 hours.  <b>NIOSH REL (United States, 10/2016).</b>  TWA: 10 ppm 10 hours.  TWA: 25 mg/m<sup>3</sup> 10 hours.  <b>OSHA PEL (United States, 5/2018).</b>  TWA: 10 ppm 8 hours.  TWA: 25 mg/m<sup>3</sup> 8 hours.</p>
--	---	--

### Occupational exposure limits (Canada)

Ingredient name	CAS #	Exposure limits
Normal butyl acetate	123-86-4	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>  15 min OEL: 200 ppm 15 minutes.  15 min OEL: 950 mg/m<sup>3</sup> 15 minutes.  8 hrs OEL: 150 ppm 8 hours.  8 hrs OEL: 713 mg/m<sup>3</sup> 8 hours.  <b>CA British Columbia Provincial (Canada, 5/2019).</b>  TWA: 20 ppm 8 hours.  <b>CA Ontario Provincial (Canada, 1/2018).</b>  TWA: 150 ppm 8 hours.  STEL: 200 ppm 15 minutes.  <b>CA Quebec Provincial (Canada, 1/2014).</b>  TWAEV: 150 ppm 8 hours.  TWAEV: 713 mg/m<sup>3</sup> 8 hours.  STEV: 200 ppm 15 minutes.  STEV: 950 mg/m<sup>3</sup> 15 minutes.  <b>CA Saskatchewan Provincial (Canada, 7/2013).</b>  STEL: 200 ppm 15 minutes.  TWA: 150 ppm 8 hours.</p>
Methyl isobutyl ketone	108-10-1	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>  8 hrs OEL: 205 mg/m<sup>3</sup> 8 hours.  8 hrs OEL: 50 ppm 8 hours.  15 min OEL: 75 ppm 15 minutes.  15 min OEL: 307 mg/m<sup>3</sup> 15 minutes.  <b>CA British Columbia Provincial (Canada, 5/2019).</b>  TWA: 20 ppm 8 hours.  STEL: 75 ppm 15 minutes.  <b>CA Ontario Provincial (Canada, 1/2018).</b>  TWA: 20 ppm 8 hours.  STEL: 75 ppm 15 minutes.  <b>CA Quebec Provincial (Canada, 1/2014).</b>  TWAEV: 50 ppm 8 hours.  TWAEV: 205 mg/m<sup>3</sup> 8 hours.  STEV: 75 ppm 15 minutes.  STEV: 307 mg/m<sup>3</sup> 15 minutes.  <b>CA Saskatchewan Provincial (Canada,</b></p>

## Section 8. Exposure controls/personal protection

2-Methoxy-1-Propanol Acetate	70657-70-4	7/2013). STEL: 75 ppm 15 minutes. TWA: 50 ppm 8 hours. <b>CA British Columbia Provincial (Canada, 5/2019).</b> TWA: 20 ppm 8 hours. STEL: 40 ppm 15 minutes. <b>CA Alberta Provincial (Canada, 6/2018).</b> <b>Absorbed through skin.</b> 8 hrs OEL: 25 mg/m <sup>3</sup> 8 hours. 8 hrs OEL: 10 ppm 8 hours. <b>CA British Columbia Provincial (Canada, 5/2019). Absorbed through skin.</b> TWA: 10 ppm 8 hours. <b>CA Ontario Provincial (Canada, 1/2018).</b> <b>Absorbed through skin.</b> TWA: 10 ppm 8 hours. <b>CA Quebec Provincial (Canada, 1/2014).</b> <b>Absorbed through skin. Skin sensitizer.</b> TWAEV: 10 ppm 8 hours. TWAEV: 25 mg/m <sup>3</sup> 8 hours. <b>CA Saskatchewan Provincial (Canada, 7/2013). Absorbed through skin.</b> STEL: 15 ppm 15 minutes. TWA: 10 ppm 8 hours.
1,2-Diaminoethane	107-15-3	

### Occupational exposure limits (Mexico)

Ingredient name	CAS #	Exposure limits
n-Butyl Acetate	123-86-4	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 150 ppm 8 hours. STEL: 200 ppm 15 minutes.
Methyl Isobutyl Ketone	108-10-1	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 50 ppm 8 hours. STEL: 75 ppm 15 minutes.

**Appropriate engineering controls** : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

**Environmental exposure controls** : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

### Individual protection measures

**Hygiene measures** : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Contaminated work clothing should not be allowed out of the workplace. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

## Section 8. Exposure controls/personal protection

- Eye/face protection** : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: chemical splash goggles and/or face shield. If inhalation hazards exist, a full-face respirator may be required instead.
- Skin protection**
- Hand protection** : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.
- Body protection** : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear anti-static protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.
- Other skin protection** : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.
- Respiratory protection** : Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use.

## Section 9. Physical and chemical properties

### Appearance

- Physical state** : Liquid.
- Color** : Not available.
- Odor** : Not available.
- Odor threshold** : Not available.
- pH** : Not available.
- Melting point/freezing point** : Not available.
- Boiling point/boiling range** : 113°C (235.4°F)
- Flash point** : Closed cup: 31°C (87.8°F) [Pensky-Martens Closed Cup]
- Evaporation rate** : 1.62 (butyl acetate = 1)
- Flammability (solid, gas)** : Not available.
- Lower and upper explosive (flammable) limits** : Lower: 1.3%  
Upper: 13.1%
- Vapor pressure** : 2.1 kPa (16 mm Hg) [at 20°C]
- Vapor density** : 3.45 [Air = 1]
- Relative density** : 0.94
- Solubility** : Not available.
- Partition coefficient: n-octanol/water** : Not available.
- Auto-ignition temperature** : Not available.
- Decomposition temperature** : Not available.
- viscosity** : Kinematic (40°C (104°F)): >0.205 cm<sup>2</sup>/s (>20.5 cSt)
- Molecular weight** : Not applicable.

## Section 9. Physical and chemical properties

### Aerosol product

Heat of combustion : 17.409 kJ/g

## Section 10. Stability and reactivity

**Reactivity** : No specific test data related to reactivity available for this product or its ingredients.

**Chemical stability** : The product is stable.

**Possibility of hazardous reactions** : Under normal conditions of storage and use, hazardous reactions will not occur.

**Conditions to avoid** : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.

**Incompatible materials** : Reactive or incompatible with the following materials:  
oxidizing materials

**Hazardous decomposition products** : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

## Section 11. Toxicological information

### Information on toxicological effects

#### Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
2-methoxy-1-methylethyl acetate	LD50 Dermal	Rabbit	>5 g/kg	-
n-Butyl Acetate	LD50 Oral	Rat	8532 mg/kg	-
	LD50 Dermal	Rabbit	>17600 mg/kg	-
Methyl Isobutyl Ketone	LD50 Oral	Rat	10768 mg/kg	-
	LD50 Oral	Rat	2080 mg/kg	-
Ethylenediamine	LD50 Oral	Rat	1200 mg/kg	-

#### Irritation/Corrosion

Product/ingredient name	Result	Species	Score	Exposure	Observation
n-Butyl Acetate	Eyes - Moderate irritant	Rabbit	-	100 mg	-
	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
Methyl Isobutyl Ketone	Eyes - Moderate irritant	Rabbit	-	24 hours 100 U1	-
	Eyes - Severe irritant	Rabbit	-	40 mg	-
Ethylenediamine	Skin - Mild irritant	Rabbit	-	24 hours 500 mg	-
	Eyes - Severe irritant	Rabbit	-	24 hours 750 ug	-
	Eyes - Severe irritant	Rabbit	-	750 ug	-
	Skin - Moderate irritant	Rabbit	-	450 mg	-
	Skin - Severe irritant	Rabbit	-	24 hours 10 mg	-

#### Sensitization

Not available.

# Section 11. Toxicological information

**Mutagenicity**

Not available.

**Carcinogenicity**

Not available.

**Classification**

Product/ingredient name	OSHA	IARC	NTP
Methyl Isobutyl Ketone	-	2B	-

**Reproductive toxicity**

Not available.

**Teratogenicity**

Not available.

**Specific target organ toxicity (single exposure)**

Name	Category	Route of exposure	Target organs
2-methoxy-1-methylethyl acetate	Category 3	Not applicable.	Narcotic effects
n-Butyl Acetate	Category 3	Not applicable.	Narcotic effects
Methyl Isobutyl Ketone	Category 3	Not applicable.	Narcotic effects
	Category 3	Not applicable.	Respiratory tract irritation
2-Methoxy-1-Propanol Acetate	Category 3	Not applicable.	Respiratory tract irritation

**Specific target organ toxicity (repeated exposure)**

Name	Category	Route of exposure	Target organs
Methyl Isobutyl Ketone	Category 2	Not determined	Not determined

**Aspiration hazard**

Not available.

**Information on the likely routes of exposure** : Not available.

**Potential acute health effects**

- Eye contact** : Causes serious eye damage.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause allergy or asthma symptoms or breathing difficulties if inhaled.
- Skin contact** : Causes severe burns. May cause an allergic skin reaction.
- Ingestion** : Can cause central nervous system (CNS) depression.

**Symptoms related to the physical, chemical and toxicological characteristics**

- Eye contact** : Adverse symptoms may include the following:  
 pain  
 watering  
 redness



## Section 11. Toxicological information

- Inhalation** : Adverse symptoms may include the following:  
wheezing and breathing difficulties  
asthma  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations
- Skin contact** : Adverse symptoms may include the following:  
pain or irritation  
redness  
blistering may occur  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations
- Ingestion** : Adverse symptoms may include the following:  
stomach pains  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations

### Delayed and immediate effects and also chronic effects from short and long term exposure

#### Short term exposure

- Potential immediate effects** : Not available.
- Potential delayed effects** : Not available.

#### Long term exposure

- Potential immediate effects** : Not available.
- Potential delayed effects** : Not available.

#### Potential chronic health effects

Not available.

- General** : May cause damage to organs through prolonged or repeated exposure. Once sensitized, a severe allergic reaction may occur when subsequently exposed to very low levels.
- Carcinogenicity** : Suspected of causing cancer. Risk of cancer depends on duration and level of exposure.
- Mutagenicity** : No known significant effects or critical hazards.
- Teratogenicity** : May damage the unborn child.
- Developmental effects** : No known significant effects or critical hazards.
- Fertility effects** : No known significant effects or critical hazards.

### Numerical measures of toxicity

#### Acute toxicity estimates

Route	ATE value
Oral	9996.8 mg/kg
Inhalation (vapors)	52.87 mg/l

## Section 11. Toxicological information

## Section 12. Ecological information

### Toxicity

Product/ingredient name	Result	Species	Exposure
n-Butyl Acetate	Acute LC50 32 mg/l Marine water	Crustaceans - Artemia salina	48 hours
Methyl Isobutyl Ketone	Acute LC50 18000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
	Acute LC50 505000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
	Chronic NOEC 78 mg/l Fresh water	Daphnia - Daphnia magna	21 days
	Chronic NOEC 168 mg/l Fresh water	Fish - Pimephales promelas - Embryo	33 days
Ethylenediamine	Acute EC50 100000 µg/l Fresh water	Algae - Chlorella pyrenoidosa	96 hours
	Acute LC50 26500 µg/l Fresh water	Daphnia - Daphnia magna	48 hours
	Acute LC50 115.7 mg/l Fresh water	Fish - Pimephales promelas	96 hours
	Chronic NOEC 160 µg/l Fresh water	Daphnia - Daphnia magna	21 days

### Persistence and degradability

Product/ingredient name	Aquatic half-life	Photolysis	Biodegradability
n-Butyl Acetate	-	-	Readily
Methyl Isobutyl Ketone	-	-	Readily

### Bioaccumulative potential

Not available.

### Mobility in soil






Soil/water partition coefficient ( $K_{oc}$ ) : Not available.

Other adverse effects : No known significant effects or critical hazards.

## Section 13. Disposal considerations

**Disposal methods** : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

## Section 14. Transport information

	DOT Classification	TDG Classification	Mexico Classification	IATA	IMDG
JN number	UN3470	UN3470	UN3470	UN3470	UN3470
UN proper shipping name	PAINT RELATED MATERIAL CORROSIVE, FLAMMABLE	PAINT RELATED MATERIAL CORROSIVE, FLAMMABLE	PAINT RELATED MATERIAL CORROSIVE, FLAMMABLE	PAINT RELATED MATERIAL CORROSIVE, FLAMMABLE	PAINT RELATED MATERIAL CORROSIVE, FLAMMABLE
Transport hazard class(es)	8 (3) 	8 (3) 	8 (3) 	8 (3) 	8 (3) 
Packing group	II	II	II	II	II
Environmental hazards	No.	No.	No.	No.	No.
Additional information	-  <u>ERG No.</u> 132	Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.40-2.42 (Class 8), 2.18-2.19 (Class 3).  <u>ERG No.</u> 132	-  <u>ERG No.</u> 132	-	<u>Emergency schedules F-E, S-C</u>

**Special precautions for user** : Multi-modal shipping descriptions are provided for informational purposes and do not consider container sizes. The presence of a shipping description for a particular mode of transport (sea, air, etc.), does not indicate that the product is packaged suitably for that mode of transport. All packaging must be reviewed for suitability prior to shipment, and compliance with the applicable regulations is the sole responsibility of the person offering the product for transport. People loading and unloading dangerous goods must be trained on all of the risks deriving from the substances and on all actions in case of emergency situations.

**Transport in bulk according to Annex II of MARPOL and the IBC Code** : Not available.

**Proper shipping name** : Not available.  
**Ship type** : Not available.  
**Pollution category** : Not available.

## Section 15. Regulatory information

### International regulations

International lists :

- Australia inventory (AICS): Not determined.
- China inventory (IECSC): Not determined.
- Japan inventory (ENCS): Not determined.
- Japan inventory (ISHL): Not determined.
- Korea inventory (KECI): Not determined.
- New Zealand Inventory of Chemicals (NZIoC): Not determined.
- Philippines inventory (PICCS): Not determined.
- Taiwan Chemical Substances Inventory (TCSI): Not determined.
- Thailand inventory: Not determined.
- Turkey inventory: Not determined.
- Vietnam inventory: Not determined.

## Section 16. Other information

### Hazardous Material Information System (U.S.A.)

Health	*	3
Flammability		3
Physical hazards		0

The customer is responsible for determining the PPE code for this material. For more information on HMIS® Personal Protective Equipment (PPE) codes, consult the HMIS® Implementation Manual.

Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks. Although HMIS® ratings and the associated label are not required on SDSs or products leaving a facility under 29 CFR 1910.1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered trademark and service mark of the American Coatings Association, Inc.

### Procedure used to derive the classification

Classification	Justification
FLAMMABLE LIQUIDS - Category 3	On basis of test data
SKIN CORROSION/IRRITATION - Category 1	Calculation method
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 1	Calculation method
RESPIRATORY SENSITIZATION - Category 1	Calculation method
SKIN SENSITIZATION - Category 1	Calculation method
CARCINOGENICITY - Category 2	Calculation method
TOXIC TO REPRODUCTION (Unborn child) - Category 1B	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 2	Calculation method

### History

Date of printing : 5/4/2020  
 Date of issue/Date of revision : 5/4/2020  
 Date of previous issue : 11/28/2019  
 Version : 11

## Section 16. Other information

**Key to abbreviations** : ATE = Acute Toxicity Estimate  
BCF = Bioconcentration Factor  
GHS = Globally Harmonized System of Classification and Labelling of Chemicals  
IATA = International Air Transport Association  
IBC = Intermediate Bulk Container  
IMDG = International Maritime Dangerous Goods  
LogPow = logarithm of the octanol/water partition coefficient  
MARPOL = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)  
N/A = Not available  
SGG = Segregation Group  
UN = United Nations

Indicates information that has changed from previously issued version.

### Notice to reader

It is recommended that each customer or recipient of this Safety Data Sheet (SDS) study it carefully and consult resources, as necessary or appropriate, to become aware of and understand the data contained in this SDS and any hazards associated with the product. This information is provided in good faith and believed to be accurate as of the effective date herein. However, no warranty, express or implied, is given. The information presented here applies only to the product as shipped. The addition of any material can change the composition, hazards and risks of the product. Products shall not be repackaged, modified, or tinted except as specifically instructed by the manufacturer, including but not limited to the incorporation of products not specified by the manufacturer, or the use or addition of products in proportions not specified by the manufacturer. Regulatory requirements are subject to change and may differ between various locations and jurisdictions. The customer/buyer/user is responsible to ensure that his activities comply with all country, federal, state, provincial or local laws. The conditions for use of the product are not under the control of the manufacturer; the customer/buyer/user is responsible to determine the conditions necessary for the safe use of this product. The customer/buyer/user should not use the product for any purpose other than the purpose shown in the applicable section of this SDS without first referring to the supplier and obtaining written handling instructions. Due to the proliferation of sources for information such as manufacturer-specific SDS, the manufacturer cannot be responsible for SDSs obtained from any other source.

5067563 31622346

## Section 1. Identification

**Product name** : LV3 - Genesis Low Voc Satin  
Black  
**Product code** : 5067563 31622346  
**Other means of identification** : Not available.  
**Product type** : Liquid.  
**Relevant identified uses of the substance or mixture and uses advised against**  
Paint or paint related material. S

**Manufacturer** : The Sherwin-Williams Company  
4440 Warrensville Center Road  
Warrensville Heights, OHIO 44128

**Emergency telephone number of the company** : (216) 566-2917

**Product Information Telephone Number** : (800) 798-5872

**Regulatory Information: Telephone Number** : (216) 566-2902

**Transportation Emergency Telephone Number** : (800) 424-9300

## Section 2. Hazards identification

**OSHA/HCS status** : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

**Classification of the substance or mixture** : FLAMMABLE LIQUIDS - Category 2  
**GHS label elements** SKIN CORROSION/IRRITATION - Category 2  
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A  
SKIN SENSITIZATION - Category 1  
CARCINOGENICITY - Category 2  
TOXIC TO REPRODUCTION - Category 2  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) Category 3  
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 1  
Percentage of the mixture consisting of ingredient(s) of unknown acute toxicity: 18.6% (dermal), 23.6% (inhalation)



**Hazard pictograms** :

**Signal word** : Danger

## Section 2. Hazards identification

**Hazard statements** : Highly flammable liquid and vapor.  
Causes skin irritation.  
May cause an allergic skin reaction.  
Causes serious eye irritation.  
May cause respiratory irritation.  
May cause drowsiness or dizziness.  
Suspected of causing cancer.  
Suspected of damaging fertility or the unborn child.  
Causes damage to organs through prolonged or repeated exposure. (lungs)

### Precautionary statements

**Prevention** : Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Wear protective gloves, protective clothing and eye or face protection. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating or lighting equipment. Use non-sparking tools. Take action to prevent static discharges. Use only outdoors or in a well-ventilated area. Do not breathe vapor. Do not eat, drink or smoke when using this product. Wash thoroughly after handling. Contaminated work clothing must not be allowed out of the workplace.

**Response** : IF exposed or concerned: Get medical advice or attention. IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER or doctor if you feel unwell. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water. Wash contaminated clothing before reuse. IF ON SKIN: Wash with plenty of water. If skin irritation or rash occurs: Get medical advice or attention. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If eye irritation persists: Get medical advice or attention.

**Storage** : Store locked up. Store in a well-ventilated place. Keep container tightly closed. Keep cool.

**Disposal** : Dispose of contents and container in accordance with all local, regional, national and international regulations.

**Supplemental label elements**  
DELAYED EFFECTS FROM LONG TERM OVEREXPOSURE. Contains solvents which can cause permanent brain and nervous system damage. Intentional misuse by deliberately concentrating and inhaling the contents can be harmful or fatal. WARNING: This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm. FOR PROFESSIONAL USE ONLY.  
Please refer to the SDS for additional information. Keep out of reach of children. Do not transfer contents to other containers for storage.

**Hazards not otherwise classified** : None known.

## Section 3. Composition/information on ingredients

**Substance/mixture** : Mixture

**Other means of identification** : Not available.

**CAS number/other identifiers**

Ingredient name	% by weight	CAS number
Acetone	≥10 - ≤25	67-64-1
p-Chlorobenzotrifluoride	≥10 - ≤25	98-56-6
Amorphous Silica	≤10	7631-86-9
n-Butyl Propionate	≤5	590-01-2
Methyl n-Propyl Ketone	≤5	107-87-9
Talc	≤3	14807-96-6
Hydroxy Functional Reactive Diluent	≤3	105527-30-8

n-Butyl Acetate	≤3	123-86-4
-----------------	----	----------

### Section 3. Composition/information on ingredients

2-Ethyl-1,3-hexanediol	<3	94-96-2
Carbon Black	≤3	1333-86-4
2-methoxy-1-methylethyl acetate	≤3	108-65-6
Methyl n-Amyl Ketone	≤3	110-43-0
Bis(pentamethyl-4-piperidyl)sebacate	≤1	41556-26-7
Xylene, mixed isomers	≤0.3	1330-20-7
Methyl Isobutyl Ketone	≤0.3	108-10-1
Methyl pentamethylpiperidyl sebacate	≤0.3	82919-37-7

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

**There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified and hence require reporting in this section.**

Occupational exposure limits, if available, are listed in Section 8.

### Section 4. First aid measures

<u>Description of necessary first aid measures</u>	Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention.
<u>Eye contact</u>	
<u>Inhalation</u>	: Remove victim to fresh air and keep at rest in a position comfortable for breathing. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention. If necessary, call a poison center or physician. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband. In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
<u>Skin contact</u>	: Wash with plenty of soap and water. Remove contaminated clothing and shoes. Wash contaminated clothing thoroughly with water before removing it, or wear gloves. Continue to rinse for at least 10 minutes. Get medical attention. In the event of any complaints or symptoms, avoid further exposure. Wash clothing before reuse. Clean shoes thoroughly before reuse.
<u>Ingestion</u>	: Wash out mouth with water. Remove dentures if any. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Get medical attention. If necessary, call a poison center or physician. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

#### Most important symptoms/effects, acute and delayed

<u>Potential acute health effects</u>	: Causes serious eye irritation.
<u>Eye contact</u>	: Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause respiratory irritation.
<u>Inhalation</u>	: Causes skin irritation. May cause an allergic skin reaction.
	: Can cause central nervous system (CNS) depression.



Skin contact

Ingestion

Over-exposure signs/symptoms

<i>Date of issue</i> / <i>Date of revision</i> 5067563 31622346 LV3 - Genesis Low Voc Satin Black	: 4/4/2023	<i>Date of previous issue</i>	: No previous validation	<i>Version</i> : 1	3/20
				SHW-85-NA-GHS-US	

## Section 4. First aid measures

**Eye contact** : Adverse symptoms may include the following:  
pain or irritation watering redness

**Inhalation** : Adverse symptoms may include the following:  
respiratory tract  
irritation coughing  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations

**Skin contact** Adverse symptoms may include the following: irritation redness  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations

**Ingestion** Adverse symptoms may include the following:  
reduced fetal weight  
: increase in fetal deaths  
: skeletal malformations

### Indication of immediate medical attention and special treatment needed, if necessary

**Notes to physician** : In case of inhalation of decomposition products in a fire, symptoms may be delayed.  
: The exposed person may need to be kept under medical surveillance for 48 hours.

**Specific treatments** No specific treatment.

**Protection of first-aiders** : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

See toxicological information (Section 11)

## Section 5. Fire-fighting measures

**Extinguishing media** : Use dry chemical, CO<sub>2</sub>, water spray (fog) or foam.

**Suitable extinguishing media** : Do not use water jet.

**Unsuitable extinguishing media**

: Highly flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Vapors may accumulate in low or confined areas or travel a considerable

**Specific hazards arising from the chemical**

### Personal precautions, protective equipment and emergency procedures

- For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.
- For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For nonemergency personnel".
- Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

## **Section 5. Fire-fighting measures**

- Hazardous thermal decomposition products** : Decomposition products may include the following materials:  
carbon dioxide carbon monoxide halogenated compounds  
carbonyl halides  
metal oxide/oxides
- Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.
- Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

## **Section 6. Accidental release measures**

### Methods and materials for containment and cleaning up

- Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.
- Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

## **Section 7. Handling and storage**

### Precautions for safe handling

- Protective measures** : Put on appropriate personal protective equipment (see Section 8). Persons with a history of skin sensitization problems should not be employed in any process in which this product is used. Avoid exposure - obtain special instructions before use. Avoid exposure during pregnancy. Do not handle until all safety precautions have been read and understood. Do not get in eyes or on skin or clothing. Do not breathe vapor or

## Section 8. Exposure controls/personal protection

mist. Do not ingest. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless

## Section 7. Handling and storage

adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.

: Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

### Advice on general occupational hygiene

: Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use.

### Conditions for safe storage, including any incompatibilities

## Section 8. Exposure controls/personal protection

### Control parameters

#### Occupational exposure limits (OSHA United States)

Ingredient name	CAS #	Exposure limits
Acetone	67-64-1	<b>ACGIH TLV (United States, 1/2022).</b> TWA: 250 ppm 8 hours. STEL: 500 ppm 15 minutes. <b>NIOSH REL (United States, 10/2020).</b> TWA: 250 ppm 10 hours. TWA: 590 mg/m <sup>3</sup> 10 hours. <b>OSHA PEL (United States, 5/2018).</b> TWA: 1000 ppm 8 hours. TWA: 2400 mg/m <sup>3</sup> 8 hours.
p-Chlorobenzotrifluoride	98-56-6	None.
Amorphous Silica	7631-86-9	<b>NIOSH REL (United States, 10/2020).</b> <b>[SILICA, AMORPHOUS]</b> TWA: 6 mg/m <sup>3</sup> 10 hours.
n-Butyl Propionate	590-01-2	None.
Methyl n-Propyl Ketone	107-87-9	<b>NIOSH REL (United States, 10/2020).</b> TWA: 150 ppm 10 hours. TWA: 530 mg/m <sup>3</sup> 10 hours. <b>OSHA PEL (United States, 5/2018).</b> TWA: 200 ppm 8 hours. TWA: 700 mg/m <sup>3</sup> 8 hours. <b>ACGIH TLV (United States, 1/2022).</b> STEL: 150 ppm 15 minutes.
Talc	14807-96-6	<b>NIOSH REL (United States, 10/2020).</b> TWA: 2 mg/m <sup>3</sup> 10 hours. Form: Respirable fraction <b>ACGIH TLV (United States, 1/2022).</b>

Hydroxy Functional Reactive Diluent n-Butyl Acetate	105527-30-8 123-86-4	TWA: 2 mg/m <sup>3</sup> 8 hours. Form: Respirable fraction None. <b>NIOSH REL (United States, 10/2020).</b>  TWA: 150 ppm 10 hours. TWA: 710 mg/m <sup>3</sup> 10 hours. STEL: 200 ppm 15 minutes. STEL: 950 mg/m <sup>3</sup> 15 minutes. <b>OSHA PEL (United States, 5/2018).</b> TWA: 150 ppm 8 hours. TWA: 710 mg/m <sup>3</sup> 8 hours. <b>ACGIH TLV (United States, 1/2022). [Butyl acetates]</b> STEL: 150 ppm 15 minutes. TWA: 50 ppm 8 hours.
2-Ethyl-1,3-hexanediol Carbon Black	94-96-2 1333-86-4	None. <b>ACGIH TLV (United States, 1/2022).</b> TWA: 3 mg/m <sup>3</sup> 8 hours. Form: Inhalable fraction <b>NIOSH REL (United States, 10/2020).</b> TWA: 3.5 mg/m <sup>3</sup> 10 hours. TWA: 0.1 mg of PAHs/cm <sup>3</sup> 10 hours. <b>OSHA PEL (United States, 5/2018).</b> TWA: 3.5 mg/m <sup>3</sup> 8 hours.
2-methoxy-1-methylethyl acetate	108-65-6	<b>OARS WEEL (United States, 1/2021).</b> TWA: 50 ppm 8 hours.
Methyl n-Amyl Ketone	110-43-0	<b>ACGIH TLV (United States, 1/2022).</b> TWA: 50 ppm 8 hours. TWA: 233 mg/m <sup>3</sup> 8 hours. <b>NIOSH REL (United States, 10/2020).</b> TWA: 100 ppm 10 hours. TWA: 465 mg/m <sup>3</sup> 10 hours. <b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours. TWA: 465 mg/m <sup>3</sup> 8 hours.
Bis(pentamethyl-4-piperidyl)sebacate Xylene, mixed isomers	41556-26-7 1330-20-7	None. <b>ACGIH TLV (United States, 1/2022). [xylene]</b> TWA: 20 ppm 8 hours. TWA: 434 mg/m <sup>3</sup> 8 hours. STEL: 651 mg/m <sup>3</sup> 15 minutes. <b>OSHA PEL (United States, 5/2018). [Xylenes]</b> TWA: 100 ppm 8 hours. TWA: 435 mg/m <sup>3</sup> 8 hours.
Methyl Isobutyl Ketone	108-10-1	<b>ACGIH TLV (United States, 1/2022).</b> TWA: 20 ppm 8 hours. STEL: 75 ppm 15 minutes. <b>NIOSH REL (United States, 10/2020).</b> TWA: 50 ppm 10 hours. TWA: 205 mg/m <sup>3</sup> 10 hours. STEL: 75 ppm 15 minutes. STEL: 300 mg/m <sup>3</sup> 15 minutes. <b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours. TWA: 410 mg/m <sup>3</sup> 8 hours.

## Section 8. Exposure controls/personal protection

Methyl pentamethylpiperidyl sebacate

82919-37-7

None.

[Occupational exposure limits \(Canada\)](#)

## Section 8. Exposure controls/personal protection

Ingredient name	CAS #	Exposure limits
acetone	67-64-1	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>            8 hrs OEL: 1200 mg/m<sup>3</sup> 8 hours.            15 min OEL: 1800 mg/m<sup>3</sup> 15 minutes.            8 hrs OEL: 500 ppm 8 hours.            15 min OEL: 750 ppm 15 minutes. <b>CA British Columbia Provincial (Canada, 3/2022).</b>            TWA: 250 ppm 8 hours.            STEL: 500 ppm 15 minutes.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>            TWA: 250 ppm 8 hours.            STEL: 500 ppm 15 minutes.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>            TWAEV: 500 ppm 8 hours.            TWAEV: 1190 mg/m<sup>3</sup> 8 hours.            STEV: 1000 ppm 15 minutes.            STEV: 2380 mg/m<sup>3</sup> 15 minutes. <b>CA Saskatchewan Provincial (Canada, 7/2013).</b>            STEL: 750 ppm 15 minutes.            TWA: 500 ppm 8 hours.</p>
Methyl propyl ketone	107-87-9	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>            8 hrs OEL: 200 ppm 8 hours.            15 min OEL: 250 ppm 15 minutes.            8 hrs OEL: 705 mg/m<sup>3</sup> 8 hours.            15 min OEL: 881 mg/m<sup>3</sup> 15 minutes. <b>CA British Columbia Provincial (Canada, 3/2022).</b>            TWA: 150 ppm 8 hours.            STEL: 250 ppm 15 minutes.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>            STEL: 150 ppm 15 minutes.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>            TWAEV: 150 ppm 8 hours.            TWAEV: 530 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>            STEL: 250 ppm 15 minutes.            TWA: 200 ppm 8 hours.</p>
talc (none asbestiform)	14807-96-6	<p><b>CA British Columbia Provincial (Canada, 3/2022).</b>            TWA: 2 mg/m<sup>3</sup> 8 hours. Form: Respirable</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>            TWAEV: 2 mg/m<sup>3</sup> 8 hours. Form: Respirable dust.</p> <p><b>CA Alberta Provincial (Canada, 6/2018).</b>            8 hrs OEL: 2 mg/m<sup>3</sup> 8 hours. Form: Respirable particulate</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>            TWA: 2 mg/m<sup>3</sup> 8 hours. Form: Respirable particulate matter. TWA: 2 f/cc 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>            TWA: 2 mg/m<sup>3</sup> 8 hours. Form: respirable</p>

## Section 8. Exposure controls/personal protection

n-butyl acetate	123-86-4	<p>fraction</p> <p><b>CA Alberta Provincial (Canada, 6/2018).</b>            15 min OEL: 200 ppm 15 minutes.            15 min OEL: 950 mg/m<sup>3</sup> 15 minutes.            8 hrs OEL: 150 ppm 8 hours.            8 hrs OEL: 713 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>            STEL: 200 ppm 15 minutes.            TWA: 150 ppm 8 hours.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>  <b>[butyl acetates, all isomers]</b>            STEL: 150 ppm 15 minutes.            TWA: 50 ppm 8 hours.</p> <p><b>CA British Columbia Provincial (Canada, 3/2022).</b> <b>[butyl acetate, all isomers]</b>            STEL: 150 ppm 15 minutes.            TWA: 50 ppm 8 hours.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>  <b>[butyl acetates]</b>            STEV: 150 ppm 15 minutes.            TWAEV: 50 ppm 8 hours.</p>
Carbon black	1333-86-4	<p><b>CA British Columbia Provincial (Canada, 3/2022).</b>            TWA: 3 mg/m<sup>3</sup> 8 hours. Form: Inhalable</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>            TWA: 3 mg/m<sup>3</sup> 8 hours. Form: Inhalable particulate matter.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>            TWAEV: 3 mg/m<sup>3</sup> 8 hours. Form: inhalable dust</p> <p><b>CA Alberta Provincial (Canada, 6/2018).</b>            8 hrs OEL: 3.5 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>            STEL: 7 mg/m<sup>3</sup> 15 minutes.            TWA: 3.5 mg/m<sup>3</sup> 8 hours.</p>
Methyl n-amyl ketone	110-43-0	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>            8 hrs OEL: 233 mg/m<sup>3</sup> 8 hours.            8 hrs OEL: 50 ppm 8 hours.</p> <p><b>CA British Columbia Provincial (Canada, 3/2022).</b>            TWA: 50 ppm 8 hours.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>            TWA: 25 ppm 8 hours.            TWA: 115 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>            TWAEV: 50 ppm 8 hours.            TWAEV: 233 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>            STEL: 60 ppm 15 minutes.            TWA: 50 ppm 8 hours.</p>
Xylene	1330-20-7	<p><b>CA Alberta Provincial (Canada, 6/2018).</b></p>

## Section 8. Exposure controls/personal protection

Methyl isobutyl ketone	108-10-1	<p><b>[Dimethylbenzene]</b>              8 hrs OEL: 100 ppm 8 hours.              15 min OEL: 651 mg/m<sup>3</sup> 15 minutes.</p> <p>15 min OEL: 150 ppm 15 minutes.              8 hrs OEL: 434 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA British Columbia Provincial (Canada, 3/2022). [Xylene (o, m &amp; p isomers)]</b>              TWA: 100 ppm 8 hours.              STEL: 150 ppm 15 minutes.</p> <p><b>CA Quebec Provincial (Canada, 6/2021). [Xylene]</b>              TWAEV: 100 ppm 8 hours.              TWAEV: 434 mg/m<sup>3</sup> 8 hours.              STEV: 150 ppm 15 minutes.              STEV: 651 mg/m<sup>3</sup> 15 minutes.</p> <p><b>CA Ontario Provincial (Canada, 6/2019). [Xylene (o-, m-, p-isomers)]</b>              STEL: 150 ppm 15 minutes.              TWA: 100 ppm 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013). [Xylene]</b>              STEL: 150 ppm 15 minutes.              TWA: 100 ppm 8 hours.</p> <p><b>CA Alberta Provincial (Canada, 6/2018).</b>              8 hrs OEL: 205 mg/m<sup>3</sup> 8 hours.              8 hrs OEL: 50 ppm 8 hours.              15 min OEL: 75 ppm 15 minutes.              15 min OEL: 307 mg/m<sup>3</sup> 15 minutes. <b>CA British Columbia Provincial (Canada, 3/2022).</b>              TWA: 20 ppm 8 hours.              STEL: 75 ppm 15 minutes.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>              TWA: 20 ppm 8 hours.              STEL: 75 ppm 15 minutes.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>              TWAEV: 20 ppm 8 hours.              STEV: 75 ppm 15 minutes.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>              STEL: 75 ppm 15 minutes.              TWA: 50 ppm 8 hours.</p>
------------------------	----------	---

### Occupational exposure limits (Mexico)

	CAS #	Exposure limits
Acetone	67-64-1	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 500 ppm 8 hours. STEL: 750 ppm 15 minutes.
Methyl n-Propyl Ketone	107-87-9	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> STEL: 150 ppm 15 minutes.
n-Butyl Acetate	123-86-4	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 150 ppm 8 hours. STEL: 200 ppm 15 minutes.
Methyl n-Amyl Ketone	110-43-0	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 50 ppm 8 hours.
Methyl Isobutyl Ketone	108-10-1	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b>



<b>Section 8. Exposure controls/personal protection</b>		
---	--	--

		TWA: 50 ppm 8 hours. STEL: 75 ppm 15 minutes.
--	--	--

## Section 8. Exposure controls/personal protection

<b>Appropriate engineering controls</b>	: Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.
<b>Environmental exposure controls</b>	: Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.
<b>Individual protection measure</b>	<b>S</b>
<b>Hygiene measures</b>	: Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Contaminated work clothing should not be allowed out of the workplace. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.
<b>Eye/face protection</b>	: Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: chemical splash goggles.
<b>Skin protection</b>	: Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.
<b>Hand protection</b>	
<b>Body protection</b>	: Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear antistatic protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.
<b>Other skin protection</b>	: Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.
<b>Respiratory protection</b>	: Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use.

## Section 9. Physical and chemical properties

The conditions of measurement of all properties are at standard temperature and pressure unless otherwise indicated.

### Appearance

<b>Physical state</b>	Liquid.
<b>Color</b>	: Various
<b>Odor</b>	: Not available.
<b>Odor threshold</b>	: Not available.
<b>pH</b>	: Not applicable.
<b>Melting point/freezing point</b>	: Not available.

## Section 11. Toxicological information

Boiling point, initial boiling point, and boiling range	Result	Species	Dose	Exposure
Acetone	55°C (131°F)	Rat	5800 mg/kg	-
<b>Section 9. Physical and chemical properties</b>				
p-Chlorobenzotrifluoride	LD50 Oral	Rat	13 g/kg	-
n-Butyl Propionate	LD50 Dermal	Rabbit	>14 g/kg	-
Flash point	Closed cup: -17°C (1.4°F) [Pensky-Martens Closed Cup]	Rat	11031 mg/kg	-
Evaporation rate	Cup 5.6 (butyl acetate = 1) Not available.	Rat	6500 mg/kg	-
Methyl n-Propyl Ketone	LD50 Dermal	Rabbit	1600 mg/kg	-
Flammability	Lower: 0.9%	Rat	>17600 mg/kg	-
Lower and upper explosion limit/flammability limit	Upper: 13.1%	Rabbit	10768 mg/kg	-
n-Butyl Acetate	LD50 Dermal	Rat	-	-
Vapor pressure	2 [Air = 1]			
Relative vapor density	1.07			
Relative density	:			
Solubility(ies)	:			
Not available.	Not applicable.			
Partition coefficient: noctanol/water	Not available.			
Auto-ignition temperature	Not available.			
Decomposition temperature	Kinematic (40°C (104°F)): <20.5 mm²/s (<20.5 cSt)			
Viscosity	Not applicable.			
Molecular weight	:			
Aerosol product	21.955 kJ/g			
Heat of combustion	:			

## Section 10. Stability and reactivity

<b>Reactivity</b>	: No specific test data related to reactivity available for this product or its ingredients.
<b>Chemical stability</b>	: The product is stable.
<b>Possibility of hazardous reactions</b>	: Under normal conditions of storage and use, hazardous reactions will not occur.
<b>Conditions to avoid</b>	: Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.
<b>Incompatible materials</b>	: Reactive or incompatible with the following materials: oxidizing materials
<b>Hazardous decomposition products</b>	: Under normal conditions of storage and use, hazardous decomposition products should not be produced.

## Section 11. Toxicological information

### Information on toxicological effects

#### Acute toxicity

2-Ethyl-1,3-hexanediol	LD50 Dermal	Rabbit	2 g/kg	-
	LD50 Oral	Rat	1400 mg/kg	-
Carbon Black	LD50 Oral	Rat	>15400 mg/kg	-
2-methoxy-1-methylethyl acetate	LD50 Dermal	Rabbit	>5 g/kg	-
	LD50 Oral	Rat	8532 mg/kg	-
Methyl n-Amyl Ketone	LD50 Oral	Rat	1600 mg/kg	-
Xylene, mixed isomers	LC50 Inhalation Gas.	Rat	6700 ppm	4 hours
	LD50 Oral	Rat	4300 mg/kg	-
Methyl Isobutyl Ketone	LD50 Oral	Rat	2080 mg/kg	-

### Irritation/Corrosion

Product/ingredient name	Result	Species	Score	Exposure	Observation
Acetone	Eyes - Mild irritant	Human	-	186300 ppm	-
	Eyes - Mild irritant	Rabbit	-	10 uL	-
	Eyes - Moderate irritant	Rabbit	-	24 hours 20 mg	-
	Eyes - Severe irritant	Rabbit	-	20 mg	-
	Skin - Mild irritant	Rabbit	-	395 mg	-
	Skin - Mild irritant	Rabbit	-	24 hours 500 mg	-
Amorphous Silica	Eyes - Mild irritant	Rabbit	-	24 hours 25 mg	-
n-Butyl Propionate	Eyes - Moderate irritant	Rabbit	-	0.1 MI	-
	Eyes - Severe irritant	Rabbit	-	100 mg	-
	Skin - Mild irritant	Guinea pig	-	0.3 MI	-
	Skin - Mild irritant	Rabbit	-	0.5 MI	-
Methyl n-Propyl Ketone	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
	Skin - Mild irritant	Rabbit	-	405 mg	-
Talc	Skin - Mild irritant	Human	-	72 hours 300 ug l	-
	Skin - Mild irritant	Human	-	72 hours 300 ug l	-
n-Butyl Acetate	Eyes - Moderate irritant	Rabbit	-	100 mg	-
	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
2-Ethyl-1,3-hexanediol	Eyes - Severe irritant	Rabbit	-	20 mg	-
	Skin - Mild irritant	Rabbit	-	500 mg	-
Methyl n-Amyl Ketone	Skin - Mild irritant	Rabbit	-	24 hours 14 mg	-
	Skin - Mild irritant	Rabbit	-	24 hours 14 mg	-
Xylene, mixed isomers	Eyes - Mild irritant	Rabbit	-	87 mg	-
	Eyes - Severe irritant	Rabbit	-	24 hours 5 mg	-
	Skin - Mild irritant	Rat	-	8 hours 60 uL	-
	Skin - Moderate irritant	Rabbit	-	100 %	-
	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
Methyl Isobutyl Ketone	Eyes - Moderate irritant	Rabbit	-	24 hours 100 uL	-
	Eyes - Severe irritant	Rabbit	-	40 mg	-

## Section 11. Toxicological information

	Skin - Mild irritant	Rabbit	-	24 hours 500 mg	-
--	----------------------	--------	---	-----------------	---

### Sensitization

Not available.

### Mutagenicity

Not available.

### Carcinogenicity

Not available.

### Classification

Product/ingredient name	OSHA	IARC	NTP
p-Chlorobenzotrifluoride	-	2B	-
Amorphous Silica	-	3	-
Talc	-	3	-
Carbon Black	-	2B	-
Xylene, mixed isomers	-	3	-
Methyl Isobutyl Ketone	-	2B	-

### Reproductive toxicity

Not available.

### Teratogenicity

Not available.

### Specific target organ toxicity (single exposure)

Name	Category	Route of exposure	Target organs
Acetone	Category 3	-	Respiratory tract irritation
p-Chlorobenzotrifluoride	Category 3	-	Narcotic effects
Methyl n-Propyl Ketone	Category 3	-	Respiratory tract irritation
n-Butyl Acetate	Category 3	-	Respiratory tract irritation
2-Ethyl-1,3-hexanediol	Category 3	-	Narcotic effects
2-methoxy-1-methylethyl acetate	Category 3	-	Narcotic effects
Methyl n-Amyl Ketone	Category 3	-	Respiratory tract irritation
Xylene, mixed isomers	Category 3	-	Narcotic effects
Methyl Isobutyl Ketone	Category 3	-	Respiratory tract irritation
	Category 3	-	Narcotic effects

### Specific target organ toxicity (repeated exposure)

Name	Category	Route of exposure	Target organs
Acetone	Category 2	-	-
Methyl n-Propyl Ketone	Category 2	-	-
Talc	Category 1	inhalation	lungs

## Section 11. Toxicological information

2-Ethyl-1,3-hexanediol	Category 2	-	-
Methyl n-Amyl Ketone	Category 2	-	-
Xylene, mixed isomers	Category 2	-	-
Methyl Isobutyl Ketone	Category 2	-	-

### Aspiration hazard

Name	Result
Xylene, mixed isomers	ASPIRATION HAZARD - Category 1

**Information on the likely routes of exposure** : Not available.

### Potential acute health effects

- Eye contact** : Causes serious eye irritation.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause respiratory irritation.
- Skin contact** : Causes skin irritation. May cause an allergic skin reaction.
- Ingestion** : Can cause central nervous system (CNS) depression.

### Symptoms related to the physical, chemical and toxicological characteristics

**Eye contact** : Adverse symptoms may include the following:  
pain or irritation watering redness

**Inhalation** : Adverse symptoms may include the following:  
respiratory tract irritation coughing nausea or vomiting headache drowsiness/fatigue dizziness/vertigo unconsciousness reduced fetal weight increase in fetal deaths skeletal malformations

**Skin contact** : Adverse symptoms may include the following:  
irritation redness reduced fetal weight increase in fetal deaths skeletal malformations

: Adverse symptoms may include the following:  
reduced fetal weight increase in fetal deaths skeletal malformations

**Ingestion**

### Delayed and immediate effects and also chronic effects from short and long term exposure

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.

### Long term exposure

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.  
**Potential chronic health effects**

Not available.

**General** : Causes damage to organs through prolonged or repeated exposure. Once sensitized, a severe allergic reaction may occur when subsequently exposed to very low levels.

**Carcinogenicity** : Suspected of causing cancer. Risk of cancer depends on duration and level of exposure.

## Section 11. Toxicological information

**Mutagenicity** : No known significant effects or critical hazards.

**Teratogenicity** : No known significant effects or critical hazards.

**Developmental effects** : No known significant effects or critical hazards.

**Fertility effects** : Suspected of damaging fertility.

### Numerical measures of toxicity

#### Acute toxicity estimates

Route	ATE value
Oral	11389.52 mg/kg
Dermal	89678.5 mg/kg
Inhalation (vapors)	562.81 mg/l

## Section 12. Ecological information

### Toxicity

Product/ingredient name	Result	Species	Exposure
Acetone	Acute EC50 7200000 µg/l Fresh water	Algae - Selenastrum sp.	96 hours
	Acute LC50 4.42589 ml/L Marine water	Crustaceans - Acartia tonsa	48 hours
		Copepodid	
	Acute LC50 7460000 µg/l Fresh water	Daphnia - Daphnia cucullata	48 hours
	Acute LC50 5600 ppm Fresh water	Fish - Poecilia reticulata	96 hours
	Chronic NOEC 4.95 mg/l Marine water	Algae - Ulva pertusa	96 hours
	Chronic NOEC 0.016 ml/L Fresh water	Crustaceans - Daphniidae	21 days
	Chronic NOEC 0.1 ml/L Fresh water	Daphnia - Daphnia magna	21 days
Amorphous Silica	Chronic NOEC 5 µg/l Marine water	Neonate	
		Fish - Gasterosteus aculeatus	42 days
		Larvae	
Methyl n-Propyl Ketone	Acute EC50 2.2 g/L Fresh water	Daphnia - Daphnia magna	48 hours
	Chronic NOEC 12.5 mg/l Fresh water	Neonate	
n-Butyl Acetate		Daphnia - Daphnia magna	21 days
		Neonate	
	Acute LC50 1240000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
2-Ethyl-1,3-hexanediol	Acute LC50 32 mg/l Marine water	Crustaceans - Artemia salina	48 hours
	Acute LC50 18000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
Methyl n-Amyl Ketone	Acute LC50 624000 µg/l Fresh water	Fish - Ictalurus punctatus	96 hours
		Fingerling	
	Acute LC50 131000 µg/l Fresh water	Fish - Pimephales promelas	96 hours

## Section 12. Ecological information

Xylene, mixed isomers	Acute LC50 8500 µg/l Marine water	Crustaceans - Palaemonetes pugio	48 hours
Methyl Isobutyl Ketone	Acute LC50 13400 µg/l Fresh water	Fish - Pimephales promelas	96 hours
	Acute LC50 505000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
	Chronic NOEC 78 mg/l Fresh water	Daphnia - Daphnia magna	21 days
	Chronic NOEC 168 mg/l Fresh water	Fish - Pimephales promelas Embryo	33 days

### Persistence and degradability

Product/ingredient name	Aquatic half-life	Photolysis	Biodegradability
Acetone	-	-	Readily
n-Butyl Acetate	-	-	Readily
Methyl n-Amyl Ketone	-	-	Readily
Xylene, mixed isomers	-	-	Readily
Methyl Isobutyl Ketone	-	-	Readily

### Bioaccumulative potential

Product/ingredient name	LogP <sub>ow</sub>	BCF	Potential
Xylene, mixed isomers	-	8.1 to 25.9	low

### Mobility in soil







Soil/water partition coefficient (K<sub>oc</sub>) : Not available.

Other adverse effects : No known significant effects or critical hazards.

## Section 13. Disposal considerations

**Disposal methods** : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

## Section 14. Transport information

Section 14. Transport information					pollutant (p-Chlorobenzotrifluoride, Bis(pentamethyl-4-piperidyl) sebacate)
	DOT Classification	TDG Classification	Mexico Classification	IATA	MDG
Transport hazard class(es)	UN1263 	UN1263 	UN1263 	UN1263 	UN1263  
UN proper shipping name	PA...	PA...	PA...	PA...	PA... Marine



	II	II	II	II
	No.	No.	Yes. The environmentally hazardous substance mark is not required.	Yes.
<u>No.</u>	Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.18-2.19 (Class 3). <u>ERG No.</u> 128	- <u>ERG No.</u> 128	The environmentally hazardous substance mark may appear if required by other transportation regulations.	The marine pollutant mark is not required when transported in sizes of ≤5 L or ≤5 kg. <u>Emergency schedules</u> F-E, S-E

**Special precautions for user**

must be trained on all of the risks deriving from the substances and on all actions in case of emergency situations. : Not available.

**Proper shipping name** : Not available.

**Transport in bulk according to IMO instruments**

: Multi-modal shipping descriptions are provided for informational purposes and do not consider container sizes. The presence of a shipping description for a particular mode of transport (sea, air, etc.), does not indicate that the product is packaged suitably for that mode of transport. All packaging must be reviewed for suitability prior to shipment, and compliance with the applicable regulations is the sole responsibility of the person offering the product for transport. People loading and unloading dangerous goods

## Section 15. Regulatory information

### SARA 313

SARA 313 (40 CFR 372.45) supplier notification can be found on the Environmental Data Sheet.

### California Prop. 65

WARNING: This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm.

### International regulations

#### International lists

- : **Australia inventory (AIIC):** Not determined.
- China inventory (IECSC):** Not determined.
- Japan inventory (CSCL):** Not determined.
- Japan inventory (ISHL):** Not determined.
- Korea inventory (KECI):** Not determined.
- New Zealand Inventory of Chemicals (NZIoC):** Not determined.
- Philippines inventory (PICCS):** Not determined.
- Taiwan Chemical Substances Inventory (TCSI):** Not determined.
- Thailand inventory:** Not determined.
- Turkey inventory:** Not determined.
- Vietnam inventory:** Not determined.

## Section 16. Other information

### Hazardous Material Information System (U.S.A.)

Health	*	3
Flammability		3
Physical hazards		0

The customer is responsible for determining the PPE code for this material. For more information on HMIS® Personal Protective Equipment (PPE) codes, consult the HMIS® Implementation Manual.

Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks. Although HMIS® ratings and the associated label are not required on SDSs or products leaving a facility under 29 CFR 1910.1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered trademark and service mark of the American Coatings Association, Inc.

### Procedure used to derive the classification

Classification	Justification
FLAMMABLE LIQUIDS - Category 2	On basis of test data
SKIN CORROSION/IRRITATION - Category 2	Calculation method
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A	Calculation method
SKIN SENSITIZATION - Category 1	Calculation method
CARCINOGENICITY - Category 2	Calculation method
TOXIC TO REPRODUCTION - Category 2	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 1	Calculation method

### History

Date of printing : 4/4/2023 Date of

issue/Date of : 4/4/2023 revision

Date of previous issue : No previous validation

## Section 16. Other information

### Key to abbreviations

: ATE = Acute Toxicity Estimate  
BCF = Bioconcentration Factor  
GHS = Globally Harmonized System of Classification and Labelling of Chemicals  
IATA = International Air Transport Association  
IBC = Intermediate Bulk Container  
IMDG = International Maritime Dangerous Goods  
LogPow = logarithm of the octanol/water partition coefficient  
MARPOL = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)  
N/A = Not available  
SGG = Segregation Group  
UN = United Nations

▣ Indicates information that has changed from previously issued version.

### Notice to reader

It is recommended that each customer or recipient of this Safety Data Sheet (SDS) study it carefully and consult resources, as necessary or appropriate, to become aware of and understand the data contained in this SDS and any hazards associated with the product. This information is provided in good faith and believed to be accurate as of the effective date herein. However, no warranty, express or implied, is given. The information presented here applies only to the product as shipped. The addition of any material can change the composition, hazards and risks of the product. Products shall not be repackaged, modified, or tinted except as specifically instructed by the manufacturer, including but not limited to the incorporation of products not specified by the manufacturer, or the use or addition of products in proportions not specified by the manufacturer. Regulatory requirements are subject to change and may differ between various locations and jurisdictions. The customer/buyer/user is responsible to ensure that his activities comply with all country, federal, state, provincial or local laws. The conditions for use of the product are not under the control of the manufacturer; the customer/buyer/user is responsible to determine the conditions necessary for the safe use of this product. The customer/buyer/user should not use the product for any purpose other than the purpose shown in the applicable section of this SDS without first referring to the supplier and obtaining written handling instructions. Due to the proliferation of sources for information such as manufacturer-specific SDS, the manufacturer cannot be responsible for SDSs obtained from any other source.

# SAFETY DATA SHEET

GH1093

## Section 1. Identification

**Product name** : GENESIS® M 3.5 Low VOC Hardener

**Product code** : GH1093

**Other means of identification** : Not available.

**Product type** : Liquid.

**Relevant identified uses of the substance or mixture and uses advised against**

Paint or paint related material.

**Manufacturer** : The Sherwin-Williams Company  
4440 Warrensville Center Road  
Warrensville Heights, OH 44128

**Emergency telephone number of the company** : US / Canada: (800) 424-9300  
Mexico: 55-4160-8800 / 55-4160-8819 Monday to Friday from 8:30 a.m. to 5:30 p.m.

**Product Information Telephone Number** : US / Canada: (800) 798-5872  
Mexico: 800-022-7926

**Regulatory Information Telephone Number** : US / Canada: (216) 566-2902  
Mexico: 55-4160-8819 / 55-4160-8806

**Transportation Emergency Telephone Number** : US / Canada: (800) 424-9300  
Mexico: SETIQ 800-00-214-00 / 55-5559-1588 Available 24 hours and 365 days a year

## Section 2. Hazards identification

**OSHA/HCS status** : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

**Classification of the substance or mixture** : FLAMMABLE LIQUIDS - Category 3  
SKIN CORROSION/IRRITATION - Category 2  
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A  
RESPIRATORY SENSITIZATION - Category 1  
SKIN SENSITIZATION - Category 1  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3  
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 2  
Percentage of the mixture consisting of ingredient(s) of unknown acute toxicity: 5.7% (dermal), 5.7% (inhalation)

**GHS label elements**

**Hazard pictograms** :



**Signal word** : Danger

## Section 2. Hazards identification

**Hazard statements** : Flammable liquid and vapor.  
Causes skin irritation.  
May cause an allergic skin reaction.  
Causes serious eye irritation.  
May cause allergy or asthma symptoms or breathing difficulties if inhaled.  
May cause respiratory irritation.  
May cause drowsiness or dizziness.  
May cause damage to organs through prolonged or repeated exposure.

### Precautionary statements

**Prevention** : Wear protective gloves, protective clothing and eye or face protection. Wear respiratory protection. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating or lighting equipment. Use non-sparking tools. Take action to prevent static discharges. Use only outdoors or in a well-ventilated area. Do not breathe vapor. Wash thoroughly after handling. Contaminated work clothing must not be allowed out of the workplace.

**Response** : Get medical advice or attention if you feel unwell. IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER or doctor if you feel unwell. If experiencing respiratory symptoms: Call a POISON CENTER or doctor. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water. Wash contaminated clothing before reuse. IF ON SKIN: Wash with plenty of water. If skin irritation or rash occurs: Get medical advice or attention. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If eye irritation persists: Get medical advice or attention.

**Storage** : Store locked up. Store in a well-ventilated place. Keep container tightly closed. Keep cool.

**Disposal** : Dispose of contents and container in accordance with all local, regional, national and international regulations.

**Supplemental label elements** DELAYED EFFECTS FROM LONG TERM OVEREXPOSURE. Contains solvents which can cause permanent brain and nervous system damage. Intentional misuse by deliberately concentrating and inhaling the contents can be harmful or fatal. FOR PROFESSIONAL USE ONLY. This product must be mixed with other components before use. Before opening the packages, READ AND FOLLOW WARNING LABELS ON ALL COMPONENTS. VAPOR AND SPRAY MIST HARMFUL. Gives off harmful vapor of solvents and isocyanates. DO NOT USE IF YOU HAVE CHRONIC (LONG-TERM) LUNG OR BREATHING PROBLEMS, OR IF YOU HAVE EVER HAD A REACTION TO ISOCYANATES. USE ONLY WITH ADEQUATE VENTILATION. WHERE OVERSPRAY IS PRESENT, A POSITIVE PRESSURE AIR SUPPLIED RESPIRATOR (NIOSH approved) SHOULD BE WORN TO PREVENT EXPOSURE. IF UNAVAILABLE, AN APPROPRIATE PROPERLY FITTED APPROVED NIOSH VAPOR/PARTICULATE RESPIRATOR MAY BE EFFECTIVE. Follow directions for respirator use. Wear the respirator for the whole time of spraying and until all vapors and mists are gone. If you have any breathing problems during use, LEAVE THE AREA and get fresh air. If problems remain or happen later, IMMEDIATELY call a doctor - If not available get emergency medical treatment. Have this label with you. Reacts with water in closed container to produce pressure which may cause container to burst.  
Please refer to the SDS for additional information. Keep out of reach of children. Do not transfer contents to other containers for storage.

**Hazards not otherwise classified** : None known.

## Section 3. Composition, information on ingredients

**Substance/mixture** : Mixture  
**Other means of identification** : Not available.

### CAS number/other identifiers

Ingredient name	% by weight	CAS number
Hexamethylene Diisocyanate Polymer	≥50 - ≤75	28182-81-2
n-Butyl Acetate	≥10 - ≤25	123-86-4
2-Butoxyethyl Acetate	≤10	112-07-2
Ethyl 3-Ethoxypropionate	≤10	763-69-9
Methyl n-Amyl Ketone	≤5	110-43-0
2-methoxy-1-methylethyl acetate	≤3	108-65-6
Hexamethylene Diisocyanate (max.)	≤0.3	822-06-0

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

**There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified and hence require reporting in this section.**

Occupational exposure limits, if available, are listed in Section 8.

## Section 4. First aid measures

### Description of necessary first aid measures

- Eye contact** : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention.
- Inhalation** : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention. If necessary, call a poison center or physician. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband. In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours. In the event of any complaints or symptoms, avoid further exposure.
- Skin contact** : Wash with plenty of soap and water. Remove contaminated clothing and shoes. Wash contaminated clothing thoroughly with water before removing it, or wear gloves. Continue to rinse for at least 10 minutes. Get medical attention. In the event of any complaints or symptoms, avoid further exposure. Wash clothing before reuse. Clean shoes thoroughly before reuse.
- Ingestion** : Wash out mouth with water. Remove dentures if any. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Get medical attention. If necessary, call a poison center or physician. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

### Most important symptoms/effects, acute and delayed

#### Potential acute health effects

- Eye contact** : Causes serious eye irritation.

## Section 4. First aid measures

- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause respiratory irritation. May cause allergy or asthma symptoms or breathing difficulties if inhaled.
- Skin contact** : Causes skin irritation. May cause an allergic skin reaction.
- Ingestion** : Can cause central nervous system (CNS) depression.

### Over-exposure signs/symptoms

- Eye contact** : Adverse symptoms may include the following:  
pain or irritation  
watering  
redness
- Inhalation** : Adverse symptoms may include the following:  
respiratory tract irritation  
coughing  
wheezing and breathing difficulties  
asthma  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness
- Skin contact** : Adverse symptoms may include the following:  
irritation  
redness
- Ingestion** : No specific data.

### Indication of immediate medical attention and special treatment needed, if necessary

- Notes to physician** : In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
- Specific treatments** : No specific treatment.
- Protection of first-aiders** : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

See toxicological information (Section 11)

## Section 5. Fire-fighting measures

### Extinguishing media

- Suitable extinguishing media** : Use dry chemical, CO<sub>2</sub>, water spray (fog) or foam.
- Unsuitable extinguishing media** : Do not use water jet.

- Specific hazards arising from the chemical** : Flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Vapors may accumulate in low or confined areas or travel a considerable distance to a source of ignition and flash back.

- Hazardous thermal decomposition products** : Decomposition products may include the following materials:  
carbon dioxide  
carbon monoxide  
nitrogen oxides

## Section 5. Fire-fighting measures

- Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.
- Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.
- Remark** : Flammable liquid.

## Section 6. Accidental release measures

### Personal precautions, protective equipment and emergency procedures

- For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.
- For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

- Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

### Methods and materials for containment and cleaning up

- Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.
- Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

## Section 7. Handling and storage

### Precautions for safe handling

- Protective measures** : Put on appropriate personal protective equipment (see Section 8). Persons with a history of skin sensitization problems or asthma, allergies or chronic or recurrent respiratory disease should not be employed in any process in which this product is used. Do not get in eyes or on skin or clothing. Do not breathe vapor or mist. Do not ingest. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.



## Section 7. Handling and storage

**Advice on general occupational hygiene** : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

**Conditions for safe storage, including any incompatibilities** : Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use.

## Section 8. Exposure controls/personal protection

### Control parameters

#### Occupational exposure limits (OSHA United States)

Ingredient name	CAS #	Exposure limits
Hexamethylene Diisocyanate Polymer n-Butyl Acetate	28182-81-2 123-86-4	None. <b>NIOSH REL (United States, 10/2020).</b> TWA: 150 ppm 10 hours. TWA: 710 mg/m <sup>3</sup> 10 hours. STEL: 200 ppm 15 minutes. STEL: 950 mg/m <sup>3</sup> 15 minutes. <b>OSHA PEL (United States, 5/2018).</b> TWA: 150 ppm 8 hours. TWA: 710 mg/m <sup>3</sup> 8 hours. <b>ACGIH TLV (United States, 1/2023). [Butyl acetates all isomers]</b> STEL: 150 ppm 15 minutes. TWA: 50 ppm 8 hours.
2-Butoxyethyl Acetate	112-07-2	<b>NIOSH REL (United States, 10/2020).</b> TWA: 5 ppm 10 hours. TWA: 33 mg/m <sup>3</sup> 10 hours. <b>ACGIH TLV (United States, 1/2023).</b> TWA: 20 ppm 8 hours.
Ethyl 3-Ethoxypropionate Methyl n-Amyl Ketone	763-69-9 110-43-0	None. <b>ACGIH TLV (United States, 1/2023).</b> TWA: 50 ppm 8 hours. TWA: 233 mg/m <sup>3</sup> 8 hours. <b>NIOSH REL (United States, 10/2020).</b> TWA: 100 ppm 10 hours. TWA: 465 mg/m <sup>3</sup> 10 hours. <b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours. TWA: 465 mg/m <sup>3</sup> 8 hours.
2-methoxy-1-methylethyl acetate	108-65-6	<b>OARS WEEL (United States, 4/2022).</b> TWA: 50 ppm 8 hours.
Hexamethylene Diisocyanate (max.)	822-06-0	<b>ACGIH TLV (United States, 1/2023).</b> TWA: 0.005 ppm 8 hours. TWA: 0.03 mg/m <sup>3</sup> 8 hours. <b>NIOSH REL (United States, 10/2020).</b> TWA: 0.005 ppm 10 hours. TWA: 0.035 mg/m <sup>3</sup> 10 hours.

## Section 8. Exposure controls/personal protection

CEIL: 0.02 ppm 10 minutes.  
CEIL: 0.14 mg/m<sup>3</sup> 10 minutes.

### Occupational exposure limits (Canada)

Ingredient name	CAS #	Exposure limits
Hexamethylene Diisocyanate Polymer	28182-81-2	<b>CA Quebec Provincial (Canada, 6/2022).</b> <b>[Isocyanate oligomers] Skin sensitizer.</b> <b>Inhalation sensitizer.</b>
n-butyl acetate	123-86-4	<b>CA Alberta Provincial (Canada, 6/2018).</b> 15 min OEL: 200 ppm 15 minutes. 15 min OEL: 950 mg/m <sup>3</sup> 15 minutes. 8 hrs OEL: 150 ppm 8 hours. 8 hrs OEL: 713 mg/m <sup>3</sup> 8 hours. <b>CA Saskatchewan Provincial (Canada, 7/2013).</b> STEL: 200 ppm 15 minutes. TWA: 150 ppm 8 hours. <b>CA Ontario Provincial (Canada, 6/2019).</b> <b>[butyl acetates, all isomers]</b> STEL: 150 ppm 15 minutes. TWA: 50 ppm 8 hours. <b>CA British Columbia Provincial (Canada, 6/2022).</b> <b>[butyl acetate, all isomers]</b> STEL: 150 ppm 15 minutes. TWA: 50 ppm 8 hours. <b>CA Quebec Provincial (Canada, 6/2022).</b> <b>[butyl acetates (all isomers)]</b> STEV: 150 ppm 15 minutes. TWAEV: 50 ppm 8 hours.
Ethylene glycol butyl ether acetate	112-07-2	<b>CA British Columbia Provincial (Canada, 6/2022).</b> TWA: 20 ppm 8 hours. <b>CA Ontario Provincial (Canada, 6/2019).</b> TWA: 20 ppm 8 hours. <b>CA Alberta Provincial (Canada, 6/2018).</b> 8 hrs OEL: 131 mg/m <sup>3</sup> 8 hours. 8 hrs OEL: 20 ppm 8 hours. <b>CA Saskatchewan Provincial (Canada, 7/2013).</b> STEL: 30 ppm 15 minutes. TWA: 20 ppm 8 hours. <b>CA Quebec Provincial (Canada, 6/2022).</b> TWAEV: 10 ppm 8 hours.
Methyl n-amyl ketone	110-43-0	<b>CA Alberta Provincial (Canada, 6/2018).</b> 8 hrs OEL: 233 mg/m <sup>3</sup> 8 hours. 8 hrs OEL: 50 ppm 8 hours. <b>CA British Columbia Provincial (Canada, 6/2022).</b> TWA: 50 ppm 8 hours. <b>CA Ontario Provincial (Canada, 6/2019).</b> TWA: 25 ppm 8 hours. TWA: 115 mg/m <sup>3</sup> 8 hours. <b>CA Quebec Provincial (Canada, 6/2022).</b> TWAEV: 50 ppm 8 hours. TWAEV: 233 mg/m <sup>3</sup> 8 hours. <b>CA Saskatchewan Provincial (Canada,</b>

## Section 8. Exposure controls/personal protection

Hexamethylene diisocyanate	822-06-0	<p>7/2013).            STEL: 60 ppm 15 minutes.            TWA: 50 ppm 8 hours.  <b>CA Alberta Provincial (Canada, 6/2018).</b>            8 hrs OEL: 0.005 ppm 8 hours.            8 hrs OEL: 0.03 mg/m<sup>3</sup> 8 hours.  <b>CA British Columbia Provincial (Canada, 6/2022). Inhalation sensitizer.</b>            TWA: 0.005 ppm 8 hours.            C: 0.01 ppm  <b>CA Quebec Provincial (Canada, 6/2022). Skin sensitizer. Inhalation sensitizer.</b>            TWAEV: 0.005 ppm 8 hours.            TWAEV: 0.034 mg/m<sup>3</sup> 8 hours.  <b>CA Saskatchewan Provincial (Canada, 7/2013).</b>            STEL: 0.015 ppm 15 minutes.            TWA: 0.005 ppm 8 hours.  <b>CA Ontario Provincial (Canada, 6/2019). [Isocyanates, organic compounds]</b>            Ceiling Limit: 0.02 ppm            TWA: 0.005 ppm 8 hours.</p>
----------------------------	----------	---

### Occupational exposure limits (Mexico)

	CAS #	Exposure limits
n-Butyl Acetate	123-86-4	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 150 ppm 8 hours. STEL: 200 ppm 15 minutes.
2-Butoxyethyl Acetate	112-07-2	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 20 ppm 8 hours.
Methyl n-Amyl Ketone	110-43-0	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 50 ppm 8 hours.

### Biological exposure indices (United States)

Ingredient name	Exposure indices
Hexamethylene Diisocyanate (max.)	<b>ACGIH BEI (United States, 1/2023)</b> BEI: 15 µg/g creatinine, 1,6-hexamethylene diamine [in urine]. Sampling time: end of shift.

### Biological exposure indices (Canada)

No exposure indices known.

### Biological exposure indices (Mexico)

No exposure indices known.

### Appropriate engineering controls

: Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

### Environmental exposure controls

: Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

## Section 8. Exposure controls/personal protection

### Individual protection measures

- Hygiene measures** : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Contaminated work clothing should not be allowed out of the workplace. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.
- Eye/face protection** : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: chemical splash goggles.
- Skin protection**
- Hand protection** : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.
- Body protection** : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear anti-static protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.
- Other skin protection** : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.
- Respiratory protection** : Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use.

## Section 9. Physical and chemical properties

The conditions of measurement of all properties are at standard temperature and pressure unless otherwise indicated.

### Appearance

- Physical state** : Liquid.
- Color** : Not available.
- Odor** : Not available.
- Odor threshold** : Not available.
- pH** : Not applicable.
- Melting point/freezing point** : Not available.
- Boiling point, initial boiling point, and boiling range** : 123°C (253.4°F)
- Flash point** : Closed cup: 27°C (80.6°F) [Pensky-Martens Closed Cup]
- Evaporation rate** : 1 (butyl acetate = 1)
- Flammability** : Flammable liquid.
- Lower and upper explosion limit/flammability limit** : Lower: 0.5%  
Upper: 13.1%
- Vapor pressure** : 1.3 kPa (10 mm Hg)
- Relative vapor density** : 3.94 [Air = 1]
- Relative density** : 1.05

## Section 9. Physical and chemical properties

Solubility(ies) :

Media	Result
cold water	Not soluble

Partition coefficient: n-octanol/water : Not applicable.

Auto-ignition temperature : Not available.

Decomposition temperature : Not available.

Viscosity : Kinematic (40°C (104°F)): >20.5 mm<sup>2</sup>/s (>20.5 cSt)

Molecular weight : Not applicable.

Heat of combustion : 9.451 kJ/g

## Section 10. Stability and reactivity

Reactivity : No specific test data related to reactivity available for this product or its ingredients.

Chemical stability : The product is stable.

Possibility of hazardous reactions : Under normal conditions of storage and use, hazardous reactions will not occur.

Conditions to avoid : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.

Incompatible materials : Reactive or incompatible with the following materials:  
oxidizing materials

Hazardous decomposition products : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

## Section 11. Toxicological information

### Information on toxicological effects

#### Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Hexamethylene Diisocyanate Polymer	LC50 Inhalation Dusts and mists	Rat	18500 mg/m <sup>3</sup>	1 hours
n-Butyl Acetate	LD50 Dermal	Rabbit	>17600 mg/kg	-
	LD50 Oral	Rat	10768 mg/kg	-
2-Butoxyethyl Acetate	LD50 Dermal	Rabbit	1500 mg/kg	-
	LD50 Oral	Rat	2400 mg/kg	-
Ethyl 3-Ethoxypropionate	LD50 Oral	Rat	3200 mg/kg	-
Methyl n-Amyl Ketone	LD50 Oral	Rat	1600 mg/kg	-
2-methoxy-1-methylethyl acetate	LD50 Dermal	Rabbit	>5 g/kg	-
	LD50 Oral	Rat	8532 mg/kg	-
Hexamethylene Diisocyanate (max.)	LC50 Inhalation Dusts and mists	Rat	124 mg/m <sup>3</sup>	4 hours

#### Irritation/Corrosion

## Section 11. Toxicological information

Product/ingredient name	Result	Species	Score	Exposure	Observation
Hexamethylene Diisocyanate Polymer	Eyes - Moderate irritant	Rabbit	-	100 mg	-
n-Butyl Acetate	Skin - Moderate irritant	Rabbit	-	500 mg	-
	Eyes - Moderate irritant	Rabbit	-	100 mg	-
	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
2-Butoxyethyl Acetate	Eyes - Mild irritant	Rabbit	-	24 hours 500 mg	-
Ethyl 3-Ethoxypropionate	Skin - Mild irritant	Rabbit	-	500 mg	-
	Skin - Mild irritant	Rabbit	-	24 hours 500 mg	-
Methyl n-Amyl Ketone	Skin - Mild irritant	Rabbit	-	24 hours 14 mg	-

### Sensitization

Not available.

### Mutagenicity

Not available.

### Carcinogenicity

Not available.

### Reproductive toxicity

Not available.

### Teratogenicity

Not available.

### Specific target organ toxicity (single exposure)

Name	Category	Route of exposure	Target organs
Hexamethylene Diisocyanate Polymer	Category 3	-	Respiratory tract irritation
n-Butyl Acetate	Category 3	-	Narcotic effects
Methyl n-Amyl Ketone	Category 3	-	Respiratory tract irritation
2-methoxy-1-methylethyl acetate	Category 3	-	Narcotic effects
Hexamethylene Diisocyanate (max.)	Category 3	-	Narcotic effects
			Respiratory tract irritation

### Specific target organ toxicity (repeated exposure)

Name	Category	Route of exposure	Target organs
Methyl n-Amyl Ketone	Category 2	-	-

### Aspiration hazard

Not available.

**Information on the likely routes of exposure** : Not available.

### Potential acute health effects

**Eye contact** : Causes serious eye irritation.

## Section 11. Toxicological information

- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness. May cause respiratory irritation. May cause allergy or asthma symptoms or breathing difficulties if inhaled.
- Skin contact** : Causes skin irritation. May cause an allergic skin reaction.
- Ingestion** : Can cause central nervous system (CNS) depression.

### Symptoms related to the physical, chemical and toxicological characteristics

- Eye contact** : Adverse symptoms may include the following:  
pain or irritation  
watering  
redness
- Inhalation** : Adverse symptoms may include the following:  
respiratory tract irritation  
coughing  
wheezing and breathing difficulties  
asthma  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness
- Skin contact** : Adverse symptoms may include the following:  
irritation  
redness
- Ingestion** : No specific data.

### Delayed and immediate effects and also chronic effects from short and long term exposure

#### Short term exposure

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.

#### Long term exposure

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.

#### Potential chronic health effects

Not available.

- General** : May cause damage to organs through prolonged or repeated exposure. Once sensitized, a severe allergic reaction may occur when subsequently exposed to very low levels.
- Carcinogenicity** : No known significant effects or critical hazards.
- Mutagenicity** : No known significant effects or critical hazards.
- Teratogenicity** : No known significant effects or critical hazards.
- Developmental effects** : No known significant effects or critical hazards.
- Fertility effects** : No known significant effects or critical hazards.

### Numerical measures of toxicity

#### Acute toxicity estimates

## Section 11. Toxicological information

Route	ATE value
Oral	15902.12 mg/kg
Dermal	26375.5 mg/kg
Inhalation (vapors)	120.67 mg/l
Inhalation (dusts and mists)	6.93 mg/l

## Section 12. Ecological information

### Toxicity

Product/ingredient name	Result	Species	Exposure
n-Butyl Acetate	Acute LC50 32 mg/l Marine water	Crustaceans - <i>Artemia salina</i>	48 hours
	Acute LC50 18000 µg/l Fresh water	Fish - <i>Pimephales promelas</i>	96 hours
Methyl n-Amyl Ketone	Acute LC50 131000 µg/l Fresh water	Fish - <i>Pimephales promelas</i>	96 hours

### Persistence and degradability

Product/ingredient name	Aquatic half-life	Photolysis	Biodegradability
n-Butyl Acetate	-	-	Readily
2-Butoxyethyl Acetate	-	-	Readily
Methyl n-Amyl Ketone	-	-	Readily

### Bioaccumulative potential

Product/ingredient name	LogP <sub>ow</sub>	BCF	Potential
Hexamethylene Diisocyanate Polymer	-	367.7	Low
Hexamethylene Diisocyanate (max.)	-	57.63	Low

### Mobility in soil

Soil/water partition coefficient ( $K_{oc}$ ) : Not available.






Other adverse effects : No known significant effects or critical hazards.

## Section 13. Disposal considerations

**Disposal methods** : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.



## Section 14. Transport information

	DOT Classification	TDG Classification	Mexico Classification	IATA	IMDG
UN number	UN1263	UN1263	UN1263	UN1263	UN1263
UN proper shipping name	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL
Transport hazard class(es)	3 	3 	3 	3 	3 
Packing group	III	III	III	III	III
Environmental hazards	No.	No.	No.	No.	No.
Additional information	-  <b>ERG No.</b> 128	Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.18-2.19 (Class 3).  <b>ERG No.</b> 128	-  <b>ERG No.</b> 128	-	<b>Emergency schedules</b> F-E, S-E

**Special precautions for user :** Multi-modal shipping descriptions are provided for informational purposes and do not consider container sizes. The presence of a shipping description for a particular mode of transport (sea, air, etc.), does not indicate that the product is packaged suitably for that mode of transport. All packaging must be reviewed for suitability prior to shipment, and compliance with the applicable regulations is the sole responsibility of the person offering the product for transport. People loading and unloading dangerous goods must be trained on all of the risks deriving from the substances and on all actions in case of emergency situations.

**Transport in bulk according to IMO instruments :** Not available.

**Proper shipping name :** Not available.

## Section 15. Regulatory information

### SARA 313

SARA 313 (40 CFR 372.45) supplier notification can be found on the Environmental Data Sheet.

### California Prop. 65

Not applicable.

### International regulations

#### Montreal Protocol

## Section 15. Regulatory information

Not listed.

### Stockholm Convention on Persistent Organic Pollutants

Not listed.

**International lists** :

- Australia inventory (AIIC): Not determined.
- China inventory (IECSC): Not determined.
- Japan inventory (CSCL): Not determined.
- Japan inventory (ISHL): Not determined.
- Korea inventory (KECI): Not determined.
- New Zealand Inventory of Chemicals (NZIoC): Not determined.
- Philippines inventory (PICCS): Not determined.
- Taiwan Chemical Substances Inventory (TCSI): Not determined.
- Thailand inventory: Not determined.
- Turkey inventory: Not determined.
- Vietnam inventory: Not determined.

## Section 16. Other information

### Hazardous Material Information System (U.S.A.)

Health	*	3
Flammability		3
Physical hazards		0

The customer is responsible for determining the PPE code for this material. For more information on HMIS® Personal Protective Equipment (PPE) codes, consult the HMIS® Implementation Manual.

Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks. Although HMIS® ratings and the associated label are not required on SDSs or products leaving a facility under 29 CFR 1910.1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered trademark and service mark of the American Coatings Association, Inc.

### Procedure used to derive the classification

Classification	Justification
FLAMMABLE LIQUIDS - Category 3	On basis of test data
SKIN CORROSION/IRRITATION - Category 2	Calculation method
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A	Calculation method
RESPIRATORY SENSITIZATION - Category 1	Calculation method
SKIN SENSITIZATION - Category 1	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 2	Calculation method

### History

**Date of printing** : 9/13/2023  
**Date of issue/Date of revision** : 9/13/2023  
**Date of previous issue** : 6/9/2023  
**Version** : 17

## Section 16. Other information

**Key to abbreviations**

- : ATE = Acute Toxicity Estimate
- BCF = Bioconcentration Factor
- GHS = Globally Harmonized System of Classification and Labelling of Chemicals
- IATA = International Air Transport Association
- IBC = Intermediate Bulk Container
- IMDG = International Maritime Dangerous Goods
- LogPow = logarithm of the octanol/water partition coefficient
- MARPOL = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)
- N/A = Not available
- SGG = Segregation Group
- UN = United Nations

▣ Indicates information that has changed from previously issued version.

### Notice to reader

It is recommended that each customer or recipient of this Safety Data Sheet (SDS) study it carefully and consult resources, as necessary or appropriate, to become aware of and understand the data contained in this SDS and any hazards associated with the product. This information is provided in good faith and believed to be accurate as of the effective date herein. However, no warranty, express or implied, is given. The information presented here applies only to the product as shipped. The addition of any material can change the composition, hazards and risks of the product. Products shall not be repackaged, modified, or tinted except as specifically instructed by the manufacturer, including but not limited to the incorporation of products not specified by the manufacturer, or the use or addition of products in proportions not specified by the manufacturer. Regulatory requirements are subject to change and may differ between various locations and jurisdictions. The customer/buyer/user is responsible to ensure that his activities comply with all country, federal, state, provincial or local laws. The conditions for use of the product are not under the control of the manufacturer; the customer/buyer/user is responsible to determine the conditions necessary for the safe use of this product. The customer/buyer/user should not use the product for any purpose other than the purpose shown in the applicable section of this SDS without first referring to the supplier and obtaining written handling instructions. Due to the proliferation of sources for information such as manufacturer-specific SDS, the manufacturer cannot be responsible for SDSs obtained from any other source.

# SAFETY DATA SHEET

GH1096

## Section 1. Identification

**Product name** : GENESIS® HARDENER LOW VOC SINGLE STAGE HARDENER

**Product code** : GH1096

**Other means of identification** : Not available.

**Product type** : Liquid.

**Relevant identified uses of the substance or mixture and uses advised against**

Paint or paint related material.

**Manufacturer** : The Sherwin-Williams Company  
4440 Warrensville Center Road  
Warrensville Heights, OH 44128

**Emergency telephone number of the company** : US / Canada: (800) 424-9300  
Mexico: 55-4160-8800 / 55-4160-8819 Monday to Friday from 8:30 a.m. to 5:30 p.m.

**Product Information Telephone Number** : US / Canada: (800) 798-5872  
Mexico: 800-022-7926

**Transportation Emergency Telephone Number** : US / Canada: (800) 424-9300  
Mexico: SETIQ 800-00-214-00 / 55-5559-1588 Available 24 hours and 365 days a year

## Section 2. Hazards identification

**OSHA/HCS status** : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

**Classification of the substance or mixture** : FLAMMABLE LIQUIDS - Category 3  
ACUTE TOXICITY (inhalation) - Category 4  
SKIN CORROSION/IRRITATION - Category 2  
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A  
RESPIRATORY SENSITIZATION - Category 1  
SKIN SENSITIZATION - Category 1  
CARCINOGENICITY - Category 2  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3  
Percentage of the mixture consisting of ingredient(s) of unknown acute toxicity: 33.2% (dermal), 33.2% (inhalation)

**GHS label elements**

**Hazard pictograms** :



**Signal word** : Danger

## Section 2. Hazards identification

**Hazard statements** : Flammable liquid and vapor.  
Causes skin irritation.  
May cause an allergic skin reaction.  
Causes serious eye irritation.  
Harmful if inhaled.  
May cause allergy or asthma symptoms or breathing difficulties if inhaled.  
May cause respiratory irritation.  
Suspected of causing cancer.

### Precautionary statements

**Prevention** : Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Wear protective gloves, protective clothing and eye or face protection. Wear respiratory protection. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating or lighting equipment. Use non-sparking tools. Take action to prevent static discharges. Use only outdoors or in a well-ventilated area. Avoid breathing vapor. Wash thoroughly after handling. Contaminated work clothing must not be allowed out of the workplace.

**Response** : IF exposed or concerned: Get medical advice or attention. IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER or doctor if you feel unwell. If experiencing respiratory symptoms: Call a POISON CENTER or doctor. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water. Wash contaminated clothing before reuse. IF ON SKIN: Wash with plenty of water. If skin irritation or rash occurs: Get medical advice or attention. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If eye irritation persists: Get medical advice or attention.

**Storage** : Store locked up. Store in a well-ventilated place. Keep container tightly closed. Keep cool.

**Disposal** : Dispose of contents and container in accordance with all local, regional, national and international regulations.

### Supplemental label elements

DELAYED EFFECTS FROM LONG TERM OVEREXPOSURE. Contains solvents which can cause permanent brain and nervous system damage. Intentional misuse by deliberately concentrating and inhaling the contents can be harmful or fatal. WARNING: This product contains a chemical known to the State of California to cause cancer. FOR PROFESSIONAL USE ONLY. This product must be mixed with other components before use. Before opening the packages, READ AND FOLLOW WARNING LABELS ON ALL COMPONENTS. VAPOR AND SPRAY MIST HARMFUL. Gives off harmful vapor of solvents and isocyanates. DO NOT USE IF YOU HAVE CHRONIC (LONG-TERM) LUNG OR BREATHING PROBLEMS, OR IF YOU HAVE EVER HAD A REACTION TO ISOCYANATES. USE ONLY WITH ADEQUATE VENTILATION. WHERE OVERSPRAY IS PRESENT, A POSITIVE PRESSURE AIR SUPPLIED RESPIRATOR (NIOSH approved) SHOULD BE WORN TO PREVENT EXPOSURE. IF UNAVAILABLE, AN APPROPRIATE PROPERLY FITTED APPROVED NIOSH VAPOR/PARTICULATE RESPIRATOR MAY BE EFFECTIVE. Follow directions for respirator use. Wear the respirator for the whole time of spraying and until all vapors and mists are gone. If you have any breathing problems during use, LEAVE THE AREA and get fresh air. If problems remain or happen later, IMMEDIATELY call a doctor - If not available get emergency medical treatment. Have this label with you. Reacts with water in closed container to produce pressure which may cause container to burst. Please refer to the SDS for additional information. Keep out of reach of children. Do not transfer contents to other containers for storage.

**Hazards not otherwise classified** : None known.

## Section 3. Composition/information on ingredients

**Substance/mixture** : Mixture  
**Other means of identification** : Not available.

### CAS number/other identifiers

Ingredient name	% by weight	CAS number
Hexamethylene Diisocyanate Polymer	≥50 - ≤75	28182-81-2
p-Chlorobenzotrifluoride	≥25 - ≤50	98-56-6
Hexamethylene Diisocyanate (max.)	≤0.3	822-06-0

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

**There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified and hence require reporting in this section.**

Occupational exposure limits, if available, are listed in Section 8.

## Section 4. First aid measures

### Description of necessary first aid measures

- Eye contact** : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention.
- Inhalation** : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention. If necessary, call a poison center or physician. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband. In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours. In the event of any complaints or symptoms, avoid further exposure.
- Skin contact** : Wash with plenty of soap and water. Remove contaminated clothing and shoes. Wash contaminated clothing thoroughly with water before removing it, or wear gloves. Continue to rinse for at least 10 minutes. Get medical attention. In the event of any complaints or symptoms, avoid further exposure. Wash clothing before reuse. Clean shoes thoroughly before reuse.
- Ingestion** : Wash out mouth with water. Remove dentures if any. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Get medical attention. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

### Most important symptoms/effects, acute and delayed

#### Potential acute health effects

- Eye contact** : Causes serious eye irritation.
- Inhalation** : Harmful if inhaled. May cause respiratory irritation. May cause allergy or asthma symptoms or breathing difficulties if inhaled.
- Skin contact** : Causes skin irritation. May cause an allergic skin reaction.
- Ingestion** : No known significant effects or critical hazards.

## Section 4. First aid measures

### Over-exposure signs/symptoms

- Eye contact** : Adverse symptoms may include the following:  
pain or irritation  
watering  
redness
- Inhalation** : Adverse symptoms may include the following:  
respiratory tract irritation  
coughing  
wheezing and breathing difficulties  
asthma
- Skin contact** : Adverse symptoms may include the following:  
irritation  
redness
- Ingestion** : No specific data.

### Indication of immediate medical attention and special treatment needed, if necessary

- Notes to physician** : In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
- Specific treatments** : No specific treatment.
- Protection of first-aiders** : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

See toxicological information (Section 11)

## Section 5. Fire-fighting measures

### Extinguishing media

- Suitable extinguishing media** : Use dry chemical, CO<sub>2</sub>, water spray (fog) or foam.
- Unsuitable extinguishing media** : Do not use water jet.

**Specific hazards arising from the chemical** : Flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion.

**Hazardous thermal decomposition products** : Decomposition products may include the following materials:  
carbon dioxide  
carbon monoxide  
nitrogen oxides  
halogenated compounds  
carbonyl halides

**Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.

**Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

**Remark** : Flammable liquid.

## Section 6. Accidental release measures

### Personal precautions, protective equipment and emergency procedures

- For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.
- For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

- Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

### Methods and materials for containment and cleaning up

- Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.
- Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

## Section 7. Handling and storage

### Precautions for safe handling

- Protective measures** : Put on appropriate personal protective equipment (see Section 8). Persons with a history of skin sensitization problems or asthma, allergies or chronic or recurrent respiratory disease should not be employed in any process in which this product is used. Avoid exposure - obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Do not get in eyes or on skin or clothing. Do not ingest. Avoid breathing vapor or mist. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.
- Advice on general occupational hygiene** : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.



## Section 7. Handling and storage

**Conditions for safe storage, including any incompatibilities** : Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use.

## Section 8. Exposure controls/personal protection

### Control parameters

#### Occupational exposure limits (OSHA United States)

Ingredient name	CAS #	Exposure limits
Hexamethylene Diisocyanate Polymer	28182-81-2	None.
p-Chlorobenzotrifluoride	98-56-6	None.
Hexamethylene Diisocyanate (max.)	822-06-0	<b>ACGIH TLV (United States, 1/2023).</b> TWA: 0.005 ppm 8 hours. TWA: 0.03 mg/m <sup>3</sup> 8 hours. <b>NIOSH REL (United States, 10/2020).</b> TWA: 0.005 ppm 10 hours. TWA: 0.035 mg/m <sup>3</sup> 10 hours. CEIL: 0.02 ppm 10 minutes. CEIL: 0.14 mg/m <sup>3</sup> 10 minutes.

#### Occupational exposure limits (Canada)

Ingredient name	CAS #	Exposure limits
Hexamethylene Diisocyanate Polymer	28182-81-2	<b>CA Quebec Provincial (Canada, 6/2022).</b> <b>[Isocyanate oligomers] Skin sensitizer. Inhalation sensitizer.</b>
Hexamethylene diisocyanate	822-06-0	<b>CA Alberta Provincial (Canada, 6/2018).</b> 8 hrs OEL: 0.005 ppm 8 hours. 8 hrs OEL: 0.03 mg/m <sup>3</sup> 8 hours. <b>CA British Columbia Provincial (Canada, 6/2022). Inhalation sensitizer.</b> TWA: 0.005 ppm 8 hours. C: 0.01 ppm <b>CA Quebec Provincial (Canada, 6/2022).</b> <b>Skin sensitizer. Inhalation sensitizer.</b> TWA <sub>EV</sub> : 0.005 ppm 8 hours. TWA <sub>EV</sub> : 0.034 mg/m <sup>3</sup> 8 hours. <b>CA Saskatchewan Provincial (Canada, 7/2013).</b> STEL: 0.015 ppm 15 minutes. TWA: 0.005 ppm 8 hours. <b>CA Ontario Provincial (Canada, 6/2019).</b> <b>[Isocyanates, organic compounds]</b> Ceiling Limit: 0.02 ppm TWA: 0.005 ppm 8 hours.

#### Occupational exposure limits (Mexico)

	CAS #	Exposure limits
None.		

#### Biological exposure indices (United States)

## Section 8. Exposure controls/personal protection

Ingredient name	Exposure indices
Hexamethylene Diisocyanate (max.)	<b>ACGIH BEI (United States, 1/2023)</b> BEI: 15 µg/g creatinine, 1,6-hexamethylene diamine [in urine]. Sampling time: end of shift.

### Biological exposure indices (Canada)

No exposure indices known.

### Biological exposure indices (Mexico)

No exposure indices known.

**Appropriate engineering controls** : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

**Environmental exposure controls** : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

### Individual protection measures

**Hygiene measures** : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Contaminated work clothing should not be allowed out of the workplace. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

**Eye/face protection** : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: chemical splash goggles.

### Skin protection

**Hand protection** : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.

**Body protection** : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear anti-static protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.

**Other skin protection** : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

**Respiratory protection** : Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use.

## Section 9. Physical and chemical properties

The conditions of measurement of all properties are at standard temperature and pressure unless otherwise indicated.

### Appearance

Physical state	: Liquid.
Color	: Not available.
Odor	: Not available.
Odor threshold	: Not available.
pH	: Not applicable.
Melting point/freezing point	: Not available.
Boiling point, initial boiling point, and boiling range	: 138°C (280.4°F)
Flash point	: Closed cup: 49°C (120.2°F) [Pensky-Martens Closed Cup]
Evaporation rate	: Not available.
Flammability	: Flammable liquid.
Lower and upper explosion limit/flammability limit	: Lower: 0.9% Upper: 10.5%
Vapor pressure	: 0.71 kPa (5.3 mm Hg)
Relative vapor density	: Not available.
Relative density	: 1.21
Solubility(ies)	:

Media	Result
cold water	Not soluble

Partition coefficient: n-octanol/water	: Not applicable.
Auto-ignition temperature	: Not available.
Decomposition temperature	: Not available.
Viscosity	: Kinematic (40°C (104°F)): <20.5 mm <sup>2</sup> /s (<20.5 cSt)
Molecular weight	: Not applicable.
Heat of combustion	: 14.574 kJ/g

## Section 10. Stability and reactivity

Reactivity	: No specific test data related to reactivity available for this product or its ingredients.
Chemical stability	: The product is stable.
Possibility of hazardous reactions	: Under normal conditions of storage and use, hazardous reactions will not occur.
Conditions to avoid	: Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition.
Incompatible materials	: Reactive or incompatible with the following materials: oxidizing materials
Hazardous decomposition products	: Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Date of issue/Date of revision : 1/18/2024 Date of previous issue : 1/15/2024

GH1096 GENESIS® HARDENER LOW VOC SINGLE STAGE  
HARDENER

Version : 17.02 8/14

SHW-85-NA-GHS-US

# Section 11. Toxicological information

## Information on toxicological effects

### Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Hexamethylene Diisocyanate Polymer	LC50 Inhalation Dusts and mists	Rat	18500 mg/m <sup>3</sup>	1 hours
p-Chlorobenzotrifluoride	LD50 Oral	Rat	13 g/kg	-
Hexamethylene Diisocyanate (max.)	LC50 Inhalation Dusts and mists	Rat	124 mg/m <sup>3</sup>	4 hours

### Irritation/Corrosion

Product/ingredient name	Result	Species	Score	Exposure	Observation
Hexamethylene Diisocyanate Polymer	Eyes - Moderate irritant	Rabbit	-	100 mg	-
	Skin - Moderate irritant	Rabbit	-	500 mg	-

### Sensitization

Not available.

### Mutagenicity

Not available.

### Carcinogenicity

Not available.

### Classification

Product/ingredient name	OSHA	IARC	NTP
p-Chlorobenzotrifluoride	-	2B	-

### Reproductive toxicity

Not available.

### Teratogenicity

Not available.

### Specific target organ toxicity (single exposure)

Name	Category	Route of exposure	Target organs
Hexamethylene Diisocyanate Polymer	Category 3	-	Respiratory tract irritation
p-Chlorobenzotrifluoride	Category 3	-	Respiratory tract irritation
Hexamethylene Diisocyanate (max.)	Category 3	-	Respiratory tract irritation

### Specific target organ toxicity (repeated exposure)

Not available.

### Aspiration hazard

Not available.

Information on the likely routes of exposure : Not available.

### Potential acute health effects

Eye contact : Causes serious eye irritation.

## Section 11. Toxicological information

- Inhalation** : Harmful if inhaled. May cause respiratory irritation. May cause allergy or asthma symptoms or breathing difficulties if inhaled.
- Skin contact** : Causes skin irritation. May cause an allergic skin reaction.
- Ingestion** : No known significant effects or critical hazards.

### Symptoms related to the physical, chemical and toxicological characteristics

- Eye contact** : Adverse symptoms may include the following:  
pain or irritation  
watering  
redness
- Inhalation** : Adverse symptoms may include the following:  
respiratory tract irritation  
coughing  
wheezing and breathing difficulties  
asthma
- Skin contact** : Adverse symptoms may include the following:  
irritation  
redness
- Ingestion** : No specific data.

### Delayed and immediate effects and also chronic effects from short and long term exposure

#### Short term exposure

- Potential immediate effects** : Not available.
- Potential delayed effects** : Not available.

#### Long term exposure

- Potential immediate effects** : Not available.
- Potential delayed effects** : Not available.

#### Potential chronic health effects

Not available.

- General** : Once sensitized, a severe allergic reaction may occur when subsequently exposed to very low levels.
- Carcinogenicity** : Suspected of causing cancer. Risk of cancer depends on duration and level of exposure.
- Mutagenicity** : No known significant effects or critical hazards.
- Teratogenicity** : No known significant effects or critical hazards.
- Developmental effects** : No known significant effects or critical hazards.
- Fertility effects** : No known significant effects or critical hazards.

### Numerical measures of toxicity

#### Acute toxicity estimates

Route	ATE value
Inhalation (dusts and mists)	4.63 mg/l

## Section 12. Ecological information

### Toxicity

Not available.

### Persistence and degradability

Not available.

### Bioaccumulative potential

Product/ingredient name	LogP <sub>ow</sub>	BCF	Potential
Hexamethylene Diisocyanate Polymer	-	367.7	Low
Hexamethylene Diisocyanate (max.)	-	57.63	Low

### Mobility in soil







Soil/water partition coefficient (K<sub>oc</sub>) : Not available.

Other adverse effects : No known significant effects or critical hazards.

## Section 13. Disposal considerations

**Disposal methods** : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

## Section 14. Transport information

	DOT Classification	TDG Classification	Mexico Classification	IATA	IMDG
UN number	UN1263	UN1263	UN1263	UN1263	UN1263
UN proper shipping name	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL	PAINT RELATED MATERIAL. Marine pollutant (p-Chlorobenzotrifluoride)
Transport hazard class(es)	3 	3 	3 	3 	3  

## Section 14. Transport information

Packing group	III	III	III	III	III
<b>Environmental hazards</b>	No.	No.	No.	Yes. The environmentally hazardous substance mark is not required.	Yes.
<b>Additional information</b>	This product may be re-classified as "Combustible Liquid," unless transported by vessel or aircraft. Non-bulk packages (less than or equal to 119 gal) of combustible liquids are not regulated as hazardous materials. <b>ERG No.</b> 128	Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.18-2.19 (Class 3). <b>ERG No.</b> 128	- <b>ERG No.</b> 128	The environmentally hazardous substance mark may appear if required by other transportation regulations.	The marine pollutant mark is not required when transported in sizes of ≤5 L or ≤5 kg. <b>Emergency schedules F-E, S-E</b>

**Special precautions for user** : Multi-modal shipping descriptions are provided for informational purposes and do not consider container sizes. The presence of a shipping description for a particular mode of transport (sea, air, etc.), does not indicate that the product is packaged suitably for that mode of transport. All packaging must be reviewed for suitability prior to shipment, and compliance with the applicable regulations is the sole responsibility of the person offering the product for transport. People loading and unloading dangerous goods must be trained on all of the risks deriving from the substances and on all actions in case of emergency situations.

**Transport in bulk according to IMO instruments** : Not available.

**Proper shipping name** : Not available.

## Section 15. Regulatory information

### SARA 313

SARA 313 (40 CFR 372.45) supplier notification can be found on the Environmental Data Sheet.

### California Prop. 65

WARNING: This product contains a chemical known to the State of California to cause cancer.

### International regulations

#### Montreal Protocol

Not listed.

#### Stockholm Convention on Persistent Organic Pollutants

Not listed.

## Section 15. Regulatory information

**International lists** :

- Australia inventory (AIC): Not determined.
- China inventory (IECSC): Not determined.
- Japan inventory (CSCL): Not determined.
- Japan inventory (ISHL): Not determined.
- Korea inventory (KECI): Not determined.
- New Zealand Inventory of Chemicals (NZIoC): Not determined.
- Philippines inventory (PICCS): Not determined.
- Taiwan Chemical Substances Inventory (TCSI): Not determined.
- Thailand inventory: Not determined.
- Turkey inventory: Not determined.
- Vietnam inventory: Not determined.

## Section 16. Other information

### Hazardous Material Information System (U.S.A.)

Health	*	3
Flammability		2
Physical hazards		0

The customer is responsible for determining the PPE code for this material. For more information on HMIS® Personal Protective Equipment (PPE) codes, consult the HMIS® Implementation Manual.

Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks. Although HMIS® ratings and the associated label are not required on SDSs or products leaving a facility under 29 CFR 1910.1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered trademark and service mark of the American Coatings Association, Inc.

### Procedure used to derive the classification

Classification	Justification
FLAMMABLE LIQUIDS - Category 3	On basis of test data
ACUTE TOXICITY (inhalation) - Category 4	Calculation method
SKIN CORROSION/IRRITATION - Category 2	Calculation method
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A	Calculation method
RESPIRATORY SENSITIZATION - Category 1	Calculation method
SKIN SENSITIZATION - Category 1	Calculation method
CARCINOGENICITY - Category 2	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Respiratory tract irritation) - Category 3	Calculation method

### History

**Date of printing** : 1/18/2024

**Date of issue/Date of revision** : 1/18/2024

**Date of previous issue** : 1/15/2024

**Version** : 17.02

**Key to abbreviations** :

- ATE = Acute Toxicity Estimate
- BCF = Bioconcentration Factor
- GHS = Globally Harmonized System of Classification and Labelling of Chemicals
- IATA = International Air Transport Association
- IBC = Intermediate Bulk Container
- IMDG = International Maritime Dangerous Goods
- LogPow = logarithm of the octanol/water partition coefficient
- MARPOL = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)



## Section 16. Other information

N/A = Not available  
SGG = Segregation Group  
UN = United Nations

▣ Indicates information that has changed from previously issued version.

### Notice to reader

It is recommended that each customer or recipient of this Safety Data Sheet (SDS) study it carefully and consult resources, as necessary or appropriate, to become aware of and understand the data contained in this SDS and any hazards associated with the product. This information is provided in good faith and believed to be accurate as of the effective date herein. However, no warranty, express or implied, is given. The information presented here applies only to the product as shipped. The addition of any material can change the composition, hazards and risks of the product. Products shall not be repackaged, modified, or tinted except as specifically instructed by the manufacturer, including but not limited to the incorporation of products not specified by the manufacturer, or the use or addition of products in proportions not specified by the manufacturer. Regulatory requirements are subject to change and may differ between various locations and jurisdictions. The customer/buyer/user is responsible to ensure that his activities comply with all country, federal, state, provincial or local laws. The conditions for use of the product are not under the control of the manufacturer; the customer/buyer/user is responsible to determine the conditions necessary for the safe use of this product. The customer/buyer/user should not use the product for any purpose other than the purpose shown in the applicable section of this SDS without first referring to the supplier and obtaining written handling instructions. Due to the proliferation of sources for information such as manufacturer-specific SDS, the manufacturer cannot be responsible for SDSs obtained from any other source.

# SAFETY DATA SHEET

3462779 26449840

## Section 1. Identification

**Product name** : G2 - Genesis M  
FEDERAL EXPRESS - FEDEX / 65199 / FEDEX WHITE

**Product code** : 3462779 26449840

**Other means of identification** : Not available.

**Product type** : Liquid.

**Relevant identified uses of the substance or mixture and uses advised against**  
Paint or paint related material. S

**Manufacturer** : The Sherwin-Williams Company  
: 4440 Warrensville Center Road  
Warrensville Heights, OHIO 44128

**Emergency telephone number of the company** : (216) 566-2917

**Product Information Telephone Number** : (800) 798-5872

**Regulatory Information: Telephone Number** : (216) 566-2902

**Transportation Emergency Telephone Number** : (800) 424-9300

## Section 2. Hazards identification

**OSHA/HCS status** : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

**Classification of the substance or mixture** : FLAMMABLE LIQUIDS - Category 2  
SKIN CORROSION/IRRITATION - Category 2  
**GHS label elements** : SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A  
SKIN SENSITIZATION - Category 1  
CARCINOGENICITY - Category 2  
TOXIC TO REPRODUCTION - Category 2  
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) Category 3  
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 2

**Hazard pictograms** :



**Signal word** : Danger

## Section 2. Hazards identification

**Hazard statements** : Highly flammable liquid and vapor.

Causes skin irritation.  
 May cause an allergic skin reaction.  
 Causes serious eye irritation.  
 May cause drowsiness or dizziness.  
 Suspected of causing cancer.  
 Suspected of damaging fertility or the unborn child.  
 May cause damage to organs through prolonged or repeated exposure.

**Precautionary statements**

**Prevention**

: Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Wear protective gloves, protective clothing and eye or face protection. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating or lighting equipment. Use non-sparking tools. Take action to prevent static discharges. Use only outdoors or in a well-ventilated area. Do not breathe vapor. Wash thoroughly after handling. Contaminated work clothing must not be allowed out of the workplace.

**Response**

: IF exposed or concerned: Get medical advice or attention. IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER or doctor if you feel unwell. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water. Wash contaminated clothing before reuse. IF ON SKIN: Wash with plenty of water. If skin irritation or rash occurs: Get medical advice or attention. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If eye irritation persists: Get medical advice or attention.

**Storage**

**Disposal**

: Store locked up. Store in a well-ventilated place. Keep container tightly closed. Keep cool.

**Supplemental label elements**

: Dispose of contents and container in accordance with all local, regional, national and international regulations.

DELAYED EFFECTS FROM LONG TERM OVEREXPOSURE. Contains solvents which can cause permanent brain and nervous system damage. Intentional misuse by deliberately concentrating and inhaling the contents can be harmful or fatal. WARNING: This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm. FOR PROFESSIONAL USE ONLY.

Please refer to the SDS for additional information. Keep out of reach of children. Do not transfer contents to other containers for storage.

**Hazards not otherwise classified**

: None known.

**Section 3. Composition/information on ingredients**

Substance/mixture : Mixture  
 Other means of identification CAS number/other identifiers : Not available.

Ingredient name	% by weight	CAS number
Titanium Dioxide	≥25 - ≤50	13463-67-7
Acetone	≤12	67-64-1
n-Butyl Acetate	≤10	123-86-4
Methyl n-Amyl Ketone	≤7.7	110-43-0
Hydroxy Functional Reactive Diluent	≤7.3	105527-30-8
n-Butyl Propionate	≤5	590-01-2
Amorphous Silica	≤3	7631-86-9
Bis(pentamethyl-4-piperidyl)sebacate	≤1	41556-26-7
2-Ethyl-2-(hydroxymethyl)-1,3-propanediol	≤0.3	77-99-6

**Section 3. Composition/information on ingredients**

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

**There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified and hence require reporting in this section.**

Occupational exposure limits, if available, are listed in Section 8.

## Section 4. First aid measures

### Description of necessary first aid measures

- Eye contact** : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention.
- Inhalation** : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention. If necessary, call a poison center or physician. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.
- Skin contact** : Wash with plenty of soap and water. Remove contaminated clothing and shoes. Wash contaminated clothing thoroughly with water before removing it, or wear gloves. Continue to rinse for at least 10 minutes. Get medical attention. In the event of any complaints or symptoms, avoid further exposure. Wash clothing before reuse. Clean shoes thoroughly before reuse.
- Ingestion** : Wash out mouth with water. Remove dentures if any. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Get medical attention. If necessary, call a poison center or physician. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

### Most important symptoms/effects, acute and delayed

#### Potential acute health effects

- Eye contact** : Causes serious eye irritation.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness.
- Skin contact** : Causes skin irritation. May cause an allergic skin reaction.
- Ingestion** : Can cause central nervous system (CNS) depression.

#### Over-exposure signs/symptoms

- Eye contact** : Adverse symptoms may include the following:  
pain or irritation  
watering  
redness
- Inhalation** : Adverse symptoms may include the following:  
nausea or vomiting  
headache  
drowsiness/fatigue  
dizziness/vertigo  
unconsciousness

reduced fetal weight  
increase in fetal deaths

## Section 4. First aid measures

<b>Skin contact</b>	: skeletal malformations : Adverse symptoms may include the following: irritation redness reduced fetal weight increase in fetal deaths skeletal malformations
<b>Ingestion</b>	: Adverse symptoms may include the following: reduced fetal weight increase in fetal deaths skeletal malformations

### Indication of immediate medical attention and special treatment needed, if necessary

<b>Notes to physician</b>	: Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.
<b>Specific treatments</b>	: No specific treatment.
<b>Protection of first-aiders</b>	: No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

See toxicological information (Section 11)

## Section 5. Fire-fighting measures

<b>Extinguishing media</b>	: Use dry chemical, CO <sub>2</sub> , water spray (fog) or foam.
<b>Suitable extinguishing media</b>	: Do not use water jet.
<b>Unsuitable extinguishing media</b>	: Highly flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Vapors may accumulate in low or confined areas or travel a considerable distance to a source of ignition and flash back.
<b>Specific hazards arising from the chemical</b>	: Decomposition products may include the following materials: carbon dioxide carbon monoxide metal oxide/oxides
<b>Hazardous thermal decomposition products</b>	
<b>Special protective actions for fire-fighters</b>	: Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.
<b>Special protective equipment for fire-fighters</b>	: Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

## Section 6. Accidental release measures

### Personal precautions, protective equipment and emergency procedures

- For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.
- For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For nonemergency personnel".

- Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

### Methods and materials for containment and cleaning up

- Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.
- Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

## Section 7. Handling and storage

- Precautions for safe handling** : Put on appropriate personal protective equipment (see Section 8). Persons with a history of skin sensitization problems should not be employed in any process in which this product is used. Avoid exposure - obtain special instructions before use. Avoid exposure during pregnancy. Do not handle until all safety precautions have been read and understood. Do not get in eyes or on skin or clothing. Do not breathe vapor or mist. Do not ingest. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.
- Protective measures**
- Advice on general occupational hygiene** : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

## Section 7. Handling and storage

**Conditions for safe storage**, : Store in accordance with local regulations. Store in a segregated and approved area. **including any incompatibilities** Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use.

## Section 8. Exposure controls/personal protection

### Control parameters

#### Occupational exposure limits (OSHA United States)

Ingredient name	CAS #	Exposure limits
Titanium Dioxide	13463-67-7	<b>ACGIH TLV (United States, 1/2021).</b> TWA: 10 mg/m <sup>3</sup> 8 hours.
Acetone	67-64-1	<b>OSHA PEL (United States, 5/2018).</b> TWA: 15 mg/m <sup>3</sup> 8 hours. Form: Total dust <b>ACGIH TLV (United States, 1/2021).</b> TWA: 250 ppm 8 hours. STEL: 500 ppm 15 minutes. <b>NIOSH REL (United States, 10/2020).</b> TWA: 250 ppm 10 hours. TWA: 590 mg/m <sup>3</sup> 10 hours. <b>OSHA PEL (United States, 5/2018).</b> TWA: 1000 ppm 8 hours. TWA: 2400 mg/m <sup>3</sup> 8 hours.
n-Butyl Acetate	123-86-4	<b>NIOSH REL (United States, 10/2020).</b> TWA: 150 ppm 10 hours. TWA: 710 mg/m <sup>3</sup> 10 hours. STEL: 200 ppm 15 minutes. STEL: 950 mg/m <sup>3</sup> 15 minutes. <b>OSHA PEL (United States, 5/2018).</b> TWA: 150 ppm 8 hours. TWA: 710 mg/m <sup>3</sup> 8 hours. <b>ACGIH TLV (United States, 1/2021).</b> STEL: 150 ppm 15 minutes. TWA: 50 ppm 8 hours.
Methyl n-Amyl Ketone	110-43-0	<b>ACGIH TLV (United States, 1/2021).</b> TWA: 50 ppm 8 hours. TWA: 233 mg/m <sup>3</sup> 8 hours. <b>NIOSH REL (United States, 10/2020).</b> TWA: 100 ppm 10 hours. TWA: 465 mg/m <sup>3</sup> 10 hours. <b>OSHA PEL (United States, 5/2018).</b> TWA: 100 ppm 8 hours. TWA: 465 mg/m <sup>3</sup> 8 hours.
Hydroxy Functional Reactive Diluent	105527-30-8	None.
n-Butyl Propionate	590-01-2	None.
Amorphous Silica	7631-86-9	<b>NIOSH REL (United States, 10/2020).</b> TWA: 6 mg/m <sup>3</sup> 10 hours.



Bis(pentamethyl-4-piperidyl)sebacate	41556-26-7	None.
2-Ethyl-2-(hydroxymethyl)-1,3-propanediol	77-99-6	None.

Occupational exposure limits (Canada)

## **Section 8. Exposure controls/personal protection**

Ingredient name	CAS #	Exposure limits
Titanium dioxide	13463-67-7	<p><b>CA British Columbia Provincial (Canada, 6/2021).</b>  TWA: 10 mg/m<sup>3</sup> 8 hours. Form: Total dust  TWA: 3 mg/m<sup>3</sup> 8 hours. Form: respirable fraction</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>  TWAEV: 10 mg/m<sup>3</sup> 8 hours. Form: Total dust.</p> <p><b>CA Alberta Provincial (Canada, 6/2018).</b>  8 hrs OEL: 10 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>  TWA: 10 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>  STEL: 20 mg/m<sup>3</sup> 15 minutes.  TWA: 10 mg/m<sup>3</sup> 8 hours.</p>
acetone	67-64-1	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>  8 hrs OEL: 1200 mg/m<sup>3</sup> 8 hours.  15 min OEL: 1800 mg/m<sup>3</sup> 15 minutes.  8 hrs OEL: 500 ppm 8 hours.  15 min OEL: 750 ppm 15 minutes.</p> <p><b>CA British Columbia Provincial (Canada, 6/2021).</b>  TWA: 250 ppm 8 hours.  STEL: 500 ppm 15 minutes.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>  TWA: 250 ppm 8 hours.  STEL: 500 ppm 15 minutes.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>  TWAEV: 500 ppm 8 hours.  TWAEV: 1190 mg/m<sup>3</sup> 8 hours.  STEV: 1000 ppm 15 minutes.  STEV: 2380 mg/m<sup>3</sup> 15 minutes.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>  STEL: 750 ppm 15 minutes.  TWA: 500 ppm 8 hours.</p>
n-butyl acetate	123-86-4	<p><b>CA Alberta Provincial (Canada, 6/2018).</b>  15 min OEL: 200 ppm 15 minutes.  15 min OEL: 950 mg/m<sup>3</sup> 15 minutes.  8 hrs OEL: 150 ppm 8 hours.  8 hrs OEL: 713 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b>  STEL: 200 ppm 15 minutes.  TWA: 150 ppm 8 hours.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b>  STEL: 150 ppm 15 minutes.  TWA: 50 ppm 8 hours.</p> <p><b>CA British Columbia Provincial (Canada, 6/2021).</b>  STEL: 150 ppm 15 minutes.  TWA: 50 ppm 8 hours.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b>  STEV: 150 ppm 15 minutes.  TWAEV: 50 ppm 8 hours.</p>

## Section 8. Exposure controls/personal protection

Methyl n-amyl ketone	110-43-0	<p><b>CA Alberta Provincial (Canada, 6/2018).</b> 8 hrs OEL: 233 mg/m<sup>3</sup> 8 hours. 8 hrs OEL: 50 ppm 8 hours.</p> <p><b>CA British Columbia Provincial (Canada, 6/2021).</b> TWA: 50 ppm 8 hours.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b> TWA: 25 ppm 8 hours. TWA: 115 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b> TWA: 50 ppm 8 hours. TWA: 233 mg/m<sup>3</sup> 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b> STEL: 60 ppm 15 minutes. TWA: 50 ppm 8 hours.</p>
Ethylene glycol butyl ether acetate	112-07-2	<p><b>CA British Columbia Provincial (Canada, 6/2021).</b> TWA: 20 ppm 8 hours.</p> <p><b>CA Ontario Provincial (Canada, 6/2019).</b> TWA: 20 ppm 8 hours.</p> <p><b>CA Alberta Provincial (Canada, 6/2018).</b> 8 hrs OEL: 131 mg/m<sup>3</sup> 8 hours. 8 hrs OEL: 20 ppm 8 hours.</p> <p><b>CA Saskatchewan Provincial (Canada, 7/2013).</b> STEL: 30 ppm 15 minutes. TWA: 20 ppm 8 hours.</p> <p><b>CA Quebec Provincial (Canada, 6/2021).</b> TWA: 10 ppm 8 hours.</p>

### Occupational exposure limits (Mexico)

	CAS #	Exposure limits
Acetone	67-64-1	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 500 ppm 8 hours. STEL: 750 ppm 15 minutes.
n-Butyl Acetate	123-86-4	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 150 ppm 8 hours. STEL: 200 ppm 15 minutes.
Methyl n-Amyl Ketone	110-43-0	<b>NOM-010-STPS-2014 (Mexico, 4/2016).</b> TWA: 50 ppm 8 hours.

#### Appropriate engineering controls

: Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

#### Environmental exposure controls

: Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

#### Individual protection measures

## Section 8. Exposure controls/personal protection

- Hygiene measures** : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Contaminated work clothing should not be allowed out of the workplace. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.
- Eye/face protection** : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: chemical splash goggles.
- Skin protection**
- Hand protection** : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.
- Body protection** : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear antistatic protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.
- Other skin protection** : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.
- Respiratory protection** : Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use.

## Section 9. Physical and chemical properties

The conditions of measurement of all properties are at standard temperature and pressure unless otherwise indicated.

### Appearance

- Physical state** :
- Color** : Liquid.
- Odor** : Various
- Odor threshold** : Not available.
- pH** : Not available.
- Melting point/freezing point** : Not applicable.
- Boiling point, initial boiling point, and boiling range** : Not available.  
55°C (131°F)
- Flash point** :
- Evaporation rate** : Closed cup: -17°C (1.4°F) [Pensky-Martens Closed
- Flammability** : Cup] 5.6 (butyl acetate = 1) Not available.
- Lower and upper explosion limit/flammability limit** : Lower: 1.1%  
Upper: 12.8%
- Vapor pressure** : 24 kPa (180 mm Hg)
- Relative vapor density** : 2 [Air = 1]
- Relative density** : 1.29
- :

---

**Solubility**

Not available.

<i>Date of issue</i> / <i>Date of revision</i>	:7/28/2022	<i>Date of previous issue</i>	: No previous validation	<i>Version</i> : 1	9/17
3462779 26449840 G2 - Genesis M FEDERAL EXPRESS - FEDEX / 65199 / FEDEX WHITE				SHW-85-NA-GHS-US	

## Section 11. Toxicological information

## Section 9. Physical and chemical properties

<b>Partition coefficient:</b> noctanol/water	: Not applicable.
<b>Auto-ignition temperature</b>	: Not available.
<b>Decomposition temperature</b>	: Not available.
<b>Viscosity</b>	: Kinematic (40°C (104°F)): >20.5 mm <sup>2</sup> /s (>20.5 cSt)
<b>Molecular weight</b>	: Not applicable.
<b>Aerosol product</b>	:
<b>Heat of combustion</b>	: 13.324 kJ/g

## Section 10. Stability and reactivity

<b>Reactivity</b>	: No specific test data related to reactivity available for this product or its ingredients.
<b>Chemical stability</b>	: The product is stable.
<b>Possibility of hazardous reactions</b>	: Under normal conditions of storage and use, hazardous reactions will not occur.
<b>Conditions to avoid</b>	: Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.
<b>Incompatible materials</b>	: Reactive or incompatible with the following materials: oxidizing materials
<b>Hazardous decomposition products</b>	: Under normal conditions of storage and use, hazardous decomposition products should not be produced.

## Section 11. Toxicological information

### Information on toxicological effects

#### Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Acetone	LD50 Oral	Rat	5800 mg/kg	-
n-Butyl Acetate	LD50 Dermal	Rabbit	>17600 mg/kg	-
	LD50 Oral	Rat	10768 mg/kg	-
Methyl n-Amyl Ketone	LD50 Oral	Rat	1600 mg/kg	-
n-Butyl Propionate	LD50 Dermal	Rabbit	>14 g/kg	-
	LD50 Oral	Rat	11031 mg/kg	-
2-Ethyl-2-(hydroxymethyl) -1,3-propanediol	LD50 Oral	Rat	14000 mg/kg	-

#### Irritation/Corrosion

Product/ingredient name	Result	Species	Score	Exposure	Observation
Titanium Dioxide	Skin - Mild irritant	Human	-	72 hours 300 ug l	-
Acetone	Eyes - Mild irritant	Human	-	186300 ppm	-
	Eyes - Mild irritant	Rabbit	-	10 uL	-
	Eyes - Moderate irritant	Rabbit	-	24 hours 20 mg	-
	Eyes - Severe irritant	Rabbit	-	20 mg	-

## Section 11. Toxicological information

n-Butyl Acetate	Skin - Mild irritant	Rabbit	-	24 hours 500 mg	-
	Skin - Mild irritant	Rabbit	-	395 mg	-
	Eyes - Moderate irritant	Rabbit	-	100 mg	-
	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
Methyl n-Amyl Ketone	Skin - Mild irritant	Rabbit	-	24 hours 14 mg	-
n-Butyl Propionate	Eyes - Moderate irritant	Rabbit	-	0.1 MI	-
	Eyes - Severe irritant	Rabbit	-	100 mg	-
	Skin - Mild irritant	Guinea pig	-	0.3 MI	-
	Skin - Mild irritant	Rabbit	-	0.5 MI	-
	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
Amorphous Silica	Eyes - Mild irritant	Rabbit	-	24 hours 25 mg	-

### Sensitization

Not available.

### Mutagenicity

Not available.

### Carcinogenicity

Not available.

### Classification

Product/ingredient name	OSHA	IARC	NTP
Titanium Dioxide	-	2B	-
Amorphous Silica	-	3	-

### Reproductive toxicity

Not available.

### Teratogenicity

Not available.

### Specific target organ toxicity (single exposure)

Name	Category	Route of exposure	Target organs
Acetone	Category 3	-	Respiratory tract irritation
n-Butyl Acetate	Category 3	-	Narcotic effects
Methyl n-Amyl Ketone	Category 3	-	Narcotic effects
	Category 3	-	Respiratory tract irritation
	Category 3	-	Narcotic effects

### Specific target organ toxicity (repeated exposure)

Name	Category	Route of exposure	Target organs
Acetone	Category 2	-	-
Methyl n-Amyl Ketone	Category 2	-	-

### Aspiration hazard

Not available.



## Section 11. Toxicological information

Information on the likely : Not available. routes of exposure

### Potential acute health effects

- Eye contact** : Causes serious eye irritation.
- Inhalation** : Can cause central nervous system (CNS) depression. May cause drowsiness or dizziness.
- Skin contact** : Causes skin irritation. May cause an allergic skin reaction.
- Ingestion** : Can cause central nervous system (CNS) depression.

### Symptoms related to the physical, chemical and toxicological characteristics

**Eye contact** : Adverse symptoms may include the following:  
pain or irritation watering redness

**Inhalation** : Adverse symptoms may include the following:  
nausea or vomiting headache  
drowsiness/fatigue dizziness/vertigo  
unconsciousness reduced fetal weight  
increase in fetal deaths skeletal malformations

**Skin contact** : Adverse symptoms may include the following:  
irritation redness  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations

**Ingestion** : Adverse symptoms may include the following:  
reduced fetal weight  
increase in fetal deaths  
skeletal malformations

### Delayed and immediate effects and also chronic effects from short and long term exposure Short term exposure

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.

### Long term exposure

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.

### Potential chronic health effects

Not available.

**General** : May cause damage to organs through prolonged or repeated exposure. Once sensitized, a severe allergic reaction may occur when subsequently exposed to very low levels.

**Carcinogenicity** : Suspected of causing cancer. Risk of cancer depends on duration and level of exposure.

**Mutagenicity** : No known significant effects or critical hazards.

**Teratogenicity** : Suspected of damaging the unborn child.

**Developmental effects** : No known significant effects or critical hazards.

**Fertility effects** : Suspected of damaging fertility.

## Section 11. Toxicological information

### Numerical measures of toxicity

#### Acute toxicity estimates

Route	ATE value
Oral	5593.77 mg/kg
Inhalation (vapors)	146.47 mg/l

## Section 12. Ecological information

### Toxicity

Product/ingredient name	Result	Species	Exposure
Titanium Dioxide	Acute LC50 >1000000 µg/l Marine water	Fish - Fundulus heteroclitus	96 hours
	Acute EC50 7200000 µg/l Fresh water	Algae - Selenastrum sp.	96 hours
	Acute LC50 4.42589 ml/L Marine water	Crustaceans - Acartia tonsa	48 hours
		Copepodid	
	Acute LC50 7460000 µg/l Fresh water	Daphnia - Daphnia cucullata	48 hours
	Acute LC50 5600 ppm Fresh water	Fish - Poecilia reticulata	96 hours
	Chronic NOEC 4.95 mg/l Marine water	Algae - Ulva pertusa	96 hours
	Chronic NOEC 0.016 ml/L Fresh water	Crustaceans - Daphniidae	21 days
	Chronic NOEC 0.1 ml/L Fresh water	Daphnia - Daphnia magna	21 days
		Neonate	
n-Butyl Acetate	Acute LC50 32 mg/l Marine water	Fish - Gasterosteus aculeatus	42 days
		Larvae	
Methyl n-Amyl Ketone	Acute LC50 32 mg/l Marine water	Crustaceans - Artemia salina	48 hours
	Acute LC50 18000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
Amorphous Silica	Acute LC50 131000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
	Acute EC50 2.2 g/L Fresh water	Daphnia - Daphnia magna	48 hours
2-Ethyl-2-(hydroxymethyl)-1,3-propanediol	Chronic NOEC 12.5 mg/l Fresh water	Daphnia - Daphnia magna	21 days
		Neonate	
2-Ethyl-2-(hydroxymethyl)-1,3-propanediol	Acute EC50 13000000 µg/l Fresh water	Daphnia - Daphnia magna	48 hours
	Acute LC50 14400000 µg/l Marine water	Fish - Cyprinodon variegatus	96 hours

### Persistence and degradability

Product/ingredient name	Aquatic half-life	Photolysis	Biodegradability
Acetone	-	-	Readily
n-Butyl Acetate	-	-	Readily
Methyl n-Amyl Ketone	-	-	Readily

### Bioaccumulative potential

Product/ingredient name	LogP <sub>ow</sub>	BCF	Potential
2-Ethyl-2-(hydroxymethyl)-1,3-propanediol	-	<1	low

### Mobility in soil

Soil/water partition coefficient (K<sub>oc</sub>) : Not available.






## Section 12. Ecological information

**Other adverse effects** : No known significant effects or critical hazards.

## Section 13. Disposal considerations

**Disposal methods** : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

## Section 14. Transport information

	<b>DOT Classification</b>	<b>TDG Classification</b>	<b>Mexico Classification</b>	<b>IATA</b>	<b>IMDG</b>
<b>UN number</b>	UN1263	UN1263	UN1263	UN1263	UN1263
<b>UN proper shipping name</b>	PAINT	PAINT	PAINT	PAINT	PAINT
<b>Transport hazard class(es)</b>	3 	3 	3 	3 	3 
<b>Packing group</b>	II	II	II	II	II
<b>Environmental hazards</b>	No.	No.	No.	No.	No.
<b>Additional information</b>	-  <b>ERG No.</b> 128	Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.18-2.19 (Class 3).  <b>ERG No.</b> 128	-  <b>ERG No.</b> 128	-	<b>Emergency schedules</b> F-E, S-E

## Section 14. Transport information

**Special precautions for user** : Multi-modal shipping descriptions are provided for informational purposes and do not consider container sizes. The presence of a shipping description for a particular mode of transport (sea, air, etc.), does not indicate that the product is packaged suitably for that mode of transport. All packaging must be reviewed for suitability prior to shipment, and compliance with the applicable regulations is the sole responsibility of the person offering the product for transport. People loading and unloading dangerous goods must be trained on all of the risks deriving from the substances and on all actions in case of emergency situations. Not available.

**Transport in bulk according to IMO instruments**

**Proper shipping name** : Not available.

## Section 15. Regulatory information

**TSCA 5(a)2 proposed significant new use rules:** 1-Methyl-2-Pyrrolidone

### SARA 313

SARA 313 (40 CFR 372.45) supplier notification can be found on the Environmental Data Sheet.

### California Prop. 65

**WARNING:** This product contains chemicals known to the State of California to cause cancer and birth defects or other reproductive harm.

### International regulations

#### **International lists**

**Australia inventory (AIIC):** Not determined.  
**China inventory (IECSC):** Not determined.  
**Japan inventory (CSCL):** Not determined.  
**Japan inventory (ISHL):** Not determined.  
**Korea inventory (KECI):** Not determined.  
**New Zealand Inventory of Chemicals (NZIoC):** Not determined.  
**Philippines inventory (PICCS):** Not determined.  
**Taiwan Chemical Substances Inventory (TCSI):** Not determined.  
**Thailand inventory:** Not determined.  
**Turkey inventory:** Not determined.  
**Vietnam inventory:** Not determined.

## Section 16. Other information

### Hazardous Material Information System (U.S.A.)

<b>Health</b>	*	2
<b>Flammability</b>		3
<b>Physical hazards</b>		0

The customer is responsible for determining the PPE code for this material. For more information on HMIS® Personal Protective Equipment (PPE) codes, consult the HMIS® Implementation Manual.

**Caution:** HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks. Although HMIS® ratings and the associated label are not required on SDSs or products leaving a facility under 29 CFR 1910.1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered trademark and service mark of the American Coatings Association, Inc. [Procedure used to derive the classification](#)

## Section 16. Other information

Classification	Justification
FLAMMABLE LIQUIDS - Category 2	On basis of test data
SKIN CORROSION/IRRITATION - Category 2	Calculation method
SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 2A	Calculation method
SKIN SENSITIZATION - Category 1	Calculation method
CARCINOGENICITY - Category 2	Calculation method
TOXIC TO REPRODUCTION - Category 2	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3	Calculation method
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 2	Calculation method

**History**

**Date of printing** : 7/28/2022

**Date of issue/Date of revision** : 7/28/2022

**Date of previous issue** : No previous validation

**Version** : 1

**Key to abbreviations** : ATE = Acute Toxicity Estimate

BCF = Bioconcentration Factor

GHS = Globally Harmonized System of Classification and Labelling of Chemicals

IATA = International Air Transport Association

IBC = Intermediate Bulk Container

IMDG = International Maritime Dangerous Goods

LogPow = logarithm of the octanol/water partition coefficient

MARPOL = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)

N/A = Not available

SGG = Segregation Group

UN = United Nations

 Indicates information that has changed from previously issued version.

**Notice to reader**

It is recommended that each customer or recipient of this Safety Data Sheet (SDS) study it carefully and consult resources, as necessary or appropriate, to become aware of and understand the data contained in this SDS and any hazards associated with the product. This information is provided in good faith and believed to be accurate as of the effective date herein. However, no warranty, express or implied, is given. The information presented here applies only to the product as shipped. The addition of any material can change the composition, hazards and risks of the product. Products shall not be repackaged, modified, or tinted except as specifically instructed by the manufacturer, including but not limited to the incorporation of products not specified by the manufacturer, or the use or addition of products in proportions not specified by the manufacturer. Regulatory requirements are subject to change and may differ between various locations and jurisdictions. The customer/buyer/user is responsible to ensure that his activities comply with all country, federal, state, provincial or local laws. The conditions for use of the product are not under the control of the manufacturer; the customer/buyer/user is responsible to determine the conditions necessary for the safe use of this product. The customer/buyer/user should not use the product for any purpose other than the purpose shown in the applicable section of this SDS without first referring to the supplier and obtaining written handling instructions. Due to the proliferation of sources for information such as manufacturer-specific SDS, the manufacturer cannot be responsible for SDSs obtained from any other source.

